

CORRES. CONTROL
INCOMING LTR NO.


00266 RF 99

DUE DATE
ACTION

DIST.	LTR	ENC
BENSUSSEN, S.J.		
BOGENBERGER, V.		
BORMOLINI, A.M.		
BRAILSFORD, M.D.		
BURDGE, L.		
CARD, R.G.		
COSGROVE, M.M.		
COX, C.M.		
CRAWFORD, A.C.		
DEJONG, V.J.		
DERBY, S.		
DIETERLE, S.E.		
FERRERA, D.W.		
FERRERA, K.P.		
FULTON, J.C.		
GERMAIN, A.I.		
HARDING, W.A.		
HARROUN, W.P.		
HEDAHL, T.G.		
HILL, J.A.		
LEONARD, R.C.		
LEWIS, M.R.		
MARTINEZ, L.A.		
NORTH, K.		
PARKER, A.M.		
PHILLIPS, F.J.	X	
POLSTON, S.		
RODGERS, A.D.		
SHELTON, D.C.	X	X
TUOR, N.R.		
VOORHEIS, G.M.		
Brooks, Z	X	X
Ayerton, C	X	X
Corsi, J	X	X


COR. CONTROL	X	X
ADMN. RECORD	X	X
PATS/T130G		

Reviewed for Addressee
Corres. Control RFP

3/11/99 
Date By

Ref Ltr. #

DOE ORDER #



Colorado Department
of Public Health
and Environment

MAR 09 1999



99-DOE-03541

Dear Stakeholder:

The Rocky Flats Cleanup Agreement (RFCA) has been updated in 1998 in accordance with its provisions. The Colorado Department of Public Health and Environment (CDPHE), the Environmental Protection Agency, Region VIII (EPA), and the Department of Energy (DOE) signed the final RFCA on July 19, 1996. On April 16, 1997, CDPHE, EPA, and DOE released substitute pages reflecting errata, modifications, and updates. Today, CDPHE, EPA, and DOE are releasing substitute update pages reflecting the 1998 updates and are providing a status update on other RFCA mandated activities.

The following Attachments and Appendices were updated in 1998:

- Attachment 4, Environmental Restoration (ER) Ranking, has been updated to reflect the current methodology used to rank Individual Hazardous Substance Sites and to provide the fiscal year 1998 ER ranking.
- Attachment 8 has been updated to reflect enforceable milestones for fiscal years 1999, 2000, and certain outyear milestones.
- Attachment 12 has been updated to reflect the approved decision documents.
- Appendix 3 has been updated to reflect the 1998 Implementation Guidance Document (IGD).
- Appendix 4 has been updated to provide the current Rocky Flats Closure Project Completion Metrics Baseline, which is in place of the Summary Level Baseline.
- Appendix 6 has been updated to reflect target activities for fiscal years 1999, 2000, 2001 and 2002.

The attachment to this letter provides substitute update pages dated February 26, 1999. The update pages should be inserted in the July 19, 1996, RFCA in lieu of the corresponding pages dated either July 19, 1996, or April 16, 1997. The July 19, 1996, version of RFCA, with replacement pages dated April 16, 1997, the 1998 IGD, and replacement pages dated February 26, 1999, shall constitute the official version of RFCA. Changes have been made in a manner to ensure continuity of text between the preceding page, the corrected page, and the subsequent page.

In addition, the following RFCA required documents were updated in 1998:

- ◆ Integrated Monitoring Plan;
- ◆ Integrated Public Involvement Plan;
- ◆ Administrative Record; and
- ◆ Historical Release Report.

MAR 1999

Best Available Copy

ADMIN RECCRD

SW-SW-A-003137

1/306


MAR 09 1999

Please contact either a RFCA Project Coordinator or an Agency Community Relations representative if you would like a copy of any of these documents.


The CDPHE, EPA, and DOE assessed the implementation of RFCA in 1998, including a review of the substantive and procedural requirements of RFCA. Upon reviewing the 1998 assessment, CDPHE, EPA, and DOE have agreed that the substantive and procedural requirements of RFCA are being met, and no changes are contemplated at this time.

If you have any questions, please contact any one of us.


Sincerely,



Joseph A. Legare
Assistant Manager
for Environment and Infrastructure
U.S. Department of Energy
Rocky Flats Field Office
(303) 966-5918 (phone)
(303) 966-2995 (fax)



Tim Rehder
Rocky Flats Project Manager
U.S. Environmental Protection Agency, Region VIII
(303) 312-6293 (phone)
(303) 312-6067 (fax)



Steve Gunderson
RFCA Project Coordinator
Colorado Department of Public Health and Environment
(303) 692-3367 (phone)
(303) 759-5355 (fax)

Enclosure



Stakeholder
99-DOE-03541

3

MAR 09 1999

cc w Enclosure:

D. Young, Office of Congressman Tom Udall
P. Jacobson, Office of Senator Wayne Allard
J. Swartout, State of Colorado Policy Office
C. Lyons, City of Arvada
K. Schnoor, City of Broomfield
T. Holeman, City of Broomfield
H. Stovall, Broomfield City Council
L. Morzel, City of Boulder
Rocky Flats Coalition of Local Governments
J. Kinsinger, Rocky Flats Citizens Advisory Board
P. Elofson-Gardine, Environmental Information Network
M. Harlow, City of Westminster
A. Rampertaap, EM-45, HQ
M. Anderson, OOC, RFFO
R. DiSalvo, OCC, RFFO
S. Bell, OCC, RFFO
D. Shelton, K-H
L. Brooks, K-H
C. Dayton, K-H
J. Corsi, K-H
Administrative Record

FY00 (cont.)

M5	Ship a minimum of 1700 cubic meters of Low Level Waste between 9/30/99 and 9/30/00.
M6	Ship 1340 cubic meters of TRU/TRM to WIPP from 10/1/99 to 9/30/00.

Outyear Milestones

M1	Initiate 903 Pad remediation by 6/1/01
M2	Complete off-site shipments of TRU/TRM by 2006..
M3	Complete D&D of Building 707 by 2005.
M4	Complete remediation of 903 Pad and off-site disposal of remediation wastes by 9/30/03.

RFCA Documents Index

1. Quality Assurance Criteria Document, Rev. 1, Kaiser-Hill Company L.L.C., effective February 2, 1996 (Or most current version).
2. Historical Release Report for the Rocky Flats Plant, Volumes I and II, U.S. Department of Energy, June 1992.
3. Existing ER Standard Operating Procedures.
4. Rocky Flats Site-wide Integrated Public Involvement Plan, U.S. Department of Energy, March 1998.
5. Treatability Study Workplans listed in the Administrative Record.
6. Health and Safety Practices, EG&G Rocky Flats, Inc., (Adopted by Kaiser-Hill Company, L.L.C. in July 1995) September 30, 1995 (Or most current version).
7. Plan for Prevention of Contaminant Dispersion, U.S. Department of Energy, February 1992.
8. Background Geochemical Characterization Report Rocky Flats Plant, U.S. Department of Energy, September 30, 1993.
9. Final Treatability Studies Plan, Volumes I and II, U.S. Department of Energy, August 1991.
10. Final resolutions of previous disputes that are relevant to implementation of RFCA. The Administrative Record shall be reviewed for such resolutions, and this list will be updated accordingly.
11. Department of Energy, Rocky Flats Environmental Technology Site, Integrated Monitoring Plan FY98/FY99, October 1998.
12. Department of Energy, Decommissioning Program Plan, Rocky Flats Environmental Technology Site, Golden, Colorado, October 8, 1998. Approved by CDPHE on November 4, 1998. Approved by EPA on November 12, 1998.
13. Department of Energy, Modification to the Decommissioning Program Plan, Rocky Flats Environmental Technology Site, December 22, 1998.

PAMs

1. Department of Energy, Proposed Action Memorandum Hotspot Removal Rocky Flats Plant Operable Unit 1, Rocky Flats Plant, Golden, Colorado, September 1994.
2. Department of Energy, Final Proposed Action Memorandum Remediation of Polychlorinated Biphenyls, Rocky Flats Environmental Technology Site, Golden, Colorado, May 1995.

3. Department of Energy, Modified Proposed Action Memorandum Passive Seep Collection and Treatment Operable Unit 7, Rocky Flats Environmental Technology Site, Golden, Colorado, July 1995.
4. Department of Energy, Modified Proposed Action Memorandum Passive Seep Collection and Treatment Operable Unit 7, minor modification, July 1998.
5. Department of Energy, Final Proposed Action Memorandum for the Remediation of Individual Hazardous Substance Site 109, Ryan's Pit, Rocky Flats Environmental Technology Site, Golden, Colorado, August 24, 1995.
6. Department of Energy, Final Proposed Action Memorandum Remediation and Draft Modification of Colorado Hazardous Waste Corrective Action Section of the Operating Permit for Rocky Flats Environmental Technology Site, Golden, Colorado, October 1995.
7. Department of Energy, Draft Proposed Action Memorandum Remediation for the Contaminant Stabilization of Underground Storage Tanks, Rocky Flats Environmental Technology Site, Golden, Colorado, February 14, 1996.
8. Department of Energy, Proposed Action Memorandum for the Source Removal at Trenches T-3 and T-4 IHSSs 110 and 111.1, Rocky Flats Environmental Technology Site, Golden, Colorado, August 24, 1995.
9. Department of Energy, Final Proposed Action Memorandum for the Source Removal at the Mound Site, IHSS 113, Revision 0, Rocky Flats Environmental Technology Site, Golden, Colorado, February 3, 1997. Approved by EPA in February 1997.
10. Department of Energy, Final Proposed Action Memorandum for the Source Removal at Trench 1, IHSS 108, Rocky Flats Environmental Technology Site, Golden, Colorado, July 1997. Approved by EPA on August 27, 1997.
11. Department of Energy, Final Proposed Action Memorandum for the Source Removal at Trench 1, IHSS 108, modification, February 1998. EPA approved the modification in March 1998.
12. Department of Energy, Building 123, Proposed Action Memorandum, Rocky Flats Environmental Technology Site, Golden, Colorado, August 1997. Approved by CDPHE on August 25, 1997.
13. Department of Energy, Building 123 Proposed Action Memorandum, minor modification, May 21, 1998.
14. Department of Energy, Building 980 Cluster, Proposed Action Memorandum, Revision 0, Rocky Flats Environmental Technology Site, Golden, Colorado, August 1997. Approved by CDPHE on August 25, 1997.
15. Department of Energy, Final Proposed Action Memorandum for the East Trenches Plume, Rocky Flats Environmental Technology Site, Golden, Colorado, February 4, 1999. Approved by EPA in February 1999.

IM/IRAs and Decommissioning Operation Plans

1. Department of Energy, Final Interim Measures/Interim Remedial Action Decision Document for Rocky Flats Industrial Area, Rocky Flats Environmental Technology Site, Golden, Colorado, November 1994.
2. Department of Energy, Operable Unit 4 Solar Evaporation Ponds Interim Measures/Interim Remedial Action Environmental Assessment Decision Document, Rocky Flats Environmental Technology Site, Golden, Colorado, April 9, 1992.
3. Department of Energy, Interim Measures/Interim Remedial Action Plan and Decision Document, 881 Hillside Area, Operable Unit No. 1, Rocky Flats Plant, Golden, Colorado, January 1990.
4. Department of Energy, Final Surface Water Interim Measures/Interim Remedial Action Plan/Environmental Assessment and Decision Document South Walnut Creek Basin, Rocky Flats Plant, Golden, Colorado, October 1994.

NOTE: The last two IM/IRA references (January 1990 IM/IRA and the October 1994 IM/IRA) were administratively combined in 1995.

5. Department of Energy, Modification to the Final Surface Water Interim Remedial Action Plan Environmental Assessment and Decision Document South Walnut Creek Basin dated October 1994. Approved by EPA on July 11, 1997.
6. Department of Energy, Modification to the Interim Measures/Interim Remedial Action Plan and Decision Document, 881 Hillside Area Operable Unit No. 1, dated January 1990. Conditionally Approved by EPA on August 27, 1997.
7. Department of Energy, Final Mound Site Plume Decision Document, Major Modification to the Final Surface Water Interim Measures/Interim Remedial Action Plan/ Environmental Assessment and Decision Document for South Walnut Creek March 1991, Revised October 1994, Rocky Flats Environmental Technology Site, Golden, Colorado, September 30, 1997. Approved by EPA in September 1997.
8. Department of Energy, Termination of the Final Surface Water Interim Remedial Action Plan Environmental Assessment and Decision Document South Walnut Creek Basin dated October 1994, July 28, 1998.
9. Department of Energy, Interim Measure/Interim Remedial Action Decision Document, National Conversion Pilot Project, Stage II, Rocky Flats Field Office, Golden, Colorado, March 30, 1995.

NOTE: Although this IM/IRA is regulated under RFCA, the IM/IRA provides that the activities conducted under the IM/IRA shall not become regulatory milestones. Further, the National Conversion Pilot Project work is funded in accordance with a Cooperative Assistance Agreement, and not through normal RFETS budget planning. The work being done under this IM/IRA will cease upon expiration of the funds provided under the Cooperative Assistance Agreement for Stage II. The IM/IRA work is not included in the Integrated Site-wide Baseline.

10. Corrective Action Management Unit Interim Measure/Interim Remedial Action Decision Document and Application Support Document for Containerized Storage at the Rocky Flats Environmental Technology Site, Golden, Colorado, Final, August 1997. Approved by CDPHE on August 28, 1997.

11. Corrective Action Management Unit Interim Measure/Interim Remedial Action Decision Document and Application Support Document for Bulk Storage at the Rocky Flats Environmental Technology Site, Golden, Colorado, Final, August 1997. Approved by CDPHE on August 28, 1997.
12. Department of Energy, Decommissioning Operations Plan for the 779 Cluster Interim Measure/Interim Remedial Action, Rocky Flats Environmental Technology Site, Golden, Colorado, February 1998. Approved by CDPHE on February 6, 1998.
13. Department of Energy, Decommissioning Operations Plan, for the 779 Cluster Interim Measure/Interim Remedial Action, modification, June 2, 1998. *(At the time the modification was requested, CDPHE verbally agreed with the modification; written approval is being sought to complete the record.)*
14. Department of Energy, Decommissioning Operations Plan for the Building 779 Cluster, modification, October 12, 1998. The modification included the demolition plan for Building 729. The modification was approved by CDPHE on November 13, 1998.
15. Department of Energy, Decommissioning Operations Plan for the Building 779 Cluster, modification, February 16, 1999. *(This modification had not been approved by CDPHE as of February 26, 1999.)*
16. Department of Energy, Building 886 Cluster Closure Project Interim Measure/Interim Remedial Action, Rocky Flats Environmental Technology Site, Golden, Colorado, July 30, 1998. Approved by CDPHE on August 3, 1998.
17. Department of Energy, Building 771/774 Closure Project Decommissioning Operations Plan, Rocky Flats Environmental Technology Site, Golden, Colorado, December 1998. Approved by CDPHE on January 11, 1999.

CAD/RODs

1. Department of Energy, Corrective Action Decision/Record of Decision, Operable Unit 11: West Spray Field, Rocky Flats Environmental Technology Site, Golden, Colorado, September 1995, Approved October 1995.
2. Department of Energy, Corrective Action Decision/Record of Decision, Operable Unit 15: Inside Building Closures, Rocky Flats Environmental Technology Site, Golden, Colorado, September 1995, Approved October 1995.
3. Department of Energy, Corrective Action Decision/Record of Decision, Operable Unit 16: Low Priorities Sites, Rocky Flats Environmental Technology Site, Golden, Colorado, August 1994, Approved October 1994.
4. Department of Energy, Corrective Action Decision/Record of Decision, Operable Unit 1, Rocky Flats Environmental Technology Site, Golden, Colorado, March 1997. Approved March 1997.
5. Department of Energy, Corrective Action Decision/Record of Decision, Operable Unit 3, Rocky Flats Environmental Technology Site, Golden, Colorado, April 1997. Approved June 1997.

A Working Group
Product of

CDPHE
DOE RFFO
EPA
Kaiser-Hill
RMRS

Rocky Flats Cleanup Agreement, Appendix 3

RFCA Implementation Guidance Document

Final



July 1998

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION	1-1
1.1 Scope and Purpose of Rocky Flats Cleanup Agreement and Implementation Guidance Document.....	1-1
1.2 Organizational and Functional Responsibilities	1-2
1.2.1 CDPHE Internal Organization and Project Coordinators	1-3
1.2.2 DOE Internal Organization and Project Coordinators	1-3
1.2.3 EPA Internal Organization and Project Coordinators	1-4
1.3 Enforceability of RFCA, Attachments, Appendices, and IGD	1-4
1.4 Overview of the IGD	1-4
2.0 PROJECT SCOPING AND REGULATORY INTEGRATION	2-1
2.1 Outline for Project Scoping	2-1
2.2 Scoping Process	2-2
2.3 Identification of Scope and Authorities	2-3
2.4 Decisionmaking Under RFCA.....	2-4
2.5 Framework for Project Scoping	2-5
2.6 Authorities and Scope External to RFCA	2-7
2.6.1 Waste Management	2-7
2.6.2 Water	2-9
2.6.3 National Environmental Policy Act.....	2-11
2.6.4 Air	2-12
2.6.5 Ecological Concerns	2-13
2.6.6 Health and Safety	2-14

3.0	TECHNICAL APPROACH AND PROCEDURES.....	3-1
3.1	Environmental Restoration Process and Documents.....	3-1
3.1.1	Interim Measure/Interim Remedial Action Decision Documents	3-4
3.1.2	Proposed Action Memorandum.....	3-6
3.1.3	Emergency Removal Actions.....	3-8
3.1.4	No Further Action Decisions.....	3-10
3.1.5	Proposed Plans and Corrective Action Decision/Record of Decision.....	3-13
3.1.6	RFCA Standard Operating Protocols.....	3-15
3.1.7	RCRA Facility Investigation/Remedial Investigation Process....	3-15
3.1.8	Sampling and Analysis Plans and Data Quality Objectives.....	3-17
3.1.9	Corrective Measures Study/Feasibility Study.....	3-18
3.1.10	Technical Memoranda.....	3-19
3.1.11	RCRA Closure.....	3-20
3.1.12	Closeout Reports.....	3-22
3.1.13	Project Cost Summary.....	3-22
3.2	Decontamination and Decommissioning	3-23
3.3	Transition Process from Decontamination and Decommissioning to Environmental Restoration.....	3-24
3.4	Data Management and Quality Assurance/Quality Control.....	3-24
3.5	ARARs and RFCA Permit Waiver	3-25
3.5.1	ARARs List	3-25
3.5.2	Project-Specific ARARs Analysis	3-26
3.5.3	Exemption from Administrative Requirements of ARARs.....	3-26
3.5.4	RFCA Permit Waiver.....	3-26
3.6	Risk Evaluation	3-27
3.6.1	Implementation of Risk Assessment Methodologies Within the RFCA Framework.....	3-28
3.6.2	Environmental Restoration Ranking.....	3-28
3.6.3	Comprehensive Risk Assessment.....	3-29
3.6.4	Radiological Dose Evaluations.....	3-30
3.6.5	Cumulative Effects Between Dose and Risk.....	3-30

3.7	The Action Levels and Standards Framework.....	3-30
3.7.1	Background	3-30
3.7.2	Application of the Action Levels to Trigger Interim Actions.....	3-31
3.7.3	Performance Objectives	3-35
3.8	Annual Reviews and Updates	3-36
3.8.1	Annual Updates of the Environmental Restoration Ranking.....	3-36
3.8.2	Annual Updates for the Historical Release Report.....	3-36
3.8.3	RFCA Annual Review.....	3-37
3.8.4	RFCA Biennial Review	3-38
3.9	Disputes.....	3-39
3.9.1	Disputes Regarding Decisions by the Lead Regulatory Agencies	3-40
3.9.2	Disputes Regarding Additional Work Required Under CERCLA	3-40
3.9.3	Disputes Regarding Budget and Work Planning.....	3-40
3.9.4	EPA-State Disputes Regarding Site-wide Issues.....	3-43
3.9.5	Disputes Regarding Overall Direction of Proposed Work.....	3-43
3.10	Modification of Decision Documents.....	3-43
3.10.1	Major Modifications.....	3-43
3.10.2	Minor Modifications.....	3-45
3.10.3	Field Modifications.....	3-46
3.11	NPL Delisting.....	3-46
3.12	Soil Management (reserved).....	3-46
3.13	Water Management.....	3-46
3.14	Integrated Monitoring Plan.....	3-47
3.14.1	Surface Water Monitoring.....	3-48
3.14.2	Ground Water Monitoring.....	3-48
3.14.3	Air Quality Monitoring	3-48
3.14.4	Ecological Monitoring.....	3-48

4.0	ADMINISTRATION	4-1
4.1	Budget Planning and Execution	4-1
4.1.1	Executive Formulation and Transmittal	4-1
4.1.2	Congressional Action	4-4
4.1.3	Budget Execution and Control	4-4
4.2	Project Planning and Budget Process	4-4
4.2.1	Project Planning/Project Scoping	4-5
4.3	Regulator Interaction in the Budget and Planning Process	4-7
4.3.1	FY Activities	4-7
4.3.2	FY+1 Activities	4-9
4.3.3	FY+2 Activities.....	4-9
4.3.4	Roles and Responsibilities	4-12
4.3.5	Cost Savings Initiatives and Productivity Improvements	4-12
4.4	Administrative Record/Records Management/Document Control	4-12
4.4.1	Administrative Record	4-12
4.4.2	Records Management	4-14
4.4.3	Document Control	4-14
4.5	Reporting	4-14
5.0	PUBLIC INVOLVEMENT AND STAKEHOLDER SUPPORT	5-1
5.1	Background	5-1
5.2	Public Involvement Objectives.....	5-1
5.3	Public Involvement Tools.....	5-2
5.4	Public Involvement Tools	5-3
6.0	REFERENCES	6-1

APPENDICES

Appendix A	Framework for Project Scoping
Appendix B	RFETS Environmental Checklist
Appendix C	Preparation of an Interim Measure/Interim Remedial Action
Appendix D	Preparation of a Proposed Action Memorandum Document
Appendix E	No Further Action Development Schedule
Appendix F	Proposed Plan and CAD/ROD Schedule
Appendix G	Generic RCRA Facility Investigation/Remedial Investigation Schedule
Appendix H	Corrective Measures Study/Feasibility Study Preparation
Appendix I	Outline of Sampling and Analysis Plan
Appendix J	Master List of Potential ARARs
Appendix K	Summary of Risk Assessment Methodology for RFETS
Appendix L	Action Levels for Radionuclides in Soils
Appendix M	Process Description for Evaluating Groundwater Impacts to Surface Water and Ecological Resources
Appendix N	Methodology for Updated Environmental Restoration Ranking
Appendix O	Example of Historical Release Report Update
Appendix P	Programmatic Preliminary Remediation Goals Tables
Appendix Q	Environmental Data Management

FIGURES

<u>Figure</u>	<u>Page</u>
2-1 Primary Oversight and Facility Disposition Flow	2-5
3-1 Environmental Restoration Process Flow	3-2
3-2 Interim Measures/Interim Remedial Action Process	3-5
3-3 Proposed Action Memorandum Process	3-8
3-4 Emergency Removal Action	3-10
3-5 Decision Points for NFA Recommendations	3-12
3-6 RCRA Facility Investigation/Remedial Investigation Process.....	3-17
3-7 Facility Disposition Process	3-21
3-8 Application of Groundwater Action Levels Through the Integrated Monitoring Plan	3-33
3-9 Evaluation Options After Data Point Comparison	3-35
3-10 Disputes Regarding Decisions by the Lead Regulatory Agency	3-40
3-11 Disputes Regarding Budget and Work Planning	3-41
3-12 EPA/CDPHE Disputes Regarding Sitewide Issues	3-43
4-1 General Timeline for Budget, ISB, RFCA Milestones and K-H Performance Measures.....	4-2
4-2 The Federal (DOE) Budget and Planning Execution Process	4-3

ACRONYMS

AFP	Approved Funding Program
APO	Analytical Project Office
ALARA	As Low As Reasonably Achievable
ALF	RFCA Action Levels and Standards Framework for Surface Water, Groundwater, and Soils
ANSI/ASQC	American National Standards Institute/American Society for Quality Control
AOC	Area of Concern
APEN	Air Pollution Emission Notices
AR	Administrative Record
ARAR	Applicable or Relevant and Appropriate Requirement
ASD	Analytical Services Division
AST	Analytical Services Toolkit
ASTM	American Society of Testing and Materials
BRA	Baseline Risk Assessment
CAA	Clean Air Act and Amendments
CAB	Citizens Advisory Board
CAD/ROD	Corrective Action Decision/Record of Decision
CAPCD	Colorado Air Pollution Control Division
CAMU	Corrective Action Management Unit
CDPHE	Colorado Department of Public Health and Environment
CDD	Closure Description Document
CEARP	Comprehensive Environmental Analysis and Response Program
C/ED	DOE Office of Communication and Economic Development
CERCLA	Comprehensive Environmental Response, Compensation and Liability Act
CHWA	Colorado Hazardous Waste Act
CMS/FS	Corrective Measure Study/Feasibility Study
COC	Chemical of Concern
CPB	Closure Project Baseline
CPS	Closure Project Schedule
CR	Continuing Resolution
CRA	Comprehensive Sitewide Risk Assessment
CWA	Clean Water Act
CWQCC	Colorado Water Quality Control Commission
CWTF	Consolidated Water Treatment Facility
D&D	Decontamination and Decommissioning
DMP	Data Management Plan
DNFSB	Defense Nuclear Facilities Safety Board
DOE	Department of Energy
DOP	Decommissioning Operations Plan
DPP	Decommissioning Program Plan
DQO	Data Quality Objective
DRC	Dispute Resolution Committee
EDD	Electronic Data Deliverable

EDDIE	Environmental Data Dynamic Information Exchange
EE/CA	Engineering Evaluation/Cost Assessment
EPA	Environmental Protection Agency
ER	Environmental Restoration
ERA	Ecological Risk Assessment
ERAM	Ecological Risk Assessment Methodology
FFCA	Federal Facility Compliance Act
FIP	Field Implementation Plan
FSP	Field Sampling Plan
FY	Fiscal Year
GRA	General Response Actions
HA	Hazard Analysis
HASP	Health and Safety Plan
HHRAM	Human Health Risk Assessment Methodology
HPGe	High Purity Germanium
HQ	DOE Headquarters
HRR	Historical Release Report
HWIR	Hazardous Waste Identification Rule
IAg	Interagency Agreement
IA IM/IRA	Industrial Area Interim Measures/Interim Remedial Action Decision Document
IDM	Investigative Derived Materials
IGD	Implementation Guidance Document
IHSS	Individual Hazardous Substance Site
IM/IRA	Interim Measure/Interim Remedial Action
IMP	Integrated Monitoring Plan
INV	Needs Further Investigation
ISB	Integrated Site-wide Baseline
ISEDS	Integrated Site-wide Environmental Data Systems
ISM	Integrated Safety Management
IWMP	Integrated Water Management Plan
LDR	Land Disposal Restrictions
LRA	Lead Regulatory Agency
M2SD	Mean Plus Two Standard Deviations
MAL	Master Activity List
MBTA	Migratory Bird Treaty Act
MCL	Maximum Contaminant Level
MCS	Management Control System
NCP	National Contingency Plan
NEPA	National Environmental Policy Act
NESHAP	National Emissions Standards for Hazardous Air Pollutants
NFA	No Action/No Further Action/No Further Remedial Action
NLR	No Longer Representative
NPDES	National Pollutant Discharge Elimination System
NPL	National Priorities List

NRMP	Natural Resources Management Policy
OC	Office of Communication
OMB	Office of Management and Budget
OSHA	Occupational Safety and Health Act
OU	Operable Unit
PAC	Potential Area of Concern
PAM	Proposed Action Memorandum
PARCC	Precision, Accuracy, Representatives, Completeness, Comparability
PBD	Project Baseline Description
PCB	Polychlorinated Biphenyl
PCOC	Potential Chemicals of Concern
PEG	Program Execution Guidance
POC	Points of Compliance
PP	Proposed Plan
PP/CAD/ROD	Proposed Plan/Corrective Action Decision/Record of Decision
PPE	Personal Protective Equipment
PPRG	Programmatic Preliminary Remediation Goal
QA	Quality Assurance
QA/QC	Quality Assurance/Quality Control
QAPjP	Quality Assurance Project Plan
QC	Quality Control
RBC	Risk-Based Concentration
RCRA	Resource Conservation and Recovery Act
RFCA	Rocky Flats Cleanup Agreement
RFEDS	Rocky Flats Environmental Data System
RFETS	Rocky Flats Environmental Technology Site
FFFO	Rocky Flats Field Office
RFI/RI	RCRA Facility Investigation/Remedial Investigation
RFSIPI	Rocky Flats Site-wide Integrated Public Involvement Plan
RI/FS	Remedial Investigation/Feasibility Study
RPD	Relative Percent Difference
RPO	Representative Process Options
RSOP	RFCA Standard Operating Protocols
SAFER	Streamlined Approach for Environmental Restoration
SAP	Sampling and Analysis Plan
SCCB	Site Change Control Board
SEC	Senior Executive Committee
SEDRC	State-EPA Dispute Resolution Committee
SESEC	State-EPA Senior Executive Committee
SNM	Special Nuclear Material
SRA	Support Regulatory Agency
STARR	Site Technical Administrative Record Review
SWD	Soil and Water Database
TM	Technical Memorandum
TRU	Transuranic

1.0 INTRODUCTION

1.1 SCOPE AND PURPOSE OF ROCKY FLATS CLEANUP AGREEMENT AND IMPLEMENTATION GUIDANCE DOCUMENT

The Rocky Flats Cleanup Agreement (RFCA) describes the regulatory framework for performing Environmental Restoration (ER) and decommissioning activities at the Rocky Flats Environmental Technology Site (RFETS or Site). RFCA replaces the 1991 Interagency Agreement (IAG) (DOE, 1991). RFCA parties include the Department of Energy (DOE), the Environmental Protection Agency Region VIII (EPA), and the Colorado Department of Public Health and Environment (CDPHE). The RFCA requires the preparation of an Implementation Guidance Document (IGD). (See RFCA ¶78). The IGD is a tool that the RFCA parties will use to guide the planning, decisionmaking, and implementation of ER and decommissioning at the RFETS.

Consistent with RFCA ¶25aj, the IGD includes information on:

- Technical approach
- Content of specific decision documents
- Implementation of accelerated actions and decommissioning
- Risk assessment

The intended purposes of the IGD are to:

- Provide a "roadmap" for project managers
- Promote the understanding and compliance of non-RFCA authorities
- Standardize and expedite the planning and execution of work
- Provide additional interpretation/clarification of RFCA
- Illustrate the procedures for work prioritization and budgeting

Project management must address a variety of RFCA topics during the planning and execution of work. The IGD is intended to organize RFCA subject matter in a manner that highlights relevant language that may be widely distributed throughout RFCA text. In this way, the IGD acts as a roadmap that provides access to relevant RFCA language.

While RFCA is a broad regulatory agreement that will be the primary authority for decommissioning and ER, other independent regulatory authorities must also be considered and addressed. As such, an additional purpose of the IGD is to identify regulatory authorities external to RFCA, to promote their consideration, and to ensure that these external authorities are addressed.

The IGD provides sample schedules, sample tables of contents, and other discussion materials to standardize work planning and execution. Although the IGD is not enforceable, a commitment by the parties to accomplish work within the schedules provided will make

parties accountable and expedite work. In addition, without a clear commitment from the parties to honor the scheduling developed during project scoping, it will be difficult to establish meaningful budgets that optimize funding.

Many complex technical and regulatory issues are within the scope of RFCA. It is impossible to craft a legal agreement that will, without interpretation, provide unambiguous language that covers every instance. For this reason, in some circumstances, the IGD will provide clarification to RFCA. The IGD will be particularly useful when procedural nuances have not been explicitly addressed; the IGD consensus process will determine appropriate terms under which the planning and execution of work will be accomplished on a project-specific basis.

Finally, the IGD provides illustrations to aid understanding of the work prioritization and budgeting process. This multi-step process represents a cooperative risk management exercise that is a vital element in the process to move RFETS through the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA); Resource Conservation and Recovery Act (RCRA); and Colorado Hazardous Waste Act (CHWA) process to closure.

1.2 ORGANIZATIONAL AND FUNCTIONAL RESPONSIBILITIES

One purpose of RFCA is to integrate CERCLA, RCRA, and CHWA regulatory authorities in a manner that minimizes conflict and expedites action. To that end, a stated objective of the IGD is to employ the same basic approach regardless of whether the work is related to the Industrial Area or the Buffer Zone. (See RFCA ¶78). RFCA also seeks to eliminate unnecessary tasks, duplicate reviews and to minimize the impact of overlapping statutory authorities. (See RFCA ¶251 and ¶250).

RFCA provides for a Lead Regulatory Agency (LRA) and Support Regulatory Agency (SRA) and prescribes the responsibilities of each. In ¶25a, RFCA defines the LRA as:

...that regulatory agency (EPA or CDPHE) which is assigned approval responsibility with respect to actions under this Agreement at a Particular Operable Unit.... In addition to its approval role, the LRA will function as the primary communication and correspondence point of contact. The LRA will coordinate technical reviews with the Support Regulatory Agency and consolidate comments, assuring technical and regulatory consistency, and assuring that all regulatory requirements are addressed.

In ¶25br, RFCA defines the SRA as:

...the regulatory agency (EPA or CDPHE) that, for purposes of streamlining implementation of this Agreement, where applicable, shall defer exercise of its regulatory authority at one or more particular OUs (Operable Unit) until the completion of all accelerated actions. The SRA may, however, provide comments to the LRA regarding proposed documents and work.

In addition, ¶57 of RFCA obligates each party to prepare a written description of its internal organization to be included in the IGD. Each party must designate one or more individuals to perform the functions of project coordinator. This designation may be changed by written notification to the other parties. Each party must also specify one or more points of contact for sending, receiving, and distributing correspondence.

The following sections provide the required description of key functional areas for each RFCA party. Updates will be incorporated on an as-needed basis.

1.2.1 CDPHE Internal Organization and Project Coordinators

Project Coordinator:	Steve Gunderson, 692-3367
Point of Contact for Document Distribution:	Michelle Cowell, 692-3349
Address:	CDPHE 4300 Cherry Creek Drive South Denver, Colorado 80246
Facsimile:	(303) 759-5355
Dispute Resolution Committee:	Howard Roitman
Senior Executive Committee:	TBD

1.2.2 DOE Internal Organization and Project Coordinators

Project Coordinator:	Regina Sarter , 966-7252 Joe Legare, 966-2282
Point of Contact for Document Distribution:	Donna Shonle, 966-7555
Address:	Rocky Flats Field Office P.O. Box 928 Golden, Colorado 80402-0928

Facsimile: 966-4728
Dispute Resolution Committee: Joe Legare
Senior Executive Committee: Jessie M. Roberson

1.2.3 EPA Internal Organization and Project Coordinators

Project Coordinator: Tim Rehder, 312-6293

Point of Contact for
Document Distribution: Tim Rehder, 312-6293

Address: 999 18th Street, Suite 500
Denver, Colorado 80202

Facsimile: 312-6067

Dispute Resolution Committee: Max Dodson
Senior Executive Committee: Jack McGraw

1.3 ENFORCEABILITY OF RFCA, ATTACHMENTS, APPENDICES, AND IGD

CHWA permits, Clean Air Act (CAA) permits, National Pollutant Discharge Elimination System (NPDES) permits, and National Environmental Policy Act (NEPA) obligations are clearly outside of RFCA jurisdiction. Regardless, the RFCA does provide mechanisms to integrate these permits with the activities that are subject to RFCA. Specifically, RFCA addresses:

- Remedial activities for Individual Hazardous Substance Sites (IHSSs)
- Decommissioning
- Federal Facility Compliance Act (FFCA) compliance for mixed wastes that are not proposed for treatment under the Site Treatment Plan
- Timely completion of milestones
- Closure of underground storage tanks

Within this realm, RFCA consists of a hierarchy of documents with distinct legal enforceability. The preamble to RFCA, the IGD, and the RFCA appendices are not enforceable, while the body of the RFCA and RFCA attachments are enforceable. Consistent with its title, the IGD is a guidance document and is not binding on DOE, CDPHE or EPA, but will be used by the parties for reviewing the adequacy of documents and work.

1.4 OVERVIEW OF THE IGD

The IGD consists of five major sections: (1) Introduction, (2) Project Scoping and Regulatory Integration, (3) Technical Approach and Procedures, (4) Administration, and (5) Public Involvement and Stakeholder Support. The Introduction discusses the scope and purpose of the IGD, the organizational and functional responsibilities of each party, and the enforceability of the IGD. The process for project scoping and the impact of RFCA on regulatory integration is discussed in Section 2. Section 3 provides technical and procedural detail related to the basic decision tools embodied in RFCA. Additionally, Section 3 discusses technical aspects of other supporting activities that are necessary components of the combined RCRA Corrective Action/CERCLA process. Examples include risk assessment and Applicable or Relevant and Appropriate Requirement (ARAR) analysis. Section 4 focuses on planning, budgeting, and administration of RFCA record keeping obligations. Processes to promote community involvement are presented in Section 5.

2.0 PROJECT SCOPING AND REGULATORY INTEGRATION

A stated goal of RFCA is to streamline the decisionmaking process. To accomplish this, RFCA clarifies each party's role in decisionmaking and the legal and regulatory authorities under which the decisions are to be made. RFCA also seeks to create procedures that combine the CERCLA, RCRA, and CHWA requirements so that activities conducted pursuant to the RFCA will satisfy CERCLA, RCRA, and the CHWA statutory requirements without duplicative paperwork.

One mechanism to promote streamlined decisionmaking is project scoping. RFCA defines scoping as:

... that period of time, from initial conceptual development of proposed work to DOE's formal request for approval to perform work on an activity, during which DOE consults with the regulators regarding the goals, methods, breadth and desired outcome for such activity. (See RFCA ¶25bk).

2.1 OUTLINE FOR PROJECT SCOPING

Project scoping offers an early opportunity for the parties to evaluate and refine technical attributes of the proposed project and to evaluate the regulatory framework, including permitting requirements, within which the project will be conducted. Additionally, project scoping is an opportunity to define how the variety of RFCA requirements and procedures will be implemented. Careful project scoping provides an opportunity to resolve many issues. The overall purpose, process, and factors for project scoping are outlined below.

Purpose and Approach

- To speed decisionmaking and cleanup through
 - Early identification of regulatory, physical, and resource barriers
 - A common understanding of goal and path
- To create a better product by using the experience and wisdom of more people

Scoping Process

- Identify players
- Provide information on proposed activity to each player
- Meet to scope the project

Factors in Scoping

- Purpose and goal of project
- Regulatory authorities
 - RFCA
 - authorities external to RFCA
- Decisionmakers
 - EPA

- CDPHE
 - DOE
 - Others
- Identify critical path events and time lines
- Integration issues
 - Waste management
 - Water management
 - Air
 - NEPA
 - Ecological concerns
 - Deactivation integration with decommissioning
 - Decommissioning integration with ER

2.2 SCOPING PROCESS

As the first step in the initiation of a RFCA activity, a scoping meeting will be held between EPA, CDPHE, and DOE to coordinate the RFCA requirements. Consistent with the RFCA, the LRA will be based upon the location at which the activity will be conducted. The purpose of the meeting is to discuss the regulatory requirements and to agree on the scope of the action and the content of the decision document. Consistent with RFCA ¶s 89 and 107, estimated agency review times for Interim Measures/Interim Remedial Actions (IM/IRAs) will be determined. This is not necessary when scoping a Proposed Action Memoranda (PAM) since RFCA is quite specific regarding review duration. Permits which may be needed or which would otherwise be required in the absence of CERCLA §121(e)(1) and the National Contingency Plan (NCP) will be identified during the meeting. At the meeting, the LRA will inform DOE of the specific performance standards to be addressed within the decision document. Performance standards are generally expected to be based on the RFCA Action Levels and Standards Framework for Surface Water, Groundwater, and Soils (ALF), ARARs, or the Building Disposition guidelines in Attachment 9 of RFCA.

During scoping, one of three permit-related actions may occur. First, if the activity is exempt from permitting DOE will: 1) identify any permit that would be required; 2) identify the standards, requirements or limitations imposed upon the response action; and 3) propose how the response action will meet the standards, requirements or limitations. (See RFCA ¶17). This process will be identical to and coincide with the identification and resolution of ARARs for the response action. Consistent with RFCA ¶18, EPA and CDPHE will provide their positions on any permit waivers in a timely manner.

Second, if permits are required for off-site activities DOE will notify and, upon request, provide CDPHE and EPA with copies of the permit applications. (See RFCA ¶20).

Third, during scoping CDPHE will determine the need for permits for any RFCA non-decommissioning activity conducted in the Industrial Area so that appropriate permit

application documentation may be packaged with the decision document for concurrent public review and approval. (See RFCA ¶103 and ¶104).

2.3 IDENTIFICATION OF SCOPE AND AUTHORITIES

CERCLA, RCRA, and CHWA are the underlying regulatory authorities for RFCA. Understandably, RFCA directly defines the limits of the CERCLA/RCRA/CHWA cleanup authorities and directly facilitates the integration of the CERCLA/RCRA/CHWA cleanup authorities where they may overlap. In the process of defining the limits of the CERCLA/RCRA/CHWA cleanup authorities embodied in RFCA, the RFCA also serves to directly and indirectly clarify the interface of the CERCLA/RCRA/CHWA cleanup authorities with other regulatory authorities that are external to RFCA.

To illustrate this point, the following two lists were prepared. The first list outlines the scope of RFCA. The second list outlines regulatory authorities that are outside the scope of RFCA but will be integrated with RFCA activities. Where RFCA gives CDPHE procedural discretion, an item will appear on both lists and will be designated as "elective."

RFCA Scope

- Decommissioning
 - Decontamination
 - Demolition
 - Dismantlement
- Environmental Restoration
 - Accelerated actions
 - Remedial action
 - Remediation waste management in Corrective Action Management Unit (CAMU)
 - Risk evaluations
 - ARARs
- Corrective Action Decision/Record of Decision (CAD/ROD)
- Modifications to decision documents
- RCRA closure
 - Permitted units (elective)
 - Interim status closure (elective)
 - Final disposition of idle equipment (elective)
- Budget planning – Closure Project Baseline (CPB)
- Administrative Record (AR)
- RFCA Dispute Resolution
- Public involvement

Scope External to RFCA

- Deactivation
- Non-hazardous radioactive waste management

- RCRA process waste management/Part B Permit
 - Waste storage
 - Treatment to meet land disposal restrictions (LDR)
 - On-site disposal (optional)
- RCRA closure
 - Permitted units (elective)
 - Interim status closure (elective)
 - Final disposition of idle equipment (elective)
- NEPA
- Air permitting and National Emission Standards for Hazardous Air Pollutants (NESHAP)
- NPDES (wastewater) and stormwater permitting
- Ecological concerns
- Natural resource damage assessment
- DOE Orders
- Toxic Substances Control Act (TSCA)

The RFCA scope and authorities are discussed in detail in Section 3.0 and associated appendices. The authorities and scope external to RFCA are discussed in Section 2.6.

2.4 DECISIONMAKING UNDER RFCA

Although the underlying CERCLA and CHWA substantive authorities held by EPA and CDPHE remain unchanged by RFCA, the assignment of lead and support roles by RFCA has significant procedural effects on decisionmaking and dispute resolution. One example is the consolidation of air permit review and public comment with the RFCA decision process for an accelerated action.

RFCA combines three administrative structures to accomplish the integration of underlying CERCLA and CHWA cleanup authorities. First, RFETS has been divided into the Industrial Area and the Buffer Zone. Second, the RFCA provides for a LRA and a SRA. The combined effect of these RFCA administrative structures is to assign the lead role to CDPHE in the Industrial Area and the lead role to EPA in the Buffer Zone. (See RFCA ¶67). The third administrative structure creates a class of "site-wide" issues. A list of site-wide documents is provided in RFCA ¶119. In contrast to the Industrial Area/Buffer Zone division of authority described above, Site-wide documents and activities are subject to joint review and approval by CDPHE and EPA. For example, the Integrated Monitoring Plan (IMP) is a Site-wide document which integrates a variety of monitoring obligations imposed under RFCA authorities and under authorities external to RFCA. The IMP summarizes Site-wide monitoring requirements for air, surface water, groundwater, and ecology.

Figure 2-1 is a simplified illustration of the RFCA's assignment of lead responsibility (primary oversight) for activities at RFETS. It should be understood that Figure 2-1

deactivation which is overseen by the Defense Nuclear Safety Board (DNFSB). Details of activities involving the DNFSB are provided in Appendix 1 of RFCA.

In addition, the figure has been simplified for clarity and may not accurately depict the relative amount of work (e.g., the amount of remediation in the Industrial Area versus the amount of remediation in the Buffer Zone) or accurately depict every jurisdictional possibility. For instance, only very limited circumstances may exist where EPA will be the lead for decommissioning conducted in the Buffer Zone. Finally, this figure shows that all activities conducted at the site are part of the CPB (formerly called the Integrated Site-wide Baseline) which is discussed in Section 4.1.

2.5 FRAMEWORK FOR PROJECT SCOPING


RFCA identifies five broad categories of activities, although deactivation is not directly subject to RFCA. Depending on the categorization of the activity and the location of the activity, specific procedures are provided in RFCA for those activities. The five major categories of activities include:

- Deactivation
- Decommissioning
- ER
- CAD/RODs
- Site-wide Treatment

For the first four categories of activities, there is potential for either a Buffer Zone or Industrial Area location, which creates a matrix of eight. This matrix of eight provides the basis for eight of the project scoping frameworks provided in Appendix A.

A ninth project scoping framework for site-wide treatment is also presented. A single project scoping framework for site-wide treatment is adequate because the joint authority is not dependent on the location of the treatment system.

In many instances, the project scoping framework reveals that some issues are not sensitive to either the type of activity or the location of the activity. In those circumstances, that portion of the framework may appear repetitive.



KEY
IA = Industrial Area
BZ = Buffer Zone

Figure 2-1 Primary Oversight and Facility Disposition Flow

2.6 AUTHORITIES AND SCOPE EXTERNAL TO RFCA

As noted earlier, a number of regulatory authorities external to RFCA need to be integrated with RFCA activities. It will be necessary to coordinate these external authorities during project scoping and during project implementation if there are any deviations from the planned action location or process on which the initial coordination was based. (See, K-H Directive, "Site Activity Environmental Assessment.") These external authorities can be critical to timely project implementation. To facilitate the coordination, RFETS has created a checklist to ensure that each internal and external authority is considered. The RFETS Environmental Checklist is included in Appendix B. Because the RFETS Environmental Checklist is revised from time to time, it is necessary to obtain the most recent version from the RFETS NEPA group.

Consideration of waste management is crucial, as the activity by nature, is waste generating. Likewise, management of wastewater from deactivation, decommissioning and ER must be addressed pursuant to appropriate permits and approvals. Air permitting or emissions notifications will also be required in many instances. Depending on the scope of the activity, varying levels of NEPA evaluations may be triggered. Ecological issues related to wildlife, plants, and wetlands may also require evaluation and mitigation. These topics are addressed in the following sections.

2.6.1 Waste Management

Waste Management activities are subject to diverse requirements external to RFCA that are dependent upon the levels of radioactivity, the types of hazards, and the management strategy employed. For that reason, the amount of waste anticipated from the activity must be evaluated so that on-site storage capacity, on-site or off-site treatment capability (as needed), and final off-site disposal options are identified. This evaluation is critical due to limited capacity for on-site storage, limited on-site and off-site treatment capabilities, restrictive waste acceptance criteria at currently licensed/permitted off-site disposal facilities, and the cost of waste management.

Two approaches will help to alleviate this situation. First, during scoping it is necessary to identify a feasible strategy for long-term waste management and to provide project-specific funding to implement the strategy. This "projectization" approach should minimize the generation of orphan wastes with no identified long-term management alternative. The waste management strategy should be sufficiently detailed to address:

- Identification and quantification of each waste stream
- Segregation and staging
- Short-term storage
- Treatment
- Sampling and packaging to meet waste acceptance criteria

- If appropriate, an existing contracting mechanism must be identified and modified or a new contract must be executed

This is not to say that long-term storage is not allowed. Instead, it obligates the project to identify and fund presently available long-term storage space or to fund and create new long-term storage space for those wastes where no other feasible management alternative is identified.

Second, CERCLA permit waivers are available to decommissioning activities, to ER activities in the Buffer Zone, and to limited ER activities in the Industrial Area. These waivers can streamline the approval of additional, protective storage capacity specifically designed to address the level of risk associated with the wastes. The basis for the waivers must be included in a submittal to CDPHE and EPA. See Section 3.5.4 for a complete discussion of permit waivers.

In addition, planning is underway to implement a CAMU for temporary waste storage as a contingency if RFETS can not meet the goals of the Site Closure Plan (currently called the Accelerating Cleanup: Focus on 2006). When completed, the CAMU may accept remediation wastes generated from RFCA decommissioning and ER activities. Process wastes that are also hazardous wastes are not within the definition of remediation wastes and will not be eligible for management in the CAMU. Similarly, some polychlorinated biphenyl (PCB) wastes (e.g., wastes generated from fluorescent light ballasts) will not be eligible for management in the CAMU. A variety of activities at the site involve disturbing and managing soils. Portions of the soil may be contaminated with hazardous or radiological constituents at varying levels. In many instances, management of the soils will be specifically addressed in a decision document or associated technical memoranda. In other situations (e.g., construction not associated with decommissioning or ER) there will be no RFCA decision document to cover the activity. In these situations, the soil should be managed in accordance with Section 3.12 of the IGD.

Wastes generated under RFCA/CERCLA authorities are subject to the CERCLA Off-site Rule. (See RFCA ¶19 and 40 CFR § 300.440). The CERCLA Off-site Rule requires a review of any off-site disposal facility used to dispose of wastes generated under CERCLA authority. The rule avoids having wastes from CERCLA authorized actions contribute to present or future environmental problems by directing these wastes to management units determined to be environmentally sound. The CERCLA Off-site Rule ensures that wastes generated under CERCLA authorities are transferred only to properly-permitted facilities that have no relevant violations or uncontrolled releases. Initial DOE requests for CERCLA Off-site Rule determinations will be accomplished as part of the RFETS procurement process. DOE must verify compliance with the off-site rule prior to waste shipment. In addition, the determination of acceptability must be updated and documented periodically. EPA will make reasonable efforts to assist DOE with timely off-site rule determinations.

For land disposal restricted (LDR) mixed wastes, treatment will be covered under the appropriate decision documents and would not be added to the RFETS Site Treatment Plan unless they would be managed in treatment systems implemented under the Site Treatment Plan or were not provided for in a decision document. The applicability of LDR treatment standards and the achievement of LDR compliance for the mixed wastes to which LDR treatment is applicable must be explicitly addressed in the appropriate decision document.

Wastes contaminated with PCBs will be generated by activities external to RFCA. As noted earlier, routinely generated, leaking fluorescent light ballasts that contain PCBs are fully regulated under TSCA and must be stored, inspected and disposed in accordance with the TSCA requirements. All PCB-containing ballasts removed during decommissioning of Type 1 buildings are also subject to TSCA regulation. Building types are described in the Decommissioning Program Plan (DPP) Section 3.2. RFETS also has two PCB-containing transformers in service. These transformers remain fully regulated by TSCA (administratively and substantively) unless and until they become subject to a decommissioning decision document.

If a decision document controlling the decommissioning of a Type 2 or Type 3 building specifically includes one or both of the transformers, management of the transformers must then be accomplished in a manner that attains the substantive attributes of the identified ARARs. Likewise, management of PCB light ballasts must also attain substantive ARARs. Full compliance with both substantive and administrative requirements for off-site PCB management is mandated when the PCB wastes are shipped off-site for treatment, storage, or disposal.

2.6.2 Water

Activities conducted pursuant to RFCA will generate a variety of water and wastewater which must be managed and, if necessary, treated at the appropriate facilities. In addition, each project may have to incorporate special considerations for stormwater management, spill controls and countermeasures, and other environmental protection measures.

Wastewater Management

Since 1979, RFETS has held a National Pollutant Discharge Elimination System (NPDES) permit regulating the discharge of treated wastewater into off-site waterways. A renewal of the current permit has been prepared, but has not been issued as of July 20, 1998. Generally, the NPDES permit implements the requirements of the Clean Water Act (CWA) and regulates the discharge of the site's wastewater treatment plant, Building 995, the release of product water from Building 374, and storm water discharges. In addition to establishing the performance standards for Buildings 995 and 374, and limitations on specific parameters in the discharge, the permit also imposes a number of administrative requirements from employee training to pollution prevention and spill control practices described below.

Presently, a variety of wastewater treatment capability is available at RFETS, but the continued availability of these wastewater treatment capabilities is subject to change. Pursuant to RFCA, an Integrated Water Management Plan (IWMP) (RFETS, 1997) has been developed as a Site-wide document to evaluate short and long-term wastewater treatment needs. (See RFCA ¶119). As a reference source the IWMP provides a variety of useful background information on RFETS water and wastewater management. The IWMP and updates should be considered during project scoping so that wastewater treatment capacity is available for project activities.

As activities proceed at RFETS, and wastewater treatment capacity is gradually reconfigured or removed from service, each project will have increasing responsibility to provide project-specific water management and wastewater treatment capacity. To expedite any NPDES permitting that may be required, RFCA provides for a consolidated review process. (See RFCA ¶ 101 and ¶103). Depending on project complexity, the consolidated review process represents a commitment by EPA and CDPHE to perform review and public comment on permit applications concurrent with the accelerated action decision process. In addition, the consolidated review process is not supposed to require more time for approval than would otherwise be required under the IM/IRA or PAM process. (See RFCA ¶99).

Spill Prevention Control and Countermeasures/Best Management Practices Plan and Storm Water Pollution Prevention Planning

RFETS is subject to regulatory requirements to have a spill prevention program and to implement best management practices (BMPs) to prevent oil and hazardous substances, respectively, from entering waters of the United States. Under the CWA, a spill prevention plan is required to prevent the release of oil in harmful quantities, which are defined as follows:

For purposes of section 311(b)(4) of the Act, discharges of oil in such quantities that the Administrator has determined may be harmful to the public health or welfare or the environment of the United States include discharges of oil that:

- (a) Violate applicable water quality standards; or*
- (b) Cause a film or sheen upon or discoloration of the surface of the water or adjoining shorelines or cause a sludge or emulsion to be deposited beneath the surface of the water or upon adjoining shorelines.*

BMPs are not specified in regulation, but, rather, rely on professional judgment as to the appropriate measures to take. BMPs that prevent storm water from coming into contact with hazardous substances and barriers to prevent materials from entering surface waters are commonly employed under these requirements.

Other activities may be subject to the substantive requirements of the regulations as ARARs. In addition, some of the construction activity associated decommissioning will be subject to select substantive requirements of the General Stormwater Permit for

Construction Activities. By virtue of the CERCLA permit waivers, formal notification under that General Permit is not required for decommissioning in the Industrial Area or accelerated actions conducted in the Buffer Zone.

Any construction activity where conditions exist that are different enough that it would be appropriate for an individual permit, may be subject to additional monitoring or substantive requirements not contained in the General Stormwater Permit for Construction Activities. Such conditions could include construction in a location contaminated from past industrial activities or where stormwater from the construction site comes into contact with industrial or process wastes. Such locations would have to be outside the Industrial Area, which is already covered by a storm water permit. The general permit is designed for use where the primary contamination anticipated is suspended solids mobilized by precipitation. However, water which falls on the site as "stormwater" may remain stormwater. Each proposed construction activity should be evaluated individually, with particular attention to the location's proximity to contamination, the proposed time frame, and the type of construction.

Projects should also consider other potential impacts of the IA IM/IRA on RFCA activities. The IA IM/IRA imposes surface water, groundwater, and air monitoring requirements on transition activities of the type conducted during deactivation, decommissioning, and accelerated actions.

2.6.3 National Environmental Policy Act

In accordance with RFCA §95 and the June 1994 Secretarial Policy on NEPA, decision documents prepared under RFCA are to incorporate NEPA values. RFCA decision documents that are subject to public and/or agency review before the actions they describe are taken, ordinarily will not require separate RFETS NEPA documentation (e.g., a categorical exclusion or an environmental assessment). Those not subject to public review before action is taken, typically will require NEPA documentation. A draft of all RFCA decision documents must be submitted to the RFETS NEPA group for review to determine if: 1) separate NEPA documentation is required, and 2) NEPA values have been adequately incorporated. To ensure NEPA equivalence, it is also necessary to include a no action alternative in the alternatives analysis for all IM/IRAs, PAMs, Decommissioning Operations Plan (DOPs), and RFCA Standard Operating Protocol (RSOPs).

For decommissioning activities, it is expected that NEPA values will be incorporated into the DPP. Any decommissioning not covered by the DPP will be subject to the process described above for decision documents.

After consultation with the stakeholders, or as a matter of policy, DOE may choose to prepare separate NEPA documentation for an action. If separate NEPA documentation is required, submittal of a project to the RFETS NEPA group for review should be by letter, preferably with a completed environmental checklist. Environmental checklist forms are

available from the NEPA group. NEPA documentation, if required, would be a categorical exclusion or an environmental assessment.

Many projects may be categorically excluded unless there are factors that make a categorical exclusion inappropriate. Such factors include high levels of radiation, other risk factors, or impacts to wetlands, threatened and endangered species habitat, or other environmentally-sensitive areas. Projects that may be categorically excluded must still receive documented approval. If a project is not eligible for a categorical exclusion, an environmental assessment will be required.

2.6.4 Air

RFETS is subject to the Colorado Air Pollution Prevention and Control Act and implementing regulations. An operating permit for RFETS is currently under development by the Colorado Air Pollution Control Division (CAPCD). To expedite any air permitting that may be required, RFCA provides for a consolidated review process. (See RFCA ¶101). The consolidated review process represents a commitment by EPA and CDPHE to conduct review and public comment on permit applications concurrent with the accelerated action decision process. In addition, the consolidated review process is not supposed to require more time for approval than would otherwise be required under the IM/IRA or PAM process. (See RFCA ¶99).

The type of air permitting required is determined by an evaluation of the activity's potential to emit air pollutants and RFETS total emission inventory. In general, de minimus levels of emissions are not subject to air permitting. In some instances, a commitment to abide by existing site procedures (e.g., dust control) can be sufficient to ensure that emissions remain at de minimus levels. At higher levels of emissions, RFETS may be required to submit air permits and Air Pollutant Emission Notices (APENs). APENs are used by CDPHE to inventory emissions for Prevention of Significant Deterioration attainment/non-attainment determinations. At high emissions levels, modifications to the RFETS Title V Operating Permit may be required. The regulations do require that numeric determinations of estimated emissions be included in the application.

Umbrella or "bubble" type permits can also be obtained. This type of permit allows RFETS contractors and subcontractors to conduct multiple excavation, clean-up, or demolition operations under a single permit which contains specified limits of annual pollutant emissions, scope definition, and control requirements. Grouping of multiple operations on a single permit is allowed by the CAPCD, provided aggregated sources are similar. Once obtained, any project subject to the permit terms and conditions is required to document specified operation parameters to demonstrate compliance. The emission limitations established for "bubble permits" will allow for multiple projects annually. As long as the total permitted annual emissions are not exceeded and the controls specified in the permit are employed, no additional permitting or public comment is required.

2.6.5 Ecological Concerns

As a federal natural resource trustee, the DOE (and its contractors) must act in the public interest with regard to conservation of natural resources. As a result of this responsibility, and for regulatory compliance, ecological concerns must be addressed during project planning at RFETS. Compliance with regulations such as the Endangered Species Act; Fish and Wildlife Coordination Act; Migratory Bird Treaty Act (MBTA); CWA; and the Colorado Nongame, Threatened, and Endangered Species Act is required for RFETS activities. Several DOE policies and orders also mandate protection of ecological resources.

Many wildlife species at RFETS are managed and protected by the State of Colorado. Penalties for violations of state wildlife protection laws can include: fines, compensation for damages, or imprisonment. The U. S. Fish and Wildlife Service administers the Endangered Species Act, the Fish and Wildlife Coordination Act, and the MBTA. These acts provide protection of ecological resources from harm. The regulatory agency with the lead for making decisions related to wildlife issues should be determined during scoping.

Pursuant to the CWA, both the EPA and the U.S. Army Corps of Engineers (USACE) have jurisdiction over activities that affect RFETS wetlands. Generally, the EPA has jurisdiction over CERCLA activities, and the USACE has jurisdiction over non-CERCLA activities. The EPA reserves the right to make all jurisdictional determinations. If a project will affect wetlands, a mitigation plan must be developed and in place prior to beginning work. In addition to CWA requirements, DOE is required to protect wetlands under Executive Order 11990. Finally, wetlands impacts must be considered whenever water treatment and operations practices are modified or eliminated.

Prior to the start of work, RFETS activities must be evaluated by a qualified ecologist for potential to impact the Preble's Meadow Jumping Mouse, migratory birds, threatened or endangered species and their habitats, and wetlands. Any outdoor work area must be surveyed in accordance with procedures 1-D06-EPR-END.03 (K-H, 1994a) and 1-G98-EPR-END.04 (K-H, 1994b).

If a protected species is found to be present at a work site, work may be delayed until consultation with the U. S. Fish and Wildlife Service has been completed. This is now particularly true if work will be in or may affect riparian areas on the Site, since the Preble's Meadow Jumping Mouse, a species that lives in these areas, has now been listed as a threatened species (63 FR 26517-26530, May 13, 1998).

Other resource protection issues of importance at RFETS include weed control and revegetation. Weed control on federal lands is mandated by the Federal Noxious Weed Act, the Colorado Weed Management Act, and the Jefferson County Undesirable Plant Management Plan. In areas where long-term soil disturbances will occur, or where revegetation will be done, projects should budget appropriate funds to meet weed control

needs. Revegetation with native plant species and limitation of the size of a surface disturbance is controlled by DOE Order 6430.1A (DOE, 1989).

The Natural Resources Management Policy (NRMP) establishes natural resource policies for management of the Buffer Zone. It is based on the open space cleanup objective expressed in the RFCA Vision. The NRMP will guide selection and funding of Buffer Zone management activities while the Site is being cleaned up under RFCA.

Consistent with the RFCA Vision, DOE will manage resources during cleanup to preserve currently available options for Buffer Zone open space use to facilitate post-closure resource management discussions. In addition, the NRMP will establish policies for addressing natural resource damage issues under CERCLA.

2.6.6 Health and Safety

The regulatory authorities for worker health and safety during activities conducted pursuant to RFCA are the Occupational Safety and Health Act (OSHA) requirements found at 29 CFR Parts 1910 and 1926 and DOE Order 440.1 (DOE, 1995h). DOE Order 440.1 entitled, "Worker Protection Management" obligates DOE contractors to comply with the OSHA 29 CFR Parts 1910 and 1926 requirements. The requirements embodied in the OSHA regulations are addressed in the RFETS Health and Safety Practices manual (K-H, 1997), specifically HSP 21.03 which addresses hazardous waste operations.

The site has an Integrated Safety Management (ISM) program that is implemented for each work activity. Consistent with the site's ISM program, hazards associated with executing the work are identified and controls are put in place to mitigate the hazards to the performance of any field work.

3.0 TECHNICAL APPROACH AND PROCEDURES

All remedial work at RFETS will be conducted as an accelerated action for one or more IHSSs, a closure plan for RCRA regulated units, or pursuant to a CAD/ROD for an Operable Unit (OU). (See RFCA ¶96). Decommissioning will be performed as described in a PAM, IM/IRA (described in the DPP), or as described in individual DOPs for more complex activities. Deactivation, decontamination, and decommissioning will be integrated with ER to ensure an orderly transition between programs.

To expedite remedial work and maximize accelerated risk reduction, the RFETS will make extensive use of accelerated actions for IHSSs, Potential Areas of Concern (PACs), and Under Building Contamination (UBC). For ease of discussion, "IHSSs," "PACs," and "UBCs" will all be termed as "IHSSs" for the remainder of this document.

The focus of the RFETS ER Program is on cleanup. The decision process will be developed using a bias for action that: (1) identifies IHSSs or evaluates the Site for risk, (2) determines whether a cleanup is necessary, and if so, evaluates whether the IHSS is appropriate for an accelerated action, and (3) ranks the area relative to other IHSSs. The ER process flow is shown in Figure 3-1.

Following completion of all accelerated actions and decommissioning, the residual risks in the Industrial Area and the Buffer Zone will be evaluated through interpretation and incorporation of available data. (See Section 3.6.3).

3.1 ENVIRONMENTAL RESTORATION PROCESS AND DOCUMENTS

The IAG (DOE, 1991) created 16 OUs. By the time the RFCA was signed in 1996, OUs 11, 15, and 16 had been closed by means of CAD/RODs. Attachment 1 to RFCA and a prior modification to the IAG consolidated the remaining OUs into seven OUs.

Development of RFETS-specific documents is described with accompanying flow charts in the following sections. Development of standard CERCLA documents will be in accordance with the NCP and other available EPA guidance documents.

In developing any RFETS decision document, the DOE RFFO will meet with the regulators to present the approach to a given IHSS or remedial action as discussed. (See Section 2.0). Once the approach is agreed upon by all parties, development of the decision document will proceed as outlined below.




Figure 3-1 Environmental Restoration Process Flow

RFCA identifies several types of decisions for action or no action.

- IM/IRAs will be developed when a formal evaluation of remedial options is necessary or remedial activities are estimated to require more than six months from commencement of physical work to completion. The requirements for IM/IRAs are discussed in Section 3.1.1 and Appendix C.
- PAMs will be used where remedy selection is straightforward, and remedial activities are estimated to take less than six months from commencement of the physical work to completion. The requirements for PAMs are described in Section 3.1.2 and Appendix D.
- Emergency Removal Actions are discussed in Section 3.1.3.
- No Action, No Further Action, and No Further Remedial Action decisions for IHSSs will be documented in updates to the Historical Release Report (HRR), as described in Section 3.1.4 and detailed in Attachment 6 to RFCA.
- CAD/RODs have been or will be developed by DOE for OUs 1, 3, 5, 6, 7, 11, 15, and 16. Future CAD/RODs will be developed to document the final corrective action/remedial decision for the Buffer Zone and the Industrial Area. Development of CAD/RODs will follow EPA guidance. The RFCA approach to CAD/RODs is described in Section 3.1.5.
- The RFCA also identifies RSOPs that are applicable to routine ER and/or decommissioning activities that DOE may repeat without obtaining additional approval. Initial approval of an RSOP will be through the IM/IRA process (See RFCA ¶25bo). The requirements for RSOPs are addressed in Section 3.1.6
- DOPs for complex decommissioning activities will be reviewed by the LRA via either the PAM or IM/IRA review process. (See RFCA: ¶121). The requirements for DOPs are addressed in Section 3.1.12.

Supporting documents identified in RFCA which may be required for an IHSS to reach the decision document stage, may include RCRA Facility Investigation/Remedial Investigation (RFI/RI) work plans and reports and Corrective Measure Study/Feasibility Studies (CMS/FSSs), which are part of the CAD/ROD process. Other supporting documents identified in RFCA are Sampling and Analysis Plans (SAPs), Technical Memoranda (TM), Closeout Reports, and Treatability Study Reports where necessary. The development of SAPs is discussed in Section 3.2 and the development of TMs is discussed in Section 3.1.9.

Appendices to this document are included which discuss the development of RFETS-specific documents. When documents will be developed using the standard CERCLA approach, the EPA guidance for developing these documents is cited.

The document review process is similar for all of the major documents identified in RFCA. Specific document review processes and times are found in Part 9 of RFCA. Generic schedules and suggested document formats are included with the IGD appendices.

During the public comment period, and after consultation with and approval by the LRA, DOE may initiate certain preliminary activities. These preliminary activities may include conducting appropriate sampling in accordance with the approved SAP and conducting any studies and administrative activities prerequisite to implementing the accelerated action.

If public comments are received, the approved Responsiveness Summary will be placed in public information repositories before the accelerated action is initiated except with regard to the preliminary activities described above. DOE will keep the LRA apprised of the progress of the activities required for implementation of the accelerated action through the monthly project coordinators meeting and the quarterly progress reports. (See RFCA ¶s 262 and 263).

3.1.1 Interim Measure/Interim Remedial Action Decision Documents

IM/IRAs apply to interim remedial activities or removal actions that are estimated to take more than six months from the commencement of physical work to completion. (See RFCA ¶107). Remedial activities performed under an IM/IRA will, to the extent practicable, be consistent with and contribute to the efficient performance of any anticipated long-term remedial action. The IM/IRA may also serve as a RCRA Part B permit modification, when indicated in the document. If CDPHE determines that an activity constitutes a RCRA Class 3 permit modification, the IM/IRA will be subject to the public comment process outlined in RFCA ¶108. The IM/IRA process is shown in Figure 3-2.

IM/IRAs will also be developed for accelerated actions where several remedial options are available. These IM/IRAs will evaluate multiple alternatives and justification of the selected alternative.

The IM/IRA process requires production of three documents: the IM/IRA, the SAP, and the Closeout Report. Public comments are received and a formal responsiveness summary is included with the final IM/IRA. The responsiveness summary may also be prepared as a separate document. The document schedule will be set during Project Scoping consistent with RFCA ¶s 89, 107, and 108.

A SAP (see Section 3.1.8) is prepared concurrently with the IM/IRA and is finalized during the public comment period. Although the SAP is submitted to the agencies for review and approval, it is not reviewed by the public because of the technical detail. Any additional documents necessary to execute the accelerated action should be made available to the agencies and the public, but they are not subject to agency approval or public comment. These documents include the Health and Safety Plan (HASP), the Hazards Analysis (HA), Readiness Analysis, and the Field Implementation Plan (FIP). Although this type of information is vital to performing the action, it is not part of the RFETS authorizing sequence.




Figure 3-2 Environmental Restoration Interim Measures/Interim Remedial Action Process

IM/IRA format and contents are discussed in Appendix C, Preparation of an IM/IRA. Consistent with RFCA ¶107, an IM/IRA includes:

...[A] brief summary of data for the site, a description of the proposed action, an explanation of how waste management considerations will be addressed, an explanation of how the proposed action relates to any long-term remedial action objectives, proposed performance standards, all ARARs and action levels related to the proposed action; and an implementation schedule and completion date for the proposed action.

Performance monitoring is required for all groundwater remedies and should be noted in the IM/IRA. Details of the performance monitoring will be developed as part of the project-specific remedial decision document and implemented through the IMP described in Section 3.14 (DOE, 1998). Performance monitoring will be required for some soil remedies, and if appropriate, identified in the IM/IRA. (See Section 3.4.E of the ALF). To meet NEPA requirements, screening of alternatives, including no action, is required and will use the Engineering Evaluation/Cost Assessment (EE/CA) process for streamlined alternatives analysis as guidance. This can be found in EPA *Guidance on Conducting Non-Time Critical Removal actions Under CERCLA* (EPA, 1993). The schedule for developing an IM/IRA will follow the document review schedule outlined in ¶107 of RFCA (or ¶108, if applicable).

3.1.2 Proposed Action Memorandum

The PAM is the primary planning and implementation document for ER accelerated actions. Actions expected to take less than six months from commencement of construction to completion may be approved under the PAM process. (See RFCA ¶106). Closeout reports for actions performed under PAMs will have the same requirements and format as for actions performed under IM/IRAs. The purpose of the PAM is to describe the nature of the contamination, the proposed mitigating action, and an implementation schedule. The PAM preparation process is summarized in Figure 3-3. The PAM may also serve as a RCRA Part B permit modification, where indicated.

The PAM process requires the production of three documents: the PAM, the SAP, and the Closeout Report. PAMs are four to thirty pages in length and reference existing information, previously published, and available documents detailing earlier field investigations. PAMs for accelerated actions are coordinated closely with EPA and CDPHE to minimize the number and duration of review cycles. If public comments are submitted, a formal responsiveness summary will be included with the final PAM, which is revised as necessary.




Figure 3-3 Proposed Action Memorandum Process

A SAP (see Section 3.1.8) is prepared concurrently with the PAM and finalized during the PAM public comment period. Although the SAP is submitted to the agencies for review and approval, it is not reviewed by the public because of the technical detail. Additional documents necessary to execute the PAM should be made available to the agencies and the public, but they are not subject to agency approval or public comment. These documents include the HASP, the HA, and the FIP. Although this type of information is vital to performing the action, it is not part of the RFETS authorizing sequence.

Details of PAM preparation are found in Appendix D. Consistent with ¶106 of RFCA, a PAM includes:

...[A] brief summary of data for the site; a description of the proposed action; an explanation of how waste management considerations will be addressed; an explanation of how the proposed action relates to any long-term remedial action objectives; proposed performance standards; all ARARs and action levels related to the proposed action; and an implementation schedule and completion date for the proposed action

Performance monitoring is required for all groundwater remedies and should be described in the PAM. Details of the performance monitoring will be developed as part of project-specific remedial decision document and implemented through the IMP described in Section 3.14 (DOE, 1998). Performance monitoring will be required for some soil remedies, and if appropriate, identified in the PAM. (See Section 3.4.E of the ALF).

The schedule for developing a PAM will closely follow the document review schedule outlined in ¶106 of RFCA, and is illustrated in Appendix D.

3.1.3 Emergency Removal Actions

RFCA ¶96 governs Emergency Removals as follows:

DOE may initiate a time-critical removal action if it determines, in accordance with the National Contingency Plan, that an immediate response is needed to eliminate or abate a release or substantial threat of release of a hazardous substance posing an immediate and substantial endangerment to the public health and welfare or the environment. DOE shall notify EPA and CDPHE within 24 hours of this determination. Once the immediate threat has been averted or mitigated, DOE shall propose any further actions that may be necessary in accordance with the provisions of this Part or Part 10, as appropriate.

If the RCRA Contingency Plan is activated, the regulators are notified through that process. Otherwise, the DOE RFCA Project Coordinator will notify the other parties.




Figure 3-4 Emergency Removal Action

The Emergency Removal Action process is depicted in Figure 3-4 and will be documented in a Closeout Report that follows the outline in Section 3.1.12. The Closeout Report will assess whether additional evaluation is needed or if sufficient data are available to evaluate for NFA. The removal action will be incorporated into the annual update of the HRR.

3.1.4 No Further Action Decisions

The criteria and documentation requirements for determining if a geographic area (IHSS, PAC, UBC, Source Area, OU, or Area of Concern [AOC]) can be recommended for NFA are detailed in RFCA Attachment 6. The NFA decision process presented within RFCA Attachment 6 meets the substantive requirements to support an NFA (as defined by CERCLA) remedy selection for a CAD/ROD. An NFA decision may be warranted at RFETS under three sets of circumstances:

- When the geographic area poses no current or potential threat to human health or the environment, including risk from radiological dose (a no action decision)
- When a previous response eliminated the need for further remedial response (a no further action decision)
- When risk estimates and radiological dose calculations based on specific exposure scenarios indicate institutional controls alone will constitute acceptable risk management (a no further remedial action decision)

Various processes were consolidated in RFCA Attachment 6 to provide decision criteria for establishing those geographic areas at RFETS not requiring further study or remediation as part of the CERCLA process. The steps, in order of performance, are shown in Figure 3-5 and summarized below.

1. **Conduct source evaluation (with available data/information)** – If a review of historical release information/defensible data reveals that no current or potential source can be found, then the exposure pathway is incomplete and the geographic area will be documented for No Action or No Further Action.

2. **Conduct an ALF comparison** – If a review of historical release information/defensible data indicates that a current or potential threat may be present, the geographic area will undergo an ALF comparison. If media-specific environmental data collected from the geographic area are shown to be at or below action levels for inorganic chemicals and no organic chemicals are detected in that media, the geographic area will be documented for No Action or No Further Action.

3. Conduct a CDPHE conservative screen and an Ecological Risk Assessment screen –

The purpose of conducting a CDPHE conservative screen is to reduce the number of geographic areas that require a CERCLA baseline risk assessment (see Appendix K). Certain geographical areas have already been screened using the CDPHE conservative screen to evaluate human health risks. Ecological risks are screened using Tier 2 of the Ecological Risk Assessment Methodology (ERAM) (DOE, 1996a and 1996b). If a geographic area or source area passes the human health and ecological risk based screens, then that geographic area will be documented for No Action or No Further Action.

4. Perform a Risk Evaluation or Baseline Risk Assessment– A risk evaluation may be performed on limited geographic areas to justify No Further Action or No Further Remedial Action. This will be described in the appropriate CAD/ROD. The Baseline Risk Assessment (BRA) consists of a human health risk assessment (conducted on a specific exposure area) and an ecological risk assessment (conducted on a site-specific drainage area). BRAs have already been performed for OUs 1, 2, 3, 5, and 6. The Comprehensive Sitewide Risk Assessment (CRA) will include an evaluation of baseline conditions as if no further action, including implementing institutional controls, were taken. Risks will be evaluated according to the land uses described in RFCA and will evaluate the cumulative risk for RFETS. If the results of the CRA show that the risks to human health and the environment are within acceptable levels, RFETS will be closed with a No Further Action or No Further Remedial Action CAD/ROD.

The rationale for an NFA decision will be summarized in an update to the HRR, and appropriate supportive documentation will be appended, as necessary. (See Section 3.8.2). The HRR update for NFA recommendation is intended to be a place keeper for documentation that the substantive requirements for NFA decisions have been met. For those sites evaluated within an RFI/RI Report or a letter report (i.e., for those geographic areas that pass the CDPHE conservative screen) additional documentation justifying the NFA decision is not necessary, and the supporting documentation can be incorporated into the HRR update by reference.

Geographic areas not evaluated as part of an RFI/RI (i.e., an area where an accelerated action has been completed) can be placed on hold by using the HRR to present an evaluation of existing information. Geographic areas documented in this manner will incur minimal administrative attention and costs while awaiting final disposition in a CAD/ROD. This process also removes any impediment the area might otherwise impose on adjacent or overlapping activities. All NFA decisions documented in this manner are subject to revisitation at the CAD/ROD. Other administrative requirements for coordination of NFA decisions with the CAD/ROD process and with RCRA closures at RFETS are discussed in RFCA Attachment 6.

Geographic areas can only achieve No Further Remedial Action status if an institutional control is in place. An institutional control and a recommendation for No Further Remedial Action for that particular area would then be incorporated in a final CAD/ROD. A generic schedule for the NFA process is included in Appendix E.




Figure 3-5 Decision Points for No Action, No Further Action, or No Further Remedial Action Recommendations

3.1.5 Proposed Plans and Corrective Action Decision/Record of Decision

CAD/RODs apply to the final corrective/remedial decision made for an OU following implementation of all accelerated actions. (See RFCA ¶96). CAD/RODs have been or will be completed for OUs 1,3,5,6,7,11,15, and 16, leaving only two areas subject to the CAD/ROD process. One will include all of the Buffer Zone, and one will include all of the Industrial Area.

Individual IHSSs will be documented as NFA sites or will be cleaned up through accelerated actions. The residual contaminant levels following accelerated actions will be documented in the various Closeout Reports, the HRR, and assessed in the CRA.

For the Industrial Area OU, CDPHE will make a recommendation to EPA whether to concur with DOE's proposed remedial decision for radionuclides and other hazardous substances that are not hazardous constituents. (See RFCA ¶84). This remediation decision will be presented to the public in a Proposed Plan (PP), and finalized in a CAD/ROD. The PP and the CAD/ROD will be developed following the *Interim Final Guidance on preparing Superfund Decision Documents* (EPA, 1989a).

For the Buffer Zone OU, following implementation of all planned accelerated actions, EPA and DOE will make a final remedial decision. The Buffer Zone remediation decision will then be presented to the public in a PP and finalized in a CAD/ROD.

Proposed Plan

Preparation of the PP is described in the *Interim Final Guidance on Preparing Superfund Decision Documents* (EPA, 1989a). The purpose of a PP is to facilitate public participation in the remedy selection process by:

- Identifying the preferred alternative for a remedial action at a site or OU and explaining the reasons for the preference
- Describing other remedial options that were considered in detail in the CMS/FS
- Soliciting public review and comment on all of the alternatives described
- Providing information on how the public can be involved in the remedy selection process

A PP is a public participation document and is expected to be widely read. Therefore, it should be written in a clear and concise manner using nontechnical language and should not exceed 5-10 pages. In addition, it should direct the public to the RFI/RI and CMS/FS reports, accelerated action closure reports, and other Site-specific information as the primary source of detailed information on the remedial alternatives analyzed.

For the OUs at RFETS, the PP should list the IHSSs that have been addressed through the NFA process which will be included in the CAD/ROD for the OU. A table format is recommended for listing the IHSS or building, how it was closed, and each IHSS or Closeout Report.

A PP should relate the findings of the RFI/RI, CRA, and CMS/FS in a brief, nontechnical format. The information should be presented in support of the preferred alternative and discuss how it is protective of human health and the environment.

A PP should clearly state that the LRA and the DOE have identified a preferred alternative based on available information, but they have not "selected" a remedy to implement. A PP supports only preliminary decisions for an OU. It should not make definitive findings or declarative statements that would be difficult to revise later.

A PP should emphasize that the preferred alternative is only an initial recommendation. It should clearly state changes to or from the preferred alternative may be made, if public comments or additional data indicate that such a change would result in a more appropriate solution. The plan must also state that the final decision will be documented in the CAD/ROD after the DOE and the LRA have taken into consideration all comments from the SRA and the public.

The EPA guidance on preparing decision documents describes statutory requirements for a PP and suggests language for these sections. The guidance also includes a suggested outline and detailed suggestions for writing a PP, and describes how to address changes to the PP following public comment. A specific appendix on development of a PP is not included in the IGD because RFETS PPs are expected to follow the general process EPA outlined.

Corrective Action Decision/Record of Decision

The CAD/ROD documents the remedial action plan for an OU. It is prepared by DOE and the LRA in consultation with the SRA. (See RFCA ¶83, 84, and 85 for discussion of regulatory authority over CAD/RODs). The CAD/ROD has the following purposes:

- To certify that the remedy selection process was carried out in accordance with the requirements of RFCA, CERCLA, and is consistent with the NCP
- To outline the engineering components and remediation goals of the selected remedy
- To provide the public with a consolidated source of information about the history, characteristics, and risks posed by the conditions at the site, as well as a summary of the cleanup alternatives considered, their evaluation, and the rationale behind the selected remedy

The CAD/ROD consists of three basic components: (1) a Declaration, (2) a Decision Summary, and (3) a Responsiveness Summary.

The Declaration functions as an abstract for the key information contained in the CAD/ROD, and it is signed by the EPA, CDPHE, and DOE. The Decision Summary provides an overview of the site characteristics, the alternatives evaluated, and the analysis of the remedial options. The Responsiveness Summary addresses public comments submitted on the PP, RFI/RI and CMS/FS report, and other information in the AR.

The Interim Final Guidance for Preparing Superfund Decision Documents (EPA, 1989a) includes a section-by-section discussion of the components of a ROD, and it should be followed in developing an RFETS CAD/ROD. RCRA units can be closed within the CAD/ROD. The EPA guidance also covers preparing a No Action, No Further Action, or No Further Remedial Action ROD. Rather than repeat information already well developed and presented, refer to this guidance and to previous RFETS CAD/RODs. Appendix F includes a generic PP/CAD/ROD development schedule.

3.1.6 RFCA Standard Operating Protocols

RSOPs:

apply to accelerated actions that are routine and substantially similar in nature, for which standardized procedures can be developed. (See RFCA ¶196).

RSOPs will be developed for remedial actions or decommissioning activities where the same approach will be applied to several different IHSSs or buildings. An example of an ER RSOP would be a generic plan for cleaning and rendering tanks inert. Review and approval of RSOPs will follow the document review process of IM/IRAs. The public comment period for RSOPs will follow the IM/IRA process. An approved RSOP, is implemented by notifying the other RFCA parties. (See RFCA ¶25)

3.1.7 RCRA Facility Investigation/Remedial Investigation Process

Since remedial actions at RFETS have been combined into fewer OUs, only two RFI/RI remain to be conducted. Other OUs have already been investigated under the RFI/RI process and are in various stages of completion. The CERCLA process for RI development will be followed for the Buffer Zone and Industrial Area OUs (EPA, 1988a). A flow diagram of the RFI/RI process, as envisioned for RFETS, is shown in Figure 3-6.




Figure 3-6 RCRA Facility Investigation/Remedial Investigation

When the RFI/RI for the Buffer Zone and the Industrial Area are developed, all identified IHSSs should have undergone risk screening and should be identified for an NFA recommendation or accelerated action. The RFETS RFI/RI will integrate existing data and gather new data only where data gaps related to remediation are identified. Decision making needs will be linked directly to data collection and will address RFCA requirements for environmental monitoring in accordance with the IMP.

The Industrial Area RFI/RI will be developed following decommissioning of the Industrial Area buildings and conducting appropriate accelerated actions. The Industrial Area RFI/RI will focus on developing an Industrial Area conceptual model and the CRA. Areas which have not undergone accelerated action, deactivation, or decommissioning will be evaluated for further data needs. The need for collection of additional data will be determined during project scoping and development of the RFI/RI work plan. If enough data are available to determine the risk from the Industrial Area and further remediation is necessary to address the risk, any additional data collected will address remedial selection and design needs.

The Buffer Zone RFI/RI process may not involve the gathering of new data, but will focus on developing the CRA. The CRA will compile the summary information and risk estimates from the previous Buffer Zone BRAs where possible. However, remedial actions, taken after production of the original BRAs, may render many of the estimates obsolete, and new estimates will have to be combined with those from the Industrial Area in order to determine the cumulative effects on some receptors. If additional action is needed as part of the final remedial action for the Buffer Zone, the remedy will either be selected through the CMS/FS process or a presumptive remedy will be used. The remedy selection will be documented in a PP/CAD/ROD. Appendix G includes a generic RFI/RI process schedule.

3.1.8 Sampling and Analysis Plans and Data Quality Objectives

SAPs will be required in support of pre-remedial characterization, waste volume calculations, waste characterization, verification of cleanup, and design data needs. Data quality objectives (DQOs) will be developed for all sampling activities. Sampling plans and related DQOs will be focused on collecting data to meet a specific need (i.e., to address a specific decision). Decision making needs will be linked directly to data collection. The purposes of the SAPs include:

- To document the decisions/uses for which data are needed, and the decision process used to determine the specific sampling approach
- To guide the field sampling crew in exactly what samples are to be collected, where and how they are to be collected, and what criteria trigger collection of additional or fewer samples
- The analytical methods to be used and the specific requirements of sample collection and handling for those methods

SAPs consist of a Field Sampling Plan (FSP) and a Quality Assurance Project Plan (QAPjP). At RFETS, a site-wide QAPjP has been developed. Therefore, most SAPs consist of the FSP and discuss project-specific modifications to the QAPjP. Because of this approach, data quality objectives focused on the project-specific data needs are developed within each SAP/FSP. Development of SAPs is described in Appendix I.

Data quality in terms of laboratory analytical methods will be focused on the primary and secondary data uses. In general, SW-846 analytical methods are appropriate for the documentation of hazardous waste characteristics, for risk evaluation, and for the determination that soils remaining following a cleanup are below the levels specified in the decision document. Radiological laboratory analysis will be performed under RFETS Statement of Work for Analytical Measurements. Field screening data are generally sufficient to meet the DQO needs of gross volume calculations before excavation or for excavation control. A statistical approach will be used, where appropriate, to determine the number of samples necessary to make a specific decision. Data will not be collected unless a specific decision has been identified for the data.

In collecting characterization or design data, a conceptual model of the IHSS, specific release, or system to be addressed will be developed based on existing data and professional judgment. The conceptual model will address contaminant transport issues such as expected presence of dense non-aqueous phase liquids, connection to higher permeability zones, and containment of the contamination by low permeability clays. Development of a conceptual model incorporating available data assists in framing the questions that justify additional data collection.

The IMP includes the sampling requirements for routine monitoring of surface water, air, and ecological resources. This monitoring plan has involved extensive DQO evaluation for samples that are collected on a routine basis. The IMP includes the location of collection points, frequency, method of sampling required, and analytical suites. The IMP also describes reporting requirements and specific triggers to increase sampling frequency or perform additional evaluations.

3.1.9 Corrective Measures Study/Feasibility Study

The CMS/FS identifies and evaluates appropriate corrective measures. "Corrective Measures Study" is a RCRA/CHWA term that is analogous the CERCLA "Feasibility Study." Under RFCA, the CMS and FS may be the same document. (See RFCA ¶25v).

The CMS/FS developed at RFETS will be consistent with the NCP and with EPA feasibility study guidance. The EPA proposed rule for Corrective Action for Solid Waste Management Units at Hazardous Waste Management Facilities (55 FR 30798) and associated guidance will also be considered. Where appropriate, the CMS/FS will evaluate CHWA's closure and post-closure care requirements. A sample table of contents for the CMS/FS and schedule are provided in Appendix H.

The CMS/FS tasks include:

- Establish narrative corrective/remedial action objectives and, if appropriate, numeric remedial action goals
- Develop General Response Actions (GRAs) and identify potential remedial technologies and process options
- Screen potential remedial technologies and process options and develop a list of representative process options (RPOs)
- Assemble RPOs into remedial alternatives
- Screen remedial alternatives to eliminate unfeasible and impracticable options
- Further define alternatives as necessary
- Analyze alternatives against the nine evaluation criteria, then against each other
- Prepare the CMS/FS report to document results

The above list of tasks is adapted from EPA's *Guidance for Conducting Remedial Investigation and Feasibility Studies Under CERCLA (EPA, 1988a)*. At RFETS, the primary use of the CMS/FS process will be to evaluate the combined results of various accelerated actions. In that instance, based upon risk assessment and ARARs evaluations, the CMS/FS may result in narrative remedial action objectives and numeric remedial action goals that do not compel evaluation of a wide range of remedial technologies and process options.

The scope and content of the CMS/FS is not subject to an arbitrary formula. The evaluation of technologies and process options, and subsequent screening and analysis is focused on the risk and ARARs-based remedial action objectives.

3.1.10 Technical Memoranda

TMs will be written, if necessary, to resolve specific interpretive issues. They will be brief, similar in nature to a "white paper," and will be focused on presentation and discussion of information relevant to the specific issue. Many TMs will be developed to address or clarify issues, and will not be subject to the document review and revision process. When the TM modifies a previous decision document, the modifications must be accomplished consistent with Part 10 of RFCA and Section 3.10 of the IGD. The RFCA specifically identifies three types of TMs:

- BRA TM
- CMS/FS TM
- RFI/RI Work Description TM

Examples of other types of TMs would be: impact evaluations of exceedances of action levels, the examination of design data needs, an evaluation of the actual impact of an ARAR on an action, or compilation and discussion of data to determine whether a constituent above an ARAR or a RFCA ALF cleanup level is within natural background variability for the site. TMs will be incorporated into the AR.

3.1.11 RCRA Closure

RFCA Attachment 10 provides direction on closure of RCRA interim status units. This guidance can also be applied to permitted units; however, these are not covered by the agreement. Four significant RCRA closure issues are included in RFCA:

- Closure of permitted and interim status units incorporated into a decision document in lieu of a unit-specific closure plan
- Closure of land-based and non-land-based RCRA interim status units
- Clean closure of RCRA units
- Phased closure of RCRA units


Hazardous waste management units are subject to closure under the RCRA Part B Permit or the Interim Status Closure Plan. According to RFCA ¶97, CDPHE will determine if a separate closure plan is required or if the closure/post-closure requirements will be incorporated into a decision document. Closure of land-based interim-status units will be incorporated in IM/IRAs; non-land-based interim-status units may be covered by a PAM, an IM/IRA, or an RSOP. RCRA units not closed under accelerated actions or decommissioning will be closed as part of the final CAD/ROD (e.g., 750 and 904 pads).

All closures will be performed in accordance with the CPB. Wastes which are generated during implementation of a closure action, either wastes from a corrective action for a land-based unit or residual wastes from a non-land-based unit, are considered remediation wastes. Existing contamination will be addressed separately, as part of RCRA corrective actions/CERCLA remedial actions as determined by the ALF and detailed in the *Ground-water Conceptual Plan for the Rocky Flats Environmental Technology Site* (RMRS, 1996b).

Section I of RFCA Attachment 10 enumerates the minimum requirements for closure of land-based interim-status units (the Solar Ponds and Present Landfill). This section specifies design criteria of a cap/cover over these land-based units as well as monitoring and other post-closure activities.

Minimum closure requirements for non-land-based units (mostly former OU 9 IHSSs) are discussed in RFCA Attachment 10, Section II. This section specifies the removal of all wastes from these units and describes how the units can accomplish clean closure via corrective action based on an appropriate decision document. If a unit cannot achieve clean closure, other requirements, including post-closure requirements, will apply.

The RCRA Part B Permit (CDPHE, 1997) parallels RFCA ¶71 by specifically providing for phased closure when appropriate. Phased closure begins when a unit is placed in a "RCRA-stable" configuration. This RCRA-stable concept is not described in or regulated by RFCA, but it is included in Section E of Part X of RFETS's Part B RCRA permit. Elements of this closure strategy include waste removal, elimination of future waste input, less stringent unit management practices (e.g., inspection requirements), and removal of the unit including



*Note, bold indicates that approval is required

Figure 3-7 Facility Disposition Process

disposition of associated equipment and debris. This strategy for clean closure allows DOE to conduct the closure of a permitted unit in two stages: first by rendering a unit/portion of a unit RCRA stable, followed by completion of the final stage of closure as part of a RFCA-regulated cleanup activity. Once a permitted unit is placed in a RCRA-stable configuration, final closure of the unit is deferred until it is scheduled pursuant to the RFCA budget planning process and prioritized and integrated with other activities. RCRA-stable units will be indicated as such, pending final closure, in the Master List of RCRA Hazardous Waste Units at Rocky Flats, which is updated semi-annually.

3.1.12 Closeout Reports

A Closeout Report will be prepared for all remedial or accelerated actions when work is completed, and the analytical data specified in the SAP has been received. The report will consist of a brief description of the work that was completed, including; (1) any modifications or variations from the original decision document; (2) analytical results, including the results of any confirmatory sampling taken to verify completion of the action to the specific performance standards; and (3) a description of the quantity, characteristics, storage and disposal of the actual wastes produced.

The report will state whether the goals and objectives of the early action were met and if not, what additional work is required. The complexity of the Closeout Report and the level of detail will reflect the scope and duration of the action. An example outline for a Closeout Report is shown below:

- Introduction
- Action description
- Verification that action goals were met
- Verification of treatment process (if applicable)
- Radiological analysis (if applicable)
- Waste stream disposition
- Site reclamation
- Deviations from the decision document
- Demarcation of excavation
- Demarcation of wastes left in place
- Dates and duration's of specific activities (approximate)
- Final disposition of wastes (actual or anticipated)

3.1.13 Project Cost Summary

Following project completion, DOE RFFO will provide the following unburdened general project cost to the agencies:

- Total project burdened and unburdened costs
- Project management

- Planning and site preparation
- Excavation and site restoration
- Treatment
- Transportation
- Waste disposal

This information must be reviewed by K-H Legal prior to its release to ensure the information is submitted to protect confidentiality.

3.2 DECONTAMINATION AND DECOMMISSIONING

The decommissioning program is governed by the DPP which describes how aspects of building decontamination and decommissioning will be implemented and elaborates on Attachment 9 of RFCA. The DPP was offered for public comment.

Included in the DPP are examples of specific end points for deactivation:

- When the probability of a criticality event is not credible
- When all combustibles that are not integral to the building are removed
- All hazards are removed and the building is in a safe and stable condition
- Primacy has shifted from the DNFSB to CDPHE and EPA

The following items listed in the DPP are part of decommissioning:

- Characterization of contamination
- Hazards identification
- Decontamination in preparation for release for reuse or dismantlement
- Strip out and removal of glove boxes, ducts, and tank/process equipment
- Size reduction of glove boxes, ducts, and tank/process equipment
- Waste minimization activities associated with decommissioning
- Dismantlement
- Demolition

The process described in the DPP begins with a scoping meeting, proceeds to reconnaissance level survey for contamination, a hazard assessment, and a reconnaissance level characterization report of the findings. At that point, the lead regulatory agency is notified of the categorization. Figure 3.4.1 of the DPP provides an illustration of the process.

The DPP identifies three categories of buildings. Each category of building is subject to progressively more rigorous levels of regulatory scrutiny. Type 1 buildings are free of contamination. Type 2 buildings are "without significant contamination or hazards but in need of decontamination". Type 3 buildings have significant contamination and/or hazards. Buildings 371/374, 559, 707, 771/774, 776/777, and 779 have been designated as Type 3.

For Type 1 buildings, following the reconnaissance level survey, buildings determined to be free of contamination may go directly to reuse, dismantlement, or demolition (i.e., Type 1 buildings). For Type 2 and Type 3 buildings, the appropriate decision document must be prepared. Buildings may be reclassified from Type 1 to Type 2 if contamination is discovered and the removal techniques will involve a threat of release. Suggested outlines for the decision documents are provided in the DPP.

Other documents may also provide useful guidance for completing decommissioning at RFETS. The Facility Decommissioning Management Plan provides broad information to facilitate projects. In addition decommissioning protocols are being developed and will assist in conducting reconnaissance level characterization.

3.3 TRANSITION PROCESS FROM DECONTAMINATION AND DECOMMISSIONING TO ENVIRONMENTAL RESTORATION

Prior to the initiation of decommissioning activities, monitoring efforts (monitoring for surface water, groundwater, and air) are required to establish the baseline conditions that exist in the Industrial Area. This effort is coordinated with the RFET's ER and Environmental Management and Compliance organizations. To establish good baseline conditions, this effort should occur very early in the decommissioning scoping phase and to the extent practicable, be incorporated into the IMP update.

The ER organization should be integrated into decommissioning project scoping to develop an understanding of the project, such as type of contaminants expected in the building; to decide whether adequate monitoring is in place to establish the baseline conditions; to decide what part of the structure will be left at the end of decommissioning; and to define the anticipated role of the ER organization at the end of decommissioning.

Following decommissioning, the area will either be evaluated for the ER ranking or have NFA justification documentation prepared.

3.4 DATA MANAGEMENT AND QUALITY ASSURANCE/QUALITY CONTROL

A variety of data will be generated during ER or decommissioning. These data include but are not limited to:

- Air monitoring data
- Meteorological data
- Ecological data
- Surface water monitoring data (including physical and chemical information)
- Groundwater monitoring data (including analytical and field parameters)
- Well construction data
- Geological information
- Spatial data

- Soils data (analytical and physical data)
- Other characterization data (including high purity germanium [HPGe] field data)

The specific types of monitoring and the types of data collected are evaluated during project scoping and identified in the project documents. The data collected during cleanup activities are essential to the successful closure of the RFETS and, therefore, proper management of the data is a key responsibility of the project.

The project manager must ensure that environmental data collected in support of RFCA activities meet all applicable data quality requirements (Appendix Q), including analytical data quality requirements; program data quality requirements; and evaluation of the data with respect to precision, accuracy, representativeness, completeness, and comparability (PARCC). Details on PARCC analysis are provided in Appendix Q.

Any verification soil sampling collected to demonstrate the satisfaction of performance objectives must be formally transferred for incorporation into the Soil and Water Database (SWD). Similarly, where treated or untreated soil has been stockpiled and sampled prior to returning the soil to an excavated location (putback), any sample results representative of the stockpile, and thus representative of the returned soil, must be included in the SWD.

Quality Assurance/Quality Control (QA/QC) requirements are addressed in a graded approach in accordance with DOE Order 5700.6C (DOE, 1996e) for non-nuclear facilities, activities and services and with the NCP (40 CFR Part 300). Specifically 40 CFR §300.415 (b)(4)(ii) for CERCLA removal actions and 40 CFR §300.430(b)(8) for CERCLA remedial actions require FSPs, SAPs, PAMs, IM/IRAs, RSOPs and Closeout Reports to address quality concerns. Additional details on QA/QC are provided in Appendices I and Q.

3.5 ARARS AND RFCA PERMIT WAIVER

The RFCA requires a process for identifying applicable or relevant and appropriate legal requirements for response actions under CERCLA be developed. (See RFCA ¶10p). To accomplish this objective, an RFETS Master List of Potential ARARs (ARARs List) will be finalized and maintained. ARARs identification will be initiated when individual projects are scoped, and ARARs will be determined when the decision document is signed. Interpretation of ARARs during a response action will be accomplished using the consultative process.

3.5.1 ARARs List

The ARARs List serves to narrow the universe of potential ARARs. The ARARs List can be found in Appendix J. Environmental requirements with little or no likelihood of applicability or relevance and appropriateness (e.g., Coastal Zone Management) have been removed from consideration. The ARARs List will be updated as needed, at a minimum on an annual basis. (See RFCA ¶5).

3.5.2 Project-Specific ARARs Analysis

ARARs will be initially identified when projects are first scoped. The identification will be conducted consistent with the NCP, the preambles to the proposed and final NCP, CERCLA Compliance with Other Laws Manuals Part I and Part II (EPA, 1988b and EPA, 1989b), and other EPA ARARs guidance.

The identification will begin by evaluating the ARARs List for applicability or relevance and appropriateness. Once the ARARs are narrowed, the final presentation and determination will occur in conjunction with approval of the decision document. ARARs interpretations during actions will be accomplished using the consultative process. Where documentation is warranted, TMs will be prepared.

3.5.3 Exemption From Administrative Requirements of ARARs

CERCLA and RFCA require compliance with substantive, not administrative, ARARs. (See 40 CFR §300.5, definition of *Relevant and Appropriate Requirements*). EPA recognizes that, in some circumstances, the distinction between administrative and substantive requirements is not clear. To address this, EPA described the problem and factors to consider as follow:

In most cases, the classification of a particular requirement as substantive or administrative will be clear, but some requirements may fall into a gray area between the provisions related primarily to program administration and those concerned primarily with environmental and human health goals. Several factors may be considered when it is not readily apparent whether a requirement is substantive or administrative; for example, the basic purpose of the requirement, any adverse effect on the ability of the actions to protect human health and the environment if the requirement were not met, the existence of other requirements (e.g. CERCLA procedures) at the site that would provide functionally equivalent compliance, and classification of similar or identical requirements as substantive or administrative in other situations. The determination of whether a requirement is substantive or administrative need not be documented.

(See preamble to the proposed NCP, 53 FR 51443, middle column, center).

3.5.4 RFCA Permit Waiver

RFCA ¶16 provides a waiver from permitting for response activities conducted entirely on the Site. The response activities eligible for the permit waiver include:

- Removal or remedial actions in the Buffer Zone
- Decommissioning activities
- Activities under any concurrence CAD/ROD

- Remedial actions in the Industrial Area for hazardous substances that are not also hazardous wastes or hazardous constituents (e.g., radionuclides that are not mixed wastes and PCBs)

In order to take the permit waiver, DOE must include in a submittal:

- An identification of each permit that will be exempt
- An identification of the standards, requirements, criteria, or limitations which would have had to have been met to obtain the permit
- An explanation of how the response action proposed will meet the standards, requirements, criteria, or limitations otherwise required by the permit

3.6 RISK EVALUATION

The evaluation of human health and ecological risk is central to the implementation of the RFCA. ¶B2a of the RFCA preamble states that controlling the sources of contamination will be the priority of the ER Program. Unacceptable risk will be reduced by remediation or management actions. Risk reduction is best achieved through the risk assessment process.

Under the authority of CERCLA, the EPA has developed guidelines for the evaluation of human health and ecological risks and hazards (EPA, 1994b). Site-specific guidance and parameters to be used in risk evaluations have been negotiated among the DOE RFFO, the EPA, and the CDPHE (DOE 1995b, 1995d, 1995e, Appendix P). The site-specific guidance and parameters have been used and approved in a series of OU-specific BRAs (DOE 1995f, 1995g, 1996c, 1996d). This section documents agreed upon risk methods and parameters, and the points at which they may be applied in the risk management process defined by RFCA and the ALF.

The ALF defines action levels as "numeric levels of contamination in , surface water, and soils which, when exceeded, trigger an evaluation, remedial action, and/or management action". A major component of any evaluation should be a detailed assessment of the risks associated with exceeding the action level. Management decisions and remedial actions should be based on a detailed knowledge of the risks to human health and the environment. The site-specific Human Health Risk Assessment Methodology (HHRAM) (DOE, 1995b) coupled with the ERAM (DOE 1996a, 1996b) provide the necessary tools. The risk assessment methodology also includes the conservative screen developed by the CDPHE and agreed to by the DOE (DOE, 1994a). These methodologies are discussed in more detail in Appendix K.

3.6.1 Implementation of Risk Assessment Methodologies Within the RFCA Framework

When a Tier I or Tier II action level for surface soil, subsurface soil, or is exceeded using single data point comparisons to action levels, the AOC is placed in the ER Ranking System and risk management options are evaluated. The sequence to be followed for action level comparisons is detailed in Section 3.7. Once it is determined that a Tier I or Tier II action level is exceeded, further risk evaluation may be needed depending upon the complexity of the site under consideration.

Action levels for non-radiological chemicals are predominantly risk-based, except for organics in subsurface soils which are calculated to be protective of and surface water uses. Action levels for radionuclides in and surface water are risk-based. Action levels for radionuclides in soils are dose-based. In accordance with ALF, chemical risk is considered to be additive when multiple chemicals are present, and radiological dose is additive when multiple radionuclides are present. The method for applying action levels when multiple contaminants are present is explained in Section 3.7.

The risk manager must be sure decisions are made using cumulative risk when multiple contaminants are present at a site. After aggregated data are compared to Tier I and Tier II action levels (see Section 3.7), a simple screening level risk assessment, using appropriate receptors and exposure factors, may be used to ensure remedial action decisions have a firm risk-based component. A situation in which a risk screen would be appropriate would be when the results of the action level comparison are very close to Tier I or Tier II breakpoints.

To perform the screening level assessment, the AOC is chosen and the data are aggregated by the methods agreed to for the site-specific HHRAM. The potential contaminants of concern can be chosen using a simplified background comparison (see Appendix K), and the exposure concentration calculated using the 95% upper confidence limit (UCL95) on the arithmetic mean concentration of contaminants within the AOC. If the estimated risks are below 1×10^{-6} and the hazard index less than one, the AOC may become a candidate for an NFA recommendation. If the risk is greater than or near 1×10^{-4} , an accelerated action may be necessary. If the risk between 1×10^{-6} and 1×10^{-4} , then a more detailed risk evaluation is warranted to ensure that an appropriate risk management decision is made. This detailed evaluation may be deferred to the CRA rather than generating multiple risk evaluations. Results of the screening level risk assessment should be reported in a condensed format (e.g., a letter report or TM).

3.6.2 Environmental Restoration Ranking

ER projects are prioritized based on an approved methodology for producing a risk-based ranking. (See RFCA ¶74). The methodology reflects the RFCA and ALF. (See Section 3.7 and Appendix N). Areas may also be added to the ranking as information from action level comparisons or risk assessments become available.

3.6.3 Comprehensive Risk Assessment

Part 8 of the RFCA states that after all accelerated actions have been completed, Site conditions, including residual risk from accelerated actions, will be evaluated and corrective/remedial action decisions will be rendered as appropriate. The preamble to the NCP discusses risk in the remedy selection process in 40 CFR 300.430(e). The preamble at 55 FR 8712 states, "*EPA selects remedies resulting in cumulative risks that fall within a range of 10^{-4} to 10^{-6} .*" OSWER Directive 9355.0-30 (EPA, 1991) more specifically states that, "*(f)or sites where the cumulative site risk to an individual based on reasonable maximum exposure for both current and future land use is less than 10^{-4} , action is generally not warranted....*" These statements are consistent with the agencies' position that a CRA must be completed, including an evaluation of the contribution of all sources of risks and hazards to off-site receptors, before a final CAD/ROD for the Industrial Area and Buffer Zone can be accepted.

The protectiveness of the final remedy to human health and the environment must be measured by evaluating the cumulative risk for the entire site. The CRA is the mechanism that can provide the answers needed for closure of the Site. The two alternative approaches that could be chosen for performance of the CRA are outlined below.

1. The CRA may be undertaken concurrent with remediation activities in the Buffer Zone and the Industrial Area. Performed in this manner, the CRA would be a living document and updated as remediation progresses. It would be used for directing resources toward remediation targets to reduce the cumulative risk to an acceptable level. The CRA would be a management tool to expedite closure and reduce unnecessary remedial activities.
2. The CRA could be done after all building disposition, waste removal, and remediation have taken place. Performed in this manner, the CRA would only be used for the final CAD/ROD to ensure no cumulative residual risks from RFETS to human health or the environment.

The methodology for performing the RFETS site-wide risk assessment has not been finalized. It has not been determined if the CRA will be done as two modules, one for the Buffer Zone and one for the Industrial Area, or if it will be performed for the entire Site at one time. If a modular approach is used, care must be taken that the modules can be combined for the final estimates of risk to appropriate on-site receptors, environmental hazard, and for modeling of effects to , surface water, and off-site receptors. The RFETS HHRA will be used as the starting point for developing an appropriate methodology for the CRA. The exposure scenarios and factors previously agreed upon will also be used. The procedure for data aggregation and determination of how source areas will be combined for evaluation must be decided by the RFCA Parties.

3.6.4 Radiological Dose Evaluations

Radiological dose evaluations of residual radioactive materials are required to ensure protection of public health under DOE Order 5400.5 (DOE, 1990) and to implement DOE's "as low as reasonably achievable" (ALARA) policy. DOE, EPA and CDPHE have agreed to use EPA's draft *Radiation Site Cleanup Regulations* (EPA, 1996c) for calculation of radionuclide action levels in soils. To be consistent with the RFCA and the ALF, all dose calculations will be done using RESRAD, the computer code the Argonne National Laboratory developed for DOE to facilitate the implementation of residual radioactive materials guidelines, and site-specific exposure scenarios, exposure factors, and environmental parameters. A detailed explanation of the derivation of radionuclide action levels for soils is provided in the Action Levels for Radionuclides in Soils (Appendix L).

3.6.5 Cumulative Effects between Dose and Risk

Action levels for non-radionuclide chemicals are risk-based, and chemical risk is considered additive when multiple chemicals are present. Radionuclide action levels are dose-based and radiation dose is considered additive when multiple radionuclides are present. Radionuclides and non-radionuclides will be assessed independently on a project-specific basis using methodology that is protective of human health and the environment. The Parties will consult regarding whether it is appropriate to assess the cumulative effects of radionuclides and non-radionuclide chemicals on a project-specific basis if the chemical risk and radiation doses are near their respective Tier I action levels.

3.7 THE ACTION LEVELS AND STANDARDS FRAMEWORK

3.7.1 Background

The goals of the ALF are to:

- Provide a basis for future decision making
- Define the common expectations for all parties
- Incorporate land and water use control into Site cleanup

The purpose of the action level is to:

- Trigger an evaluation, remedial action, or management action
- Serve as interim cleanup levels, when appropriate
- Provide "put-back" levels for interim soil removals
- As defined in the ALF:

Action levels are numeric levels that, when exceeded, trigger an evaluation, remedial action, and/or management action. Final cleanup levels will be determined in the

CAD/ROD. For interim remedial actions, interim cleanup levels will equal Tier 1 action levels unless some other ALF provision requires a greater level of cleanup (e.g., protection of surface water)... A standard is an enforceable narrative and/or numeric restriction established by regulation and applied so as to protect one or more existing or potential future uses. Within this framework, standards are associated with surface water use classifications and applied at points of compliance (POCs). Standards are not being directly applied to or soils.

The surface water standards are based on promulgated state surface water quality standards below the terminal ponds and are applied as action levels above the terminal ponds. The action levels for are based on the maximum contaminant levels (MCLs). For those chemical constituents without MCLs or standards, these action levels are based on programmatic preliminary remediation goals (PPRGs). PPRGs are chemical-specific and medium-specific risk-based concentrations calculated for each exposure scenario (e.g., office worker, open space recreational user) using site-specific exposure factors, standard toxicity factors, and a carcinogenic risk level of 1×10^{-6} , or a hazard index of 1 for non-carcinogenic compounds. (See Appendix P for PPRG Tables)

The action levels for surface soils were developed to be protective of human exposure under the designated land use conditions. The PPRGs are used as action levels for all non-radionuclides. Action levels for radionuclides in surface soil are based on the 15/85 mrem per year dose limits, consistent with EPA's draft Radiation Site Cleanup Regulations, and DOE's proposed rule to be codified at 10 CFR 834 (58 FR 16268).

Subsurface soil action levels for many organics were developed to be protective of using the EPA Soil Screening Guidance (EPA, 1996a, 1996b). For the PPRGs, metals, radionuclides and some organics, the subsurface soil samples were set equal to surface soil action levels.

3.7.2 Application of the Action Levels to Trigger Interim Actions

Surface Water and

The application of the ALF to surface water and monitoring is described in detail in the IMP. The application of ALF to the portion of the IMP is shown in Figure 3-8.

Appendix M provides a "process description" as the approach to integrate the goals and objectives of monitoring, hydrogeologic characterization, and remedial actions at RFETS. The intent of this "process description" is not to prescribe specific analyses that must be performed, but to present a general approach that defines how contamination at RFETS will be assessed and addressed. By developing an integrated process, the basis for decisions regarding the need for remediation and the evaluation of remediation performance should be consistent, and will effectively protect surface water and ecological resources.




Figure 3-8 Application of Groundwater Action Levels Through the Integrated Monitoring Plan

The IMP describes the routine site-wide monitoring programs for surface water, , air, and ecology. Sampling locations, frequency, analyte suites, and reporting requirements are provided for each media. The IMP implements additional sampling if Tier II action levels are exceeded or if surface water action levels/standards are exceeded at POCs.

For those constituents for which background levels exceed the Tier I and Tier II action levels, the defacto action level is the background mean plus two standard deviations. In that instance, more frequent sampling and remediation will not be triggered by exceeding the action level. Examples under discussion are uranium (all isotopes) and manganese. Background values are being developed using available data.

Soil

The application of soil action levels to trigger interim actions requires a multi-step approach which includes: soil data value comparison, determination of the AOC, aggregation of the data and comparison to the action levels, evaluation of options including additional characterization (as needed), and selection of management options. An overview of evaluation options available after the initial single data point comparison is shown in Figure 3-9.

Step 1: Soil Data Value Comparison

The sequence for comparison of soil action levels to single soil data values is shown below.

- Compare each soil data value to the appropriate action level
- Compare each soil data value to the background mean plus 2 standard deviations
- Tier I exceedance
 - the ratio of each soil data value to the Tier I action level is > 1 , or
 - the sum of the ratios for either non-radionuclides or radionuclides is > 1
- Tier II exceedance
 - the ratio of each soil data value to the Tier II action level is > 1 , or
 - the sum of the ratios for either non-radionuclides or radionuclides is > 1
- Below Tier II and above background or conservative screen
 - the ratio of each soil data value to the Tier II action level is < 1 , or
 - the sum of the ratios for either non-radionuclides or radionuclides is < 1

Further evaluation is necessary for sites with soil data values exceeding Tier I action levels to determine whether remediation is necessary.




Figure 3-9 Evaluation Options After Data Point Comparison

Step 2: Data Aggregation

The spacial extent of contamination must be known for a remedial action to be planned and undertaken. The AOC is determined for this purpose. When an evaluation of a Tier I exceedance shows an area of very limited extent (e.g., a "hot spot"), data aggregation may not be appropriate, and an action may be performed. The AOC is determined and the data aggregated as follows:

- Determine AOC with respect to Tier I and Tier II action levels using comparison to:
 - background mean plus 2 standard deviations for inorganics
 - detection limits for organics
 - AOCs will be established based on the spacial data distribution
 - here is no lower limit on the size of an AOC, but no single AOC shall exceed 10 acres
- Average data over the AOC, as appropriate
- Use the UCL95 of the mean for comparison to the appropriate action level

Step 3: Evaluation Options

Other evaluation options shown in Figure 3-9 include further characterization or a more detailed risk analysis. If the amount of data available for a site is limited, then further characterization may be required. If the result of the action level screen, after data aggregation, is near the breakpoint of Tier I or Tier II, then a more detailed risk assessment may be performed to better define the appropriate action. If the results of the action level comparison are below Tier II, then it may be appropriate to apply the conservative screen to determine NFA status (Section 3.1.4).

Step 4: Management Options

Various management options are available for source areas depending on the outcome of the action level evaluation and the media. These are detailed in RFCA Attachment 5. (A general discussion is presented in RFCA Attachment 5, Section 1.3, and action determinations for subsurface and surface soils are detailed in Section 4.3 and for soils in Section 5.3, respectively.)

3.7.3 Performance Objectives

As stated in RFCA, Attachment 5, interim cleanup levels for interim remedial actions will equal Tier I action levels unless a provision of ALF, such as protection of surface water, requires a lower remediation goal. Each project will define its specific remediation goals in the appropriate decision document.

3.8 ANNUAL REVIEWS AND UPDATES

3.8.1 Annual Updates of the Environmental Restoration Ranking

In accordance with RFCA Attachment 4, the ER ranking will be updated annually, or more frequently if significant new information or updated action levels become available. If no cleanup or investigation activities occur within a fiscal year, the ranking will not be updated that year. With the consensus of all parties, the priority of any ER site can be changed before updating the list, if additional information indicates that this is required.

The original methodology was refined for the 1996 report in order to make it compatible with RFCA and ALF. Appendix N presents the general methodology for ranking ER sites including media-specific evaluations and chemical score tabulation. The methodology produces a prioritized list of ER sites, and includes both a list of sites that require more information and a list of sites awaiting final disposition. The prioritization focuses the cleanup process, making it possible to address high-risk sites before low-risk sites, thus more quickly reducing risks to human health and the environment. The prioritization of cleanup targets results in a reduction of costs associated with cleanup by allowing better planning and more efficient utilization of resources. The 1997 ranking was completed in September, 1997 (K-H, 1997a).

3.8.2 Annual Updates for the Historical Release Report

The HRR is required by CERCLA §103(c) to describe the known, suspected or likely releases of hazardous substances from RFETS. Original authorization for the HRR was provided in Section I.B.5 of the IAG (DOE, 1991). The HRR, which was published in June 1992, provided a complete listing of all known spills, releases, and/or incidents involving hazardous substances that had occurred since the inception of RFETS. Section I.B.3 of the IAG established the requirement for DOE RFFO to notify EPA and CDPHE of any newly-identified or suspected releases or threats of release at RFETS, which may threaten human health or the environment. HRR updates were initially required every three months; however, all three parties to the IAG have agreed that DOE RFFO can submit HRR updates annually. The first annual HRR update report was delivered on August 30, 1996.

The process for updating the HRR has been developed through negotiations and document reviews by DOE RFFO, EPA, and CDPHE. As shown in the example presented in Appendix O, the document format includes: a description of the release event; complete physical and chemical descriptions of the constituents released; validated analytical data; responses to the events; fate of the constituents released; action/no action recommendations; comments; and a reference section. Additionally, signature lines for DOE, EPA, and CDPHE concurrence are provided in the HRR updates.

Among other purposes, the HRR updates serve as a basis for approving soil disturbance permits; as an aid in making waste determinations; and as an aid in deciding the appropriate level of personal protection equipment for work in an IHSS. RFCA Attachment 6, No

Action/No Further Action/No Further Remedial Action Decision Criteria for RFETS, expands the scope of the HRR updates to include information on geographic areas for which a NFA recommendation is warranted. HRR updates were selected as the vehicle for recommending NFA decisions, tracking IHSS status (e.g., boundary changes), and communicating IHSS information (e.g., analytical information for waste determinations required by EPA and CDPHE).

The NFA decisions recommended in the HRR updates are intended to be "place keepers." An IHSS can be placed on hold until the NFA working group or another appropriate body agrees that initiating the OU-wide administrative process (PP, CAD/ROD, RCRA Permit Modification, etc.) for IHSS closure is beneficial.

3.8.3 RFCA Annual Review

RFCA ¶5 states that:

The Parties shall conduct an annual review of all applicable new and revised statutes and regulations and written policy and guidance to determine if an amendment pursuant to Part 19 (Amendment of Agreement) is necessary.

The RFCA Annual Review is completed by July 19 each year by reviewing Attachment 5 and the following major environmental laws, and associated regulations, written policy, and guidance:

- CERCLA
- RCRA
- TSCA
- CWA
- Clean Air Act (CAA)
- NEPA
- Ecology (e.g. Endangered Species Act)
- Radiation
- Radioactive Waste
- Defense Authorization Acts and Appropriation Acts

Questions which should be addressed for each area during the review are:

- Are there any new or revised statutes, regulations, written policy, or guidance
- Has the change been implemented at the Site
- Does it need to be implemented
- Does the change impact RFCA and is an amendment required

The annual review prescribed in RFCA paragraph 5 is sometimes referred to as the "Regulatory Review."

In addition to the annual review prescribed in RFCA paragraph 5, the RFCA Parties committed to conducting an internal annual review of the radionuclide soil action levels (RSALS). Questions to be addressed on an annual basis include:

- Is there new scientific information available that would impact the interim action levels
- Has a national soil action level been promulgated within the year? If yes, the parties commit to revisit RFETS interim action levels
- How were the interim action levels applied to the site over the course of the year
- Have the remedies been effective

For more details, see the Responsiveness Summary for Soil Action Levels released on November 6, 1996.

While not required by RFCA, the RFCA Project Coordinators invite the public to submit any new information relevant to the RFCA or RSALS for these reviews during a 60-day comment period. A public meeting by the RFCA Project coordinators will be held if requested.

The results of the annual regulatory review and the annual RSAL review are combined and documented in a RFCA Annual Review report which is completed by the end of August.

In addition to the regulatory annual review and the RSAL annual review, RFCA requires the following items also be reviewed on an annual basis:

IMP (¶267)
Integrated Public Involvement Plan (¶ 281 (g))
ER Ranking (¶ 79)
AR (¶ 284)
Milestones (¶ 147)
Target Activities (¶ 136)
Summary Level Baseline (¶141)
ALF (¶ 5)
HRR (¶119(1))

An annual review commitment is discussed in the IWMP and the IGD.

For more details on the annual review past processes, see the 1998 RFCA Regulatory/Radionuclide Soil Action Levels Annual Review Report.

3.8.4 RFCA Biennial Review

RFCA ¶257 states that:

The parties shall assess the implementation of the Agreement every two years with the first assessment being conducted no later than the second anniversary date of the

execution of this Agreement. In this assessment, the parties shall conduct a review of the substantive and procedural requirements for this Agreement, including but not limited to the regulatory approach set forth in Part 8, to determine what measures each Party will take to ensure effective implementation of this Agreement. Such measures may include reallocation of resources, internal reorganization, revised procedures for consultation or internal coordination, and additional training of appropriate staff.

The RFCA Biennial Review will be completed by the second anniversary date of the execution of RFCA (by July 19, 1998) and every two years thereafter. The Biennial review is accomplished by establishing a RFCA Party assessment team charged with evaluating the progress at the Site during the past two years. The assessment team may conduct interviews and/or file and document reviews of parties responsible for the implementation and progress of RFCA and parties who were involved with the initial negotiations of the agreement.

For more details on the biennial review past processes, see the 1998 RFCA Biennial Review Assessment Report.

3.9 DISPUTES

Part 15 of the RFCA enumerates procedures for dispute resolution. RFCA directs the parties to attempt first to resolve disputes informally. Where the dispute cannot be informally resolved, the RFCA directs the parties to raise the disputed issue quickly. The types of disputes identified in the RFCA include:

- Disapproval of a proposed final document (RFCA ¶s 115, 188)
- Denial or partial grant of a change requested for a regulatory milestone (RFCA ¶s 169, 188)
- Stop work orders (RFCA ¶s 176, 188)
- Force majeure (RFCA ¶175)
- Permit waivers (RFCA ¶16)
- Proposed permit modifications (RFCA ¶s 22, 188)
- Accelerated Actions (RFCA ¶69)
- Decommissioning (RFCA ¶69)
- Determinations that conditions or activities constitute a release or threat of release (RFCA ¶69)
- Corrective Action Management Unit (RFCA ¶82)
- Additional work required under CERCLA (RFCA ¶200)
- RFCA interpretation or implementation (RFCA ¶189)
- Amendments to RFCA (RFCA ¶190)
- IMP (RFCA ¶188)
- Imposition of fees by CDPHE (RFCA ¶188)

The RFCA also identifies five classes of disputes and specifies the procedures for each. The five classes of disputes include:

- Decisions by lead regulatory agencies
- Disputes regarding additional work required under CERCLA
- Disputes regarding budget and work planning
- EPA-State disputes regarding Site-wide issues
- Disputes regarding overall direction of proposed work

More specifics may be included in the future based on the results of the RFCA Biennial review concerning timing of disputes and recognizing issues as a dispute.

3.9.1 Disputes Regarding Decisions By Lead Regulatory Agencies

The RFCA creates two organizations to perform dispute resolution. The Dispute Resolution Committee (DRC) consists of the following individuals:

- CDPHE – Hazardous Waste and Materials Management Division Director
- DOE – Assistant Manager for Environmental Compliance, RFFO
- EPA – Region VIII Assistant Regional Administrator for Ecosystems Protection and Remediation

The DRC is the first level of formal dispute resolution. The second level of dispute resolution is the Senior Executive Committee (SEC). The SEC consists of the following individuals:

- CDPHE – Director, Office of Environment
- EPA – Assistant Regional Administrator
- DOE – Manager, RFFO

The SEC receives disputes that the DRC has unanimously elevated without resolution or disputes that the DRC has resolved but are under appeal. A schematic of the process is provided in Figure 3-10.

3.9.2 Disputes Regarding Additional Work Required Under CERCLA

Disputes regarding additional work required under CERCLA follow the basic procedures outlined in Figure 3-10. Authority to review appeals of SEC decisions is controlled by RFCA ¶69.

3.9.3 Disputes Regarding Budget and Work Planning

DOE disputes regarding budget and work planning employ the procedures diagrammed in Figure 3-11.




Figure 3-10 Disputes Regarding Decisions by the Lead Regulatory Agency




Figure 3-11 Disputes Regarding Budget and Work Planning

3.9.4 EPA-State Disputes Regarding Site-wide Issues

For purposes of EPA-State disputes regarding site-wide issues, the State-EPA Dispute Resolution Committee (SEDRC) and the State-EPA Senior Executive Committee (SESEC) have the same composition as the DRC and SEC except the DOE does not vote on those committees. The RFCA identifies the following as site-wide issues:

- PP/draft permit modifications
- CADs/RODs
- Updates to the ER Ranking
- Updates to the IGD
- Future RSOPs for activities regulated under this agreement that are related to more than one OU
- Treatment systems that will treat wastes from the Industrial Area and the Buffer Zone
- Treatability study reports for activities that are related to more than one OU
- IMP
- Updates to the Rocky Flats Sitewide Integrated Public Involvement Plan (RFSIPIP)
- Updates to the HRR

For a complete listing of sitewide issues see ¶207 of RFCA. DOE disputes regarding site-wide issues employ the procedures diagrammed in Figure 3-12.

3.9.5 Disputes Regarding Overall Direction of Proposed Work

If one of the project coordinators is unable to concur with the overall direction of proposed work, dispute resolution employs the procedures outlined in Section 3.9.1 with minor changes. (See RFCA ¶214).

3.10 MODIFICATION OF DECISION DOCUMENTS

The RFCA identifies three types of decision modifications: major modifications; minor modifications; and field modifications.

3.10.1 Major Modifications

Major modifications represent a significant departure from the approved decision document. RFCA defines major modifications as follows:

[A] modification to work that constitutes a significant departure from the approved decision document or the basis by which a decision was previously made or approved, e.g., a change in a selected remedial technology, a technical impracticability determination or a significant change to the performance of Standard Operating Procedures (SOP) (e.g., a tank closure that results in closure




Figure 3-12 EPA/CDPHE Disputes Regarding Site-wide Issues

*in place versus removal) that fundamentally alters the pre-approved procedure.
(See RFCA ¶25ar).*

Major modifications to work being done pursuant to a CAD/ROD are accomplished by submitting a written request with justification not less than 90 days prior to executing the change. Concurrently, public notice will be provided followed by opportunity for a 30-day public comment period. Following the public comment, the LRA will, if appropriate, approve the change or deny it and provide written explanation no longer than 30 days after the close of public comment.

Major modifications to work being done pursuant to an IM/IRA are accomplished by submitting a written request with justification not less than 30 days prior to executing the change. The LRA will, if appropriate, approve the change or deny it within 21 days of receipt. For PAMs, the written request must be received no less than 14 days prior to executing the change, and the LRA will approve or deny the change within 7 days.

3.10.2 Minor Modifications

Minor modifications are changes that achieve substantially the same level of performance using a different technique. In effect, the change does not affect the final result of the activity. The RFCA defines minor modification as follows:

*[A] modification that achieves a substantially equivalent level of protection of workers and the environment and does not constitute a significant departure from the approved decision document or the basis by which a decision was previously made or approved, but may alter techniques or procedures by which the work is completed, e.g., a change in an RSOP that does not change the final result of the activity (e.g., alteration to a tank closure procedure that still results in a clean closure), or a change in operation or capacity of a treatment system that does not cause the system to exceed an effluent limit.
(See RFCA ¶25as).*

Minor modifications to work being done pursuant to a PAM are accomplished by submitting a written notification with justification not less than 7 days prior to executing the change. Prior approval of a minor modification is not required. If the LRA disputes the appropriateness of a minor modification, a stop work order by the LRA must be issued within seven days of notification.

Minor modifications to work being done pursuant to an IM/IRA are accomplished by submitting a written request with justification not less than 21 days prior to executing the change. For an IM/IRA the LRA will approve the change or deny it with an explanation in writing within seven days of receipt. In appropriate circumstances, the LRA may waive the 21-day waiting period.

3.10.3 Field Modifications

A field modification is allowed when unanticipated conditions are encountered. Field modifications are permitted, without prior approval, to avoid an imminent threat to human health or safety of the environment, prevent undue delay, or where a cost-effective alternative approach to the safe and protective execution of work is identified. (See RFCA ¶25ag).

Field modifications require DOE project coordinators give verbal notice to the LRA within one day of making the modification and follow the verbal notice with a written justification within seven days. The LRA may issue a stop work order within seven days of the notification if the work is: inadequate or defective, likely to have substantial adverse impacts on other response action selection or implementation processes, or likely to significantly affect cost, scope, or schedule and requires further evaluation.

3.11 NPL DELISTING

The NPL delisting process begins upon approval and acceptance of the Buffer Zone and Industrial Area CAD/RODs. There are five steps in the delisting process:

- Preparation of the Notice of Intent to Delete with EPA and State review and approval
- Publication of the Notice of Intent to Delete in the Federal Register for public comment
- Publication of the Notice of Availability for the Notice of Intent to Delete
- Publication of the Notice of Deletion along with the comment responsiveness summary in the Federal Register
- Placement of the final information package in local information repositories

It is possible to partially delist those portions of the site where NFAs or remedies involving institution controls have been implemented. Deletion of the site from the NPL may occur before the cessation of operation and maintenance activities specified in the CAD/ROD. Additionally, five-year reviews may be required after delisting.

3.12 SOIL MANAGEMENT

(Reserved)

3.13 WATER MANAGEMENT

The IA IM/IRA (DOE 1994c) defines incidental waters to include any waters that may accumulate in excavation sites, pits, trenches or ditches, secondary containments or berms, process waste valve vaults, electrical vaults, steam pits and other utility pits and or telephone manholes. Incidental waters also include fire suppression system discharges and the natural collection of precipitation and stormwater runoff in excavation pits, trenches and depressions. The IA IM/IRA authorizes management of incidental waters using currently available water

treatment systems. See Section 2.6.2 for a complete discussion of wastewater and incidental water management options and procedures.

3.14 INTEGRATED MONITORING PLAN

RFCA Part 21 Sections 267 and 268 require the development of an IMP which collects and reports the data required to ensure the protection of human health and the environment consistent with the Preamble, and which is compliant with RFCA, laws, and regulations, and the effective management of RFETS resources.

The IMP describes Site monitoring performed for a variety of legal, contractual, and operational purposes and states the agreed-upon types of monitoring, monitoring locations, sampling frequencies, and purposes of monitoring. In some instances, the IMP includes monitoring that is already required outside of RFCA. The IMP is designed to provide data to support operational and regulatory decisions, and address the following primary regulatory drivers:

- RCRA
- CERCLA
- CAA
- CWA
- Colorado Water Quality Control Commission standards
- Regulations governing natural resource (ecological) management
- Site-specific monitoring and cleanup agreements
- DOE Orders and technical guidance

The IMP Background Document provides additional information on the DQO decision process and the regulatory framework that drives many of the monitoring decisions at the Site, as well as QA/QC requirements. The IMP Background Document is not subject to enforcement under RFCA.

The monitoring program outlined by the IMP reports exceedences of the ALF which may lead to active management or remediation. Following implementation of management/remedial actions, the IMP is re-engaged to conduct performance monitoring in accordance with the applicable decision document.

RFCA also specifies that the IMP will be jointly reviewed annually "based on previous monitoring results, changed conditions, planned activities and public input." Changes to the IMP are subject to approval of the EPA and CDPHE.

The prescribed monitoring is performed in four primary areas: surface water, air, and ecological systems. A fifth medium, soil, interacts with each of the other media and is also discussed in the IMP, but since soil is no longer routinely monitored, the discussion of soil mainly concerns project-specific sampling.

3.14.1 Surface Water Monitoring

Surface water monitoring encompasses five areas:

1. Site-wide water quality
2. Quality of waters within the Industrial Area
3. Quality of discharges from the Industrial Area
4. Quality of water leaving the site
5. Off-site water quality

3.14.2 Monitoring

The monitoring program is designed to accomplish the following:

- Detect and identify contaminants in , and monitor their concentrations
- Identify contaminant sources, and monitor remediation efforts
- Delineate contaminant pathways
- Assess the effects of Site remediation and closure activities
- Protect from new sources of contamination
- Evaluate any effects of contaminated on surface water

3.14.3 Air Quality Monitoring

The air monitoring activities on the Site assist in protecting the public and the environment by detecting and tracking the impacts of Site operations on air quality at and near the Site, characterizing any air borne materials (radiological or non-radiological) that may be introduced, and monitoring the meteorological conditions that influence the transport and dispersion of airborne materials.

3.14.4 Ecological Monitoring

Ecological monitoring is designed to protect wildlife in the Buffer Zone, including any special-concern species (i.e., threatened, endangered, candidate, proposed, state-listed, or other sensitive species). In addition to the terrestrial vegetation communities, the aquatic communities of the riparian channels and ponds at the Site are monitored for ecological health.

4.0 ADMINISTRATION

This section provides an overview of the following:

- The Federal budgeting process
- Requirements for budget planning and authorization
- Controlling a project
- Compilation of the AR
- Records management and document control
- Reporting requirements

Section 4.0 has been written in conjunction with RFCA and RFETS standard policies and practices which provide policy and procedural direction for the diverse administrative functions performed at RFETS. The referenced plans, procedures, and documents are intended to supplement the guidance and minimum requirements presented in this section.

4.1 BUDGET PLANNING AND EXECUTION

All RFETS budgeting is performed in accordance with approved RFETS budget planning, formulation, and execution procedures. A summary of the budget planning and execution process is provided on Figure 4-1, General Timeline for Budget, RFETS CPB, RFCA Milestones, and K-H Performance Measures.

Funding at RFETS is based on the Fiscal Year (FY) cycle. The federal FY starts on October 1 and ends on September 30 of the following year. The FY is designated by the calendar year in which it ends. At any given time, four FYs are under consideration:

- PY – Prior Year (the previous FY completed)
- FY (the current FY or the execution year)
- FY+1 (also called the budget year) – where Congress considers DOE's budget request
- FY+2 (the first planning year) – where RFETS activity requirements are identified
- FY+3 through FY+5 (and beyond for some activities) – where budget plans are developed

The budget process has three main phases: (1) executive budget formulation and transmittal, (2) Congressional action, and (3) budget execution and control.

4.1.1. Executive Budget Formulation and Transmittal

The budget formulation process begins at least 14 - 18 months before the budget request is transmitted to Congress by the President. DOE RFFO prepares its budget request based on the guidelines provided by the President through the Office of Management and Budget (OMB) and through DOE Headquarters (HQ). (See Figure 4-2).

General Timeline for Budget, PCB, RFCA Milestones and K-H Performance Measures

	October	November	December	January	February	March	April	May	June	July	August	September	October	November	December
Federal Budget Process (Row A)	DOE-HQ and OMB negotiate FY+1 budget based on DOE FY+2 submit the previous spring (B-4). (May include preliminary input on next FY+2 budget.)				President submits FY+1 budget.	Congressional appropriations hearings, and negotiations with DOE and OMB.						President signs FY+1 federal appropriations bills into law.			
RFETS Budget/Planning (Row B)		RFEO gets FY+2 planning, budget call from HQ. (Oct-Nov)	RFEO reviews and updates FY+2 budget, including any additional work, and 2006 Closure Plan, receives input from President's FY+1 budget submittal (A-2).			RFEO gives Kaiser-Hill Program Execution Guidance for FY+1.	RFEO submits FY+2 budget to DOE-HQ. DOE-HQ documents revisions.		RFEO finalizes FY+1 baseline budget, with input from DOE-HQ (A-4).			RFEO sets FY+1 baseline budget, with input from DOE-HQ (A-4).			
Closure Project Baseline (CPB) (Row C)			RFEO and Kaiser-Hill budget and planning staffs revise draft CPB based on approved Baseline Change Actions.												
RFCA Milestones & Target Activities (Row D)			RFEO, after consulting with Parties and CAB, proposes FY+2 activities and priorities.	Parties agree, or regulators set, FY+2 Milestones and Target Activities.	Dispute Resolution begins for disputed Milestones and Target Activities.		EPA and CDPHE set FY+2 Milestones even if no consensus exists.		Revised FY+1, +2 LOB mult. scenarios (B-2), D-4, D-9) (C-2) (B-6) (C-3)	Informal DRC-level meeting to evaluate FY+1, +2 Milestones and Target Activities.		Final FY+1 agreement; input from final budget (B-7).	FY budget allocation; Parties consult on FY, FY+1 Milestones and Target Activities.	Re-establish FY, FY+1 Milestones and Target Activities, or begin Dispute Process.	
Kaiser-Hill Performance Measures (Row E)										Negotiate FY+1 PMs, starting July 1. (Includes DOE-HQ approval.)		Final FY+1 PMs; requires step B-7 (May extend into FY)			
Regulatory Agency Reviews (Row F)		RFEO tells Parties and CAB of FY+2 budget call (B-1). (E-1)		RFEO shares FY+1 budget, based on A-2.	RFEO briefs Parties on FY+1 impacts.				Parties evaluate current FY projects, especially those critical to RFCA Milestones.						

Note: Arrows (→) highlight some flows of information.

J. Morris, RFFO (966-7198), and J. Schneider, RFFO (966-5924), 2/6/98




Figure 4-2 The Federal (DOE) Budget Execution Process

The budget is developed in the context of a multi-year budget planning system that includes coverage of the current FY as well as the FYs beyond FY+1. In FY 1997, the planning process was expanded to include coverage of all project years required to complete the RFETS mission and is not limited to four FYs. The system requires that broad budgetary goals, agency spending, and employment targets be established beyond the budget year.

During the formulation of the budget, there is a continual exchange of information, proposals, evaluations, and policy decisions among DOE RFFO staff, DOE HQ, OMB, and the President. Decisions concerning the upcoming budget are influenced by the results of budget validation reviews, previously enacted budgets (including the one being executed by the agencies), and the reactions to the last proposed budget under consideration by Congress. In accordance with current law, the President submits final agency budget requests to Congress no later than the first Monday in February.

4.1.2 Congressional Action

Between February and September 30, Congress is considering all federal agency budget requests. If Congress does not complete its work before the start of the FY (October 1), then a Continuing Resolution (CR) may be enacted for a given amount of time to keep agencies operating at the same level as the prior FY. During a CR, no new projects or activities may be started.

At any time, Congress can change funding levels, eliminate programs, enact legislation that authorizes an agency to carry out a program, or add programs not requested by the President or an agency. After the appropriation process, the program may be realigned through a reprogramming request. Both actions require OMB and Congressional approval.

4.1.3 Budget Execution and Control

Once approved, the President's budget, as modified by Congress, becomes the basis of the financial plan for the operations of each agency during the FY. The sequence is as follows:

- The Director of OMB apportions appropriation (funding) to DOE HQ by time periods and by activities
- DOE HQ allocates funds to the various sites across the DOE complex

For the remainder of the FY, DOE RFFO budget execution focuses on monitoring the contractor's progress in performing RFETS cost baseline activities.

4.2 PROJECT PLANNING AND BUDGET PROCESS

To accomplish work at RFETS, the internal authorization basis process is closely coupled with RFETS CPB, and the provisions of the RFCA provide the planning and scope for achieving the RFETS Vision:

- To achieve accelerated cleanup and closure of RFETS in a safe, environmentally protective manner and in compliance with applicable state and federal environmental laws
- To ensure the RFETS does not pose an unacceptable risk to the citizens of Colorado or to the site's workers from either contamination or an accident
- To work toward the disposition of contamination, wastes, buildings, facilities and infrastructure from RFETS consistent with community preferences and national goals

4.2.1 Project Planning/Project Scoping

The RFETS system incorporates methods and procedures for planning, authorizing, and controlling a project so that work can be performed to defined specifications, schedule, and budget. The system defines the processes for:

- Organizing and defining work
- Assigning, planning, and authorizing work
- Measuring work performed
- Analyzing and reporting costs of work performed
- Controlling changes to an established baseline by use of a Site Change Control Board

All RFETS project planning is done in accordance with approved site procedures.

Scope

The project scope formally establishes the project mission, functional objectives, scope of work, technical approach, regulatory requirements, and assumptions. Project scope is determined by the project mission needs, objectives, and regulatory requirements. Project scope is outlined in a Project Baseline Description (PBD).

Schedules

The critical path method of scheduling is used for establishing schedule baselines. Total life-cycle of a project is scheduled; however, near-term work may be in greater detail than out year work. Ongoing coordination between EPA, CDPHE, and DOE RFFO will occur to determine the appropriate target dates for intermediate milestones for multiyear projects.

Closure Project Baseline

All work performed by DOE RFFO at RFETS will be scheduled and integrated by inclusion in a controlled master resource-loaded critical path method schedule, referred to as the CPB, that will include the life-cycle schedule of all the work scope required to achieve the RFCA Vision. Schedule detail will reflect a "Rolling Wave" method of scheduling which produces a decreasing level of detail as time is extended from the current FY. The CPB will be used to direct and manage the RFETS work efforts while being the basis for current year and out year budgeting and planning. All scheduled reports, both internal and external (DOE RFFO, EPA, CDPHE, Stakeholders, etc.), will be produced from the CPB. Individual schedules not incorporated into the CPB will not be recognized.

The CPB is the basis against which planning and project performance will be evaluated. A cost and resource loaded schedule allows the evaluation of planning alternatives as they relate to funding and resource constraints, while insuring the plan maintains the logical sequence of activity execution as the plan proceeds through multiple iterations. The CPB will also be used to manage the project and evaluate performance in prior and current fiscal years. The current working schedule and budgets will be updated using actual costs and schedule status to be compared to the baseline in the calculation of cost and schedule variances.

RFETS has developed a CPB that describes activities necessary to achieve the end of the Intermediate Site Condition. The CPB reflects planning assumptions that are agreed to by DOE RFFO, EPA, and CDPHE. Changes to the project baseline which could lead to delays of important milestone completion dates will be approved by DOE RFFO, EPA, and CDPHE as defined in RFCA. The CPB shall be reviewed monthly and updated as required -- annually at a minimum.

Closure Project Schedule

The Closing Project Schedule (CPS) is a schedule depicting activities necessary to achieve the end of the Intermediate Site Condition. This schedule will reflect data found in the CPB. The Expanded Management Summary Schedule is a summary representation of the CPS.

RFCA Change Control

The RFCA change control process is the mechanism used by DOE RFFO, EPA, or CDPHE to assure that scope, schedule, or cost changes are reviewed for need, justification, and impact in a structured manner, and to assure that all parties can fulfill their responsibilities. This process is defined in the RFCA, Part 10 (Changes to Work). If the change will affect regulatory milestones, DOE RFFO will identify proposed modifications to the regulatory milestones in accordance with RFCA, Part 12 (Changes to Regulatory Milestones) and notify the other parties of modifications to the baseline.

Milestones

EPA and CDPHE will establish milestones from the CPB; no more than 12 milestones total per FY for FY, FY+1, and FY+2. Milestones will be designed to:

- Provide accountability for key commitments
- Ensure adequate progress at the site
- Provide adequate scope drivers
- Facilitate budget planning and execution

EPA and CDPHE may also establish a few key out year milestones (i.e., beyond FY+2) to provide long-term drivers for achieving the end of the RFCA Intermediate Site Condition (See RFCA preamble for description).

Regulatory Milestone Change Control Process

A regulatory milestone that is established according to the provisions of RFCA shall be changed upon receipt of a timely request for change, provided good cause exists. Requests

for change shall be submitted no less than 30 days before the date of the regulatory milestone except for changes sought on the basis of a force majeure. Consistent with ¶165 of RFCA, any request for change shall be submitted in writing and shall specify:

- The regulatory milestone that is sought to be changed
- The length of the change sought
- Good cause(s) for the change
- Any related regulatory milestone or target date that would be affected if the change were granted

4.3 REGULATOR INTERACTION IN THE BUDGET AND PLANNING PROCESS

This section provides an overview of regulatory participation in the budget and planning process for FY, FY+1, and FY+2. Refer to Part 11, Subpart A, ¶s 133-149 of the RFCA for detailed information regarding these interface points.

4.3.1 FY Activities

FY activities are those that occur during the current FY. These activities are as follows:

April – May

Within 30 days following the completion of DOE RFFO's annual midyear management review, DOE RFFO will brief EPA and CDPHE on any decisions that affect the CPB and RFCA regulatory milestones.

July – September

DOE RFFO, EPA, and CDPHE will evaluate the current schedule, cost and funding status of all projects in progress in the just-ending fiscal year, particularly those activities or projects that are on the critical path to meet regulatory milestones in the upcoming two fiscal years.

In addition, the DOE RFFO, CDPHE, and EPA Project Coordinators will meet periodically through the FY to monitor and discuss the status of projects scheduled during the year. DOE RFFO will promptly notify EPA and CDPHE of any proposed site-specific or programmatic action, if such action may have an impact on DOE RFFO's ability to meet the baselines or regulatory milestones of RFCA.

4.3.2 FY+1 Activities

FY+1 activities are those that are being planned during the current FY and will be performed in the next FY. These activities include the following:

January – May

- DOE RFFO will submit to CDPHE, EPA, and the Rocky Flats Citizens Advisory Board (CAB) a summary of the DOE RFFO budget request.

July – October

- DOE RFFO will provide EPA, CDPHE, and the CAB with copies of the Program Execution Guidance (PEG).
- DOE RFFO will consult with EPA and CDPHE in the development, verification, and review of draft Work Proposal Documents (WPDs) and CPB for FY+1.
- DOE RFFO will review and revise CPB and regulatory milestones and target activities as necessary.

October – December

- DOE RFFO and DOE HQ will brief EPA and CDPHE on the budget appropriation and tentative funding.
- No more than 60 days after OMB apports DOE funds, DOE RFFO, EPA, and CDPHE will evaluate schedule, cost, and funding status of projects for the new FY to incorporate information into budget, milestone, and target DOE activities.

If there is a delay in Congressional appropriations beyond the first day of the new fiscal year, DOE RFFO will inform EPA and CDPHE of any CRs, and of the impact of the delay on its ability to meet regulatory milestones and other requirements of the RFCA. EPA and CDPHE will review these actions and may recommend reallocation of available funds.

4.3.3 FY+2 Activities

FY+2 activities are those which are being planned during the current year and will be performed two years from the current FY.

January – April

- Within one week after DOE HQ issues planning/budget guidance, DOE RFFO will provide a copy of guidance to the EPA and CDPHE
- Within three weeks after DOE RFFO receives target level funding, DOE RFFO will provide its preliminary RFCA impact assessment
- Before submittal of the FY+2 budget request to DOE HQ, FY+2 baselines, regulatory milestones and target activities will be established or revised

4.3.4 Roles and Responsibilities

The budgetary roles and responsibilities for DOE RFFO include:

- Requesting necessary funds to meet RFCA regulatory milestones, target activities, and other commitments/requirements
- Interacting with DOE HQ regarding budget formulation document submittals, the presidential budget submittal, problems with the RFETS cost baseline and budget
- Communicating RFETS objectives and priorities
- Conveying information and guidance to the CDPHE, EPA, and the CAB

DOE RFFO's role focuses on maintaining the RFETS's CPB, preparing budget formulation documents, and ensuring that projects have the proper authorization basis for planning and execution. The role of the CDPHE and EPA focuses on evaluating the CPB and funding status of projects to determine if the RFETS budget is adequate for meeting RFCA requirements and other environmental laws, and to establish milestones and target activities for the budget and planning years. EPA and CDPHE should be involved early in the budget process during the consultative process set forth in RFCA. All RFCA Parties have the responsibility to identify areas in the CPB where cost savings can be achieved in order to free funding for other risk reduction activities.

4.3.5 Cost Savings Initiatives and Productivity Improvements

EPA and CDPHE shall consult with DOE RFFO during the RFETS budget planning and execution processes and other times deemed appropriate to identify and evaluate opportunities and incentives to improve productivity and reduce costs associated with activities at RFETS.

Standards, requirements, and practices shall be regularly reviewed to determine that activities at RFETS are conducted in a manner that is sufficient to achieve compliance with requirements and to protect workers, the public, and the environment, and necessary to accomplish the RFCA preamble objectives expeditiously and efficiently. Refer to RFCA ¶s 158-162 for additional guidance on cost savings and productivity improvements.

4.4 ADMINISTRATIVE RECORD/RECORDS MANAGEMENT/ DOCUMENT CONTROL

4.4.1 Administrative Record

The AR is the compilation of documents relied on by DOE to select a response action for cleanup of a hazardous waste site. In accordance with Section 113(k) of CERCLA, as amended by the Superfund Amendments and Reauthorization Act of 1986, AR files will be maintained for CERCLA response actions at or near RFETS, using EPA policies and guidelines. DOE RFFO is ultimately responsible for AR contents for RFETS.

The AR will be kept in accordance with CERCLA, NCP, and OSWER Directive 9833.3a-1 (EPA, 1994a) *Guidance on Administrative Record for Selecting of CERCLA Response Actions* and AR Implementation Procedure 2-S65-ER-ADM-17.02 *Administrative Record Document Identification and Transmittal* (RMRS, 1995a). An AR shall be established for

each OU, for each ER action, and for each decommissioning action. Documents necessary to be included in each AR are delineated in OSWER Directive 9833.3a-1 (EPA, 1994a).

RFETS procedure 1-F78-ER-ARP-001 *CERCLA Administrative Record Program* (RMRS, 1994b), establishes and defines the requirements and responsibilities for the compilation and maintenance of CERCLA AR files and completed ARs. Any future changes to AR policies and guidelines affecting the AR files shall be discussed by DOE RFFO, EPA, and CDPHE and an agreement shall be reached on how best to accommodate those changes.

EPA, after consultation with CDPHE when necessary, shall make the final determination of whether a document is appropriate for inclusion in an AR. EPA and CDPHE shall participate in compiling the AR by submitting documents to DOE RFFO as EPA and CDPHE deem appropriate. DOE RFFO will forward these documents to the RFETS AR files. Every AR file will be reviewed and approved by DOE RFFO, EPA, and CDPHE (i.e., Site Technical Administrative Record Review [STARR]) before the file is closed at the signing of the appropriate decision document.

Four information repositories have been established to provide the public with access to the AR. A copy of the AR is accessible to the public at times other than RFETS normal business hours through the Public Reading Room at Front Range Community College.

Information Repositories:

U.S. Environmental Protection Agency
Region VIII
Superfund Records Center
999 18th Street, Suite 500
Denver, Colorado 80202-2466
(303) 312-6473

Citizens Advisory Board
9035 Wadsworth Parkway
Suite 2250
Westminster, Colorado 80021
(303) 420-7855

**Colorado Department of Public Health
and Environment**
Information Center, Bldg. A
4300 Cherry Creek Drive South
Denver, Colorado 80220-1530
(303) 692-3312

U.S. Department of Energy
Rocky Flats Public Reading Room
Front Range Community College Library
3645 West 112th Avenue
Westminster, Colorado 80030
(303) 469-4435

4.4.2 Records Management

The objectives of the RFETS records management program are to identify, capture, protect, and maintain active project records for both ER and decommissioning; index active records to ensure efficient and effective retrievability; safeguard records to prevent loss, damage, or unauthorized accesses; and turn over inactive records to the RFETS for disposition in accordance with approved retention schedules. Final records disposition shall be approved by the DOE RFFO designee and be consistent with the CERCLA, RCRA, CHWA, and DOE RFFO records

retention schedules, whichever is longer. DOE shall make all such records or documents available to CDPHE and EPA upon request.

RFETS procedure 1-V41-RM-001, *Records Management Guidance for Records Sources* (RMRS, 1996c), provides detailed guidance on the RFETS Records Management Program. Procedures for implementation of the records management program elements identified in the above procedure are: (1) RM-06.03 *Records Receipt, Processing, Retrieval, and Disposition* (RMRS, 1997a); and (2) RM-06.02 *Records Identification, Generation, and Transmittal* (RMRS, 1997b).

4.4.3 Document Control

Document control is the process of managing the authorized release of specific documents and changes to ensure that only the most current, approved-for-release copies of controlled documents are used to perform program activities, including those that prescribe activities affecting quality and safety. RFETS procedure 1-77000-DC-001, *Document Control Program* (RMRS, 1993), establishes requirements responsibilities, and instructions for the identification and control of controlled documents.

4.5 REPORTING

All reporting shall be done in accordance with established DOE HQ and Environmental Management policies and requirements. DOE-stipulated elements focus on cost, schedule, and technical performance against approved baselines. Additional reporting requirements established by DOE RFFO are provided in RFETS policy 1-R97-F&A-MCS-001, *Management Control Systems and ER Project Control Management Procedures and Requirements* (RMRS, 1996d).

RFCA Project Coordinators will meet at least monthly to discuss accomplishments, work in progress and anticipated work, potential changes to the baseline, implementation difficulties, compliance issues, opportunities for streamlining, and other matters of importance to implementation.

Quarterly, DOE RFFO will provide EPA and CDPHE with a progress report that describes progress toward implementation of activities covered by RFCA. Whenever possible, existing reports and databases will be used to fulfill this reporting requirement. Upon request, DOE RFFO will provide EPA and/or CDPHE with copies of project status reports on a monthly basis.

5.0 PUBLIC INVOLVEMENT AND STAKEHOLDER SUPPORT

5.1 BACKGROUND

Public involvement is an important part of the RFCA Vision. An effective public involvement strategy, as part of routine project planning, is required by both law and DOE policy for many project activities. In addition, it is the best management practice on any project potentially impacting public health. This section describes the RFETS approach to involving stakeholders in project decisionmaking as RFETS progresses toward cleanup and closure.

All public involvement activities will be conducted in compliance with applicable requirements under NEPA, CERCLA, RCRA, and DOE Orders and guidelines. Those requirements and guidelines are identified in the RFSIPIP.

5.2 PUBLIC INVOLVEMENT OBJECTIVES

The RFSIPIP is designed to increase stakeholders' understanding of the Site's ER and waste management programs and to open avenues for stakeholders to participate in RFETS decision-making processes. This program has been developed to:

- Provide accurate and timely information about environmental contamination and hazardous materials, cleanup plans, monitoring, and implementation progress
- Ensure stakeholders have the opportunity to provide input regarding planned actions and to have their opinions considered in decision-making
- Ensure the DOE RFFO and its contractors understand and take into account stakeholder values and concerns
- Meet RCRA, CERCLA, NEPA, and RFCA public involvement requirements

Public involvement in the decision-making process will be conducted utilizing the Rocky Flats Public Participation Guidance, which was created to ensure public involvement at RFETS meaningful (i.e., influential in the site decisions) and to optimize the effectiveness of public involvement efforts.

Additionally, public participation will adhere to the following guidelines and principles as outlined in the RFCA:

- Ongoing consultation with the local elected officials
- Consistency with the RFETS long-term vision, mission, and budget
- Clear linkage to a decision-making process
- Adherence to state and federal requirements
- Stakeholder consultation on significant public policy issues, even if there is no legal requirement for involvement
- Inclusion of various and diverse community groups and people with varying levels of knowledge and understanding of RFETS issues

5.3 PUBLIC INVOLVEMENT PLANNING

It is the responsibility of all managers at RFETS to plan for the appropriate level of stakeholder involvement as a primary element of site closure projects. Stakeholder involvement before selection of alternatives ensures decisions are made with full awareness of all relevant issues. Failure to involve stakeholders at appropriate points can result in costly project delays and reformulation of plans. In developing a public involvement strategy, managers should base decisions about the level and timing of public involvement on the following:

- Probable impact on stakeholders
- Likelihood of value conflicts among stakeholders
- Level of perceived risk to stakeholders
- Uneven distribution of impacts of alternatives among stakeholder groups

Managers should consult with the RFETS Office of Communication (OOC) during the project planning stages to develop a strategy for involving the public in project decisions, as well as to develop the tools necessary to implement that strategy. The OOC will prepare information for managers' use while engaging the public. The OOC coordinates outreach programs (e.g., Speakers Bureau and Tours and Visits) to promote additional face-to-face interaction.

Project-specific public involvement strategies, while not required for all projects, will provide the framework for soliciting stakeholder input. These strategies, or "mini" public involvement plans should identify the desired outcome of the strategy, the primary audience, the message, sensitive issues, and tools to be used.

Once the level of public involvement has been identified, it is important to communicate clearly what role the stakeholders have in the decision making process, to explain how the public fits into that process, and how public input will affect the decision. As a project progresses through planning into implementation, the extent to which public input can be effective will decrease. Accurately communicating the appropriate level of involvement can reduce misunderstanding.

5.4 PUBLIC INVOLVEMENT TOOLS

Using the tools below, the public involvement strategy will adhere to the objectives and meet requirements set forth in NEPA, RCRA, CERCLA, RFCA, and DOE Orders and guidelines. Other tools and resources can be developed and utilized as needed to promote effective public involvement. The OOC supports management in the proper utilization of these tools:

Briefings, Presentations & Discussions - Upon request, and to the extent possible, subject matter experts will meet the schools, groups, elected officials, regulators, individual stakeholders, and stakeholder organizations. The OOCs prepared presentations on numerous topics available for use.

Public Hearings & Public Information Meetings - The Site schedules public hearings and/or meetings as needed to disseminate information and accept feedback on key activities. Hearings usually are scheduled close to the midpoint of a public comment period. Public Information Meetings are not necessarily tied to specific public comment period and incorporate as many topics as appropriate to warrant the meeting. The OOC will plan, coordinate, and facilitate these public forums.

Employee Meetings - Employees are among the most important stakeholders at RFETS. It is important to keep employees informed and ensure they understand how their work contributes to the successful cleanup and closure of the site. Town hall meetings, cascading meetings, Manager's Information Meetings, staff meetings, and written and electronic newsletters provide to keep employees informed and solicit employee feedback about site activities.

News Releases and Community Advisories - The OOC disseminates information to news media outlets and key stakeholders and groups. In addition, the OOC serves as the point of contact for inquiries from news media and stakeholders.

Fact Sheets - The OOC creates brief informational materials (usually one or two pages in length) that identify key elements of specific projects and activities. Fact sheets describe processes and activities to assist stakeholders in understanding the projects.

Mailing List(s) - RFETS maintains a facility mailing list of about 2,000 stakeholders interested in obtaining information about the Site. Separate mailing lists (e.g., RCRA mailing lists) are maintained which contain the names of smaller numbers of stakeholders interested in receiving information on specific topics.

Public Tours - The OOC coordinates, plans, and conducts tours of the site to allow interested parties a first-hand look at work being accomplished at RFETS.

Speakers Bureau - Knowledgeable site employees visit schools, civic groups, stakeholder organizations, and other groups to inform small audiences of site activities relevant to their interests.

Reading Rooms - There are six locations throughout the Denver metropolitan area where interested parties can access information about RFETS. The Rocky Flats Public Reading Room contains thousands of documents relating to RFETS and other DOE weapons complex sites.

Electronic Access to Information - Site information is available through Internet and Intranet access. Information for public dissemination will be made available on-line for stakeholders. An option of submitting comments on-line is in planning.

5.5 SUMMARY

Involving the public in RFETS decisions and clearly communicating stakeholders' roles in affecting decisions are paramount to successful site closure. Regardless of legal requirements for public involvement, involving the stakeholders in decision-making building public trust and confidence that RFETS is being managed in the public interest. Teamwork between project managers, the OOC, and affected stakeholders will promote an effective strategy and use of communication tools to inform and involve stakeholders in the project activities.

OOO Contact Telephone Numbers

DOE Communication	(303) 966-5993
Kaiser-Hill Communication	(303) 966-7412

6.0 REFERENCES

Chemrisk, 1992, *Project Task 3/4 Report: Reconstruction of Historical Rocky Flats Operations and Identification of Release Points (final draft report)*, August, 1992.

Chromec, F.W., M.L. Hogg, M. Siders, R. Randall, R. Roberts, The Effectiveness of the Rocky Flats Environmental Technology Site Background Comparison Methodology, Environmental Restoration 1995 Conference, DOE, Denver, CO., August 14-17.

CDPHE, 1997, Rocky Flats Environmental Technology Site RCRA Permit, Permit No. CO-97-05-30-01, June, 1997.

DOE, 1989, "General Design Criteria," Order 6430.1A, U.S. DOE, Washington, DC, April, 1989.

DOE, 1990, "General Environmental Protection Program," Order 5400.1, U.S. DOE, Washington, DC, June, 1990.

DOE, 1991, Federal Facility Agreement and Consent Order (Interagency Agreement [IAG] Among the U.S. DOE, U.S. EPA, and the Colorado Department of Health), U.S. Department of Energy, Washington, DC, January 22, 1991.

DOE, 1992a, *Historical Release Report for the Rocky Flats Plant*, Golden, CO., June, 1992.

DOE, 1992b, *Final No Further Action Justification Document for Operable Unit 16 Low-Priority Sites*, Rocky Flats Environmental Technology Site, Golden, CO., June, 1992.

DOE, 1993a, *Background Geochemical Characterization Report*, September 30, 1993.

DOE, 1993b, *Radiation Protection of the Public*, U.S. Department of Energy, July 7, 1993.

DOE, 1994a, CDH Conservative Screen Implementation SGS-405-94, 94-RF-07465, Correspondence from S. Stiger, July 13, 1994.

DOE, 1994b, *Corrective Action Decision/Record of Decision for OU 16: Low-Priority Sites*, Rocky Flats Environmental Technology Site, Golden, CO., August, 1994.

DOE, 1994c, *Final Interim Measures/Interim Remedial Action Decision Document for the Rocky Flats Industrial Area*, Rocky Flats Environmental Technology Site, Golden, CO., August, 1994.

DOE, 1995a, Environmental Restoration Ranking, September 27, 1995.

DOE, 1995b, *Human Health Risk Assessment Methodology for RFETS* (Draft), Prepared for DOE Rocky Flats Field Office by EG&G Rocky Flats, Inc., RF/ER-95-0088.

DOE, 1995c, *Geochemical Characterization of Background Surficial Soils, Background Soils Characterization Program*, May, 1995 .

DOE, 1995d, Programmatic Risk-Based Preliminary Remediation Goals, Final Revision 2, February, 1995.

DOE, 1995e, Letter Transmitting Exposure Scenarios and Factors, 95-DOE-08453, From Steven W. Slaten (DOE) to Martin Hesmark (EPA) and Joe Scheffelin (CDPHE), June 15, 1995.

DOE, 1995f, Final Phase II RFI/RI Report Operable Unit No. 2, RF/ER-95-0079.UN, Rocky Flats Environmental Technology Site, Golden, CO., May, 1995.

DOE, 1995g, Phase I RFI/RI Report Operable Unit No. 5, Draft Final, Rocky Flats Environmental Technology Site, Golden, CO., October, 1995.

DOE, 1995h, "Worker Protection Management for DOE Federal and Contractor Employees," Order 440.1, U.S. DOE, Washington, DC, October, 1995.

DOE, 1996a, *Ecological Risk Assessment Methodology: Sitewide Conceptual Model* (Final), Prepared for DOE Rocky Flats Field Office, by EG&G Rocky Flats, Inc., June, 1996.

DOE, 1996b, *Ecological Risk Assessment Methodology: Ecological Chemicals of Concern* (Final), Prepared for DOE Rocky Flats Field Office, by EG&G Rocky Flats, Inc., June, 1996.

DOE, 1996c, Final Phase RFI/RI Report, Walnut Creek Priority Drainage, Operable Unit 6, RF/ER-95-0119.UN. Rocky Flats Environmental Technology Site, Golden, CO., February, 1996

DOE, 1996d, Resource Conservation and Recovery Act Facility Investigation/Remedial Investigation Report, Operable Unit 3, RF/ER-96-0029.UN, Rocky Flats Environmental Technology Site, Golden, CO., June, 1996.

DOE, 1996e, "Quality Assurance," Order 5700.6C, U.S. DOE, Washington, DC, May, 1996.

DOE, 1997, *Rocky Flats Environmental Technology Site Integrated Monitoring Plan* (final draft), Rev 1, Rocky Flats Environmental Technology Site, Golden, CO, June, 1997.

EPA, 1980, Superfund Amendments and Reauthorization Act, Section 121(d) as amended CERCLA 42 USC § 9601 et seq., U.S. Environmental Protection Agency.

EPA, 1987, *Data Quality Objectives for Remedial Response Activities – Development Process*.

EPA, 1988a, *Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA*, 540/6-89/004, U.S. Environmental Protection Agency, October, 1988.

EPA, 1988b, *CERCLA Compliance with Other Laws Manual: Interim Final*, August 1988.

EPA, 1989a, *Interim Final Guidance on Preparing Superfund Decision Documents: The Proposed Plan, The Record of Decision, Explanation of Significant Differences, and The Record of Decision Amendment*, OSWER Directive 9355.3-02.

EPA, 1989b, *CERCLA Compliance with Other Laws Manual: Part II. Clean Air Act and Other Environmental Statutes and State Requirements*, EPA/540/G-89/009, August 1989.

EPA, 1991, *Role of Baseline Risk Assessment in Superfund Remedy Selection Decisions*, OSWER Directive 9355.0-30, EPA, April 22, 1991.

EPA, 1993, *EPA Guidance for Conducting Non-Time Critical Removal Actions Under CERCLA*, EPA, August, 1993.

EPA, 1994a, *Guidance on Administrative Record for Selecting CERCLA Response Actions*, OSWER Directive 9833.3a-1, October, 1994.

EPA, 1994b, *Ecological Guidance for Superfund: Process for Designing and Conducting Ecological Risk Assessments* (Review Draft), Environmental Response Team, Edison, NJ, September, 1994.

EPA/CDPHE 1995, Letter from Tim Rehder (EPA) and Joe Scheffelin (CDPHE) to Steven W. Slaten (DOE), December 12, 1995.

EPA/CDPHE/DOE, 1996, Final Rocky Flats Cleanup Agreement. CERCLA VIII-96-21, RCRA[3008(h)] VIII-96-01, State of Colorado Docket # 96-07-19-01, July 19, 1996.

EPA, 1996a, *Soil Screening Guidance: User's Guide*, EPA/540/R-96/018, OSWER, Washington, DC, April, 1996.

EPA, 1996b, *Soil Screening Guidance: Technical Background Document*, EPA/540/R-95/128, OSWER, Washington, DC, May, 1996.

EPA, 1996c, *Draft 40 CFR Part 196 - Environmental Protection Agency Radiation Site Cleanup Regulation (preliminary working draft)*, February, 1996.

Federal Register, 1993, 58 FF 16268, *Radiation Protection of the Public and the Environment; Proposed Rule*, U.S. DOE, March 25, 1993.

Gilbert, R.O. and J.C. Simpson, 1992, *Statistical Methods for Evaluating the Attainment of Cleanup Standards, Volume 3: Referenced-Based Standards for Soils and Solid Media*, Pacific Northwest Laboratory, Richland, Washington, DC.

K-H Procedure 1-D06-EPR-END.03, 1994a, *Identification and Protection of Threatened, Endangered, and Special Concern Species*, January 14, 1994.

K-H Procedure 1-G98-EPR-END.04, 1994b, *Migratory Bird Evaluation and Protection*, April 19, 1994.

K-H, 1997, RFETS Health and Safety Practices, Kasier-Hill Company, as amended.

K-H, Master Activity List, Revision 2, April, 1996.

RFETS, 1996, *Integrated Water Management Plan for the Rock Flats Environmental Technology Site* (Final), RF/ER-96-0037, RFETS, Golden, CO, August, 1996.

RMRS Procedure 3-21000-ADM, 1991, *EMD Administrative Procedures Manual*, August 16, 1991.

RMRS Procedure 1-77000-DC-001, 1993, *Document Control Program*, November 15, 1993.

RMRS Procedure 4-H46-ENV-OPS-FO.29, 1994a, *Disposition of Soil and Sediment Investigations - Derived Materials*, June 24, 1994.

RMRS Procedure 1-F78-ER-ARP.001, 1994b, *CERCLA Administrative Record Program*, October 5, 1994.

RMRS Procedure 4-B29-ER-OPS-FO.13, 1994c, *Containerization, Preserving, Handling, and Shipping of Soil and Water Samples*, March 4, 1994.

RMRS Procedure 4-B29-ER-OPS-FO.14, 1994d, *Field Data Management*, September 4, 1994.

RMRS Procedure 2-G32-ER-ADM-80.02, 1994e, *Evaluation of ERM Data for Usability and Final Reports*, October 21, 1994.

RMRS Procedure 2-S97-ER-ADM-05.14, *Use of Field Log Books and Forms*, 1995b

RMRS Procedure 2-S65-ER-ADM-17.02, 1995, *Administrative Record Document Identification and Transmittal*, March 26, 1995.

RMRS, 1996a, *1996 Annual Update Environmental Restoration Ranking*, Rocky Mountain Remediation Services, September, 1996.

RMRS, 1996b, *Groundwater Conceptual Plan for the Rocky Flats Environmental Technology Site*, RF/ER-95-0121.UN, RMRS, September, 1996.

RMRS Procedure 1-V41-RM-001, 1996c, *Records Management Guidance for Records Sources*, July 2, 1996.

RMRS Procedure 1-R97-F&A-MCS-001, 1996d, *Management Control System*, December 12, 1996.

RMRS Procedure 1-R32-ADM-02.38, 1996e, *Activity Definition Process*, Revision 0, December 26, 1996.

RMRS Procedure RM-06.03, 1997a, *Records Receipt , Processing, Retrieval, and Disposition*, May 28, 1997.

RMRS Procedure RM-06.02, 1997b, *Records Identification, Generation, and Transmittal*, May 28, 1997.

RMRS Procedure ADM-TOC, 1997c, *Rocky Flats Administrative Procedures Manual*, April 28, 1997.

Section 113(k) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980, as amended by the Superfund Amendments and Reauthorization Act of 1986.

APPENDIX A

1.0 PURPOSE

The Framework for Project Scoping is intended to provide a more direct approach to understanding the constraints RFCA imposes on activities conducted at RFETS. RFCA divides activities/processes into five broad categories, and divides RFETS into two areas. The five activities include:

- deactivation
- decommissioning
- environmental remediation
- CAD/RODs
- Site-wide activities

The two areas include:

- buffer zone
- industrial area

The framework that follows represents a matrix of the first four activities/processes (Site-wide activities are excluded) paired with a buffer zone or industrial area location. Site-wide activities are not divided by location as they are, by definition, not location dependent. The result is a matrix composed of nine elements.

By assembling the information within the activity and location-based matrix, users can readily access and understand topics that may otherwise be widely distributed throughout RFCA. The topics included in the framework were chosen based upon commonly encountered questions as to authority and jurisdiction and based upon topics which need to be addressed during project scoping.

Activity: DEACTIVATION
Location: INDUSTRIAL AREA

Sources of RFCA Authority:

None

Potential Authorities External to RFCA:

Colorado Hazardous Waste Act and Rules

CHWA/RCRA Part B Permit

CHWA/RCRA Interim Status Requirements

Generator and transporter CHWA/RCRA Hazardous Waste Management Requirements

NRC Licensing Requirements for Off-site Disposal Facilities

Atomic Energy Act

DOE Orders

NEPA

NPDES Permit

Colorado Water Quality Control Act and Rules

NESHAP

Colorado Air Pollution Prevention and Control Act and Rules

OSHA

TSCA (PCBs)

Decision-making Responsibility:

For Non-waste (Radioactive Materials, SNM, Transuranic (TRU), Byproducts) during Operations; Processing; On-site Storage, Transport, and Decontamination (not associated with decommissioning); **Deactivation**; and Final Disposition-

DNFSB - Primary; CDPHE - Review and Comment

For Low Level Waste during Operations; Processing; On-site Storage, Transport, and Decontamination (not associated with decommissioning); **Deactivation**; and Final Disposition-

DNFSB - Primary; CDPHE Review and Concur if final disposition in Colorado, with CDPHE Primary on final disposition itself

For TRU Mixed Waste during Operations; Processing; On-site Storage, Transport, and Decontamination (not associated with decommissioning); **Deactivation**; and Final Disposition-

CDPHE - Primary; DNFSB - Review and Concur

Activity: **DEACTIVATION (continued)**
Location: **INDUSTRIAL AREA (continued)**

For Low-Level Mixed Waste during Operations; Processing; On-site Storage, Transport, and Decontamination (not associated with decommissioning); **Deactivation**; and Final Disposition-

CDPHE - Primary; DNFSB - Review and Concur

For Hazardous and Solid Waste during Operations; Processing; On-site Storage, Transport, and Decontamination (not associated with decommissioning); **Deactivation**; and Final Disposition-

CDPHE - Primary

For CERCLA Hazardous Substances (exclusively) during Operations; Processing; On-site Storage, Transport, and Decontamination (not associated with decommissioning); **Deactivation**; and Final Disposition-

CDPHE - Primary; EPA retains final authority on Record of Decision

Waste Management:

Wastes removed during deactivation are fully regulated as RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination. In addition, municipal waste and radiologically contaminated property must be considered.

Permit Waiver:

Permit waivers for deactivation in the Industrial Area are not available. Full administrative and substantive compliance is required. Elementary neutralization, and 90-day LDR treatment in tanks or containers do not require permits.

RCRA Closure:

Because it is not anticipated that deactivation will be performed pursuant to a RFCA decision document, the closure requirements and procedures in the RCRA Part B permit apply.

Requirements Analysis:

Deactivation must be conducted in full compliance with all administrative and substantive requirements of applicable environmental regulatory authorities. Because it is not anticipated that deactivation will be performed pursuant to a RFCA decision document, the closure requirements and procedures in the RCRA Part B permit apply.

Activity: DEACTIVATION (continued)
Location: INDUSTRIAL AREA (continued)

Modifications:

Modifications to a closure plan submitted pursuant to the Part B Permit or the interim status requirements are subject to the Part B permit or Part 265 requirements and procedures.

Public Involvement:

Deactivation that does not involve closure of RCRA units can be accomplished without public notice and comment.

Exceptions/Comments:

As part of scoping also consider non-RFCA authorities, including NEPA, air, water, and ecological concerns. See the discussions at Section 2.6.

Activity: DEACTIVATION
Location: BUFFER ZONE

Sources of RFCA Authority:

Not applicable.

Potential Authorities External to RFCA:

Not applicable.

Decision making Responsibility:

Not applicable.

Waste Management:

Not applicable.

Permit Waiver:

Not applicable.

RCRA Closure:

Not applicable.

Requirements Analysis:

Not applicable.

Modifications:

Not applicable.

Public Involvement:

Not applicable.

Exceptions/Comments:

Deactivation will not be required in the Buffer Zone.

Activity: DECOMMISSIONING
Location: INDUSTRIAL AREA

Sources of RFCA Authority:

CERCLA/NCP Removal Action Authorities
CHWA/RCRA Permitted and Interim Status Closure Requirements
CHWA/RCRA Corrective Action Requirements

Potential Authorities External to RFCA:

Colorado Hazardous Waste Act and Rules
CHWA/RCRA Part B Permit
CHWA/RCRA Interim Status Requirements
Generator and transporter CHWA/RCRA Hazardous Waste Management Requirements
NRC Licensing Requirements for Off-site Disposal Facilities
Atomic Energy Act
DOE Orders
Colorado Water Quality Control Act and Rules
Colorado Air Pollution Prevention and Control Act and Rules
CHWA/RCRA Permitted and Interim Status Closure Requirements
NPDES Permit and Rules
Stormwater Permitting Requirements
NEPA
Industrial Area IM/IRA
NESHAP
OSHA
TSCA (PCBs)

Decision making Responsibility:

For Non-waste (radioactive materials, SNM, TRU, Byproduct), LLW, TRU-Mixed Waste, Low Level Mixed Waste, during decontamination of residual contamination of fixed structures and during dismantlement and demolition

CDPHE - Primary; EPA - Review and Comment; DNFSB - Review and Comment

For Hazardous and Solid Waste and CERCLA/RCRA Material in the Environment during decontamination of residual contamination of fixed structures and during dismantlement and demolition

CDPHE - Primary; EPA - Review and Comment

Permit Waiver:

Permit waivers are available in the Industrial Area for decommissioning activities (§16). The basis for the permit waiver must be included in the decision document in accordance with RFCA §17.

Activity: DECOMMISSIONING (continued)

Location: INDUSTRIAL AREA (continued)

Waste Management:

By operation of RFCA, decommissioning waste is remediation waste. Equipment contaminated with limited hazardous or solid waste residues that remain after deactivation/removal may be regulated by CDPHE as decommissioning. If CDPHE elects to regulate the final remediation of the contaminated equipment as a decommissioning activity the residual wastes in the equipment shall be considered remediation wastes.

During the decommissioning project permits for waste management are not required (see "permit waiver," above). At the close of the decommissioning project the decommissioning wastes become fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination. Although fully regulated, if a CAMU becomes operational at some future time, the wastes remain "remediation wastes" and may be managed in the CAMU. Remediation waste may also be managed in CAMU waste piles and temporary units (as ARAR) in either the Industrial Area or the Buffer Zone.

At any time the decommissioning wastes are shipped off-site they are fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination.

The CERCLA Off-site Rule determinations and updates will be maintained by the RFETS contract representative for each off-site disposal contract.

Water Management:

Remediation wastewater generated during decommissioning can be managed, as appropriate, by free release where surface-water quality ARARs are attained; in the sewage treatment plant in accordance with the NPDES permit requirements; or in the Consolidated Water Treatment Facility (CWTF) in B891 if the remediation wastewater meets the CDPHE Wastewater Treatment Unit Policy. Authority for management in the CWTF must be provided in the decision document.

RCRA Closure:

During decommissioning, the complete or phased closure of permitted units, of interim status units and of IHSSs designated as "RCRA" in RFCA Appendix 3, may, at CDPHE discretion, use either a separate closure plan or an accelerated action decision document. If an accelerated action decision document is used the closure requirements must be addressed in that document. There are three types of accelerated action decision documents that may act in lieu of a permit modification: 1) IM/IRAs, 2) PAMs, 3) RSOPs. The substantive and administrative requirements for complete or phased closure of permitted units are found in the Part B permit and the requirements for closure of interim status units are found in Attachment 10 of RFCA.

Activity: DECOMMISSIONING (continued)
Location: INDUSTRIAL AREA (continued)

Requirements Analysis:

A requirements analysis must be performed. Pursuant to the NCP, removal actions require attainment of ARARs to the maximum extent practicable. If an accelerated action decision document is used in lieu of a permit modification, the applicable closure requirements, including post-closure care must be addressed by the decision document.

The requirements associated with authorities external to RFCA must also be addressed. Waste management, wastewater management, stormwater management, air permitting, NEPA and ecological concerns must be considered.

Modifications:

Field modifications, minor modifications and major modifications are allowed. See Section 3.10 for a discussion.

Public Involvement:

PAMs require a thirty-day public comment period. IM/IRAs and RSOPs require a forty five to sixty-day public comment period, except for Class 3 permit modifications. Any IM/IRA that requires a Class 3 permit modification will be subject to two sixty-day comment periods. Once public comment on the RSOP is complete, the RSOP may be invoked by letter notification to the parties. For a complete description see Section 5.0 and the sample schedules provided for each type of decision document in the Appendices.

Exceptions/Comments:

The Industrial Area IM/IRA imposes groundwater, surface water and air monitoring obligations on decommissioning activities conducted in the Industrial Area. As such, the Industrial Area IM/IRA obligations must be considered and addressed during project scoping. Implementation of the Industrial Area IM/IRA obligations must conform to the building decommissioning decision process presented in the IMP.

As part of scoping also consider non-RFCA authorities, including NEPA, air, water, and ecological concerns. See the discussions at Section 2.6.

Soil data generated as part of the decommissioning must be formally transferred and incorporated in the SWD. In addition, existing data that are "No Longer Representative" must be flagged in the database.

Activity: DECOMMISSIONING
Location: BUFFER ZONE

Sources of RFCA Authority:

CERCLA/NCP Removal Action Authorities
CHWA/RCRA Interim Status Closure Requirements
CHWA/RCRA Corrective Action Requirements

Potential Authorities External to RFCA:

Colorado Hazardous Waste Act and Rules
CHWA/RCRA Part B Permit
CHWA/RCRA Interim Status Requirements
Generator and transporter CHWA/RCRA Hazardous Waste Management Requirements
NRC Licensing Requirements for Off-site Disposal Facilities
Atomic Energy Act
DOE Orders
Colorado Air Pollution Prevention and Control Act and Rules
Colorado Water Quality Control Act and Rules
NPDES Permit
Stormwater Permitting Requirements
NEPA
NESHAP
OSHA
TSCA (PCBs)

Decision making Responsibility:

For decommissioning performed in the buffer zone-

EPA - Primary; CDPHE - Review and Comment

Waste Management:

By operation of RFCA, decommissioning waste is remediation waste.

During the decommissioning project, permits for waste management (i.e., storage > 90 days) are not required (see "permit waiver," below), but the waste management must comply with the substantive requirements of RCRA. At the close of the decommissioning project, the decommissioning wastes become fully regulated (substantively and procedurally) as either RCRA hazardous waste, as solid waste, as low level waste, as TRU waste, or any combination if the wastes are moved into the industrial area. Although fully regulated in the industrial area, if a CAMU becomes operational at some future time, the wastes remain "remediation wastes" and may be managed in the CAMU. Remediation waste may also be managed in CAMU waste piles and temporary units (as ARAR) in either the Industrial Area or the Buffer Zone.

Activity: DECOMMISSIONING (continued)
Location: BUFFER ZONE (continued)

At any time the decommissioning wastes are shipped off-site they are fully regulated (substantively and procedurally) as either RCRA hazardous waste, as TSCA waste (PCBs), as solid waste, as low level waste, as TRU waste, or any combination.

Water Management:

Remediation wastewater generated during decommissioning can be managed, as appropriate, by free release where surface-water quality ARARs are attained; in the sewage treatment plant in accordance with the NPDES permit requirements; or in the CWTF in B891 if the remediation wastewater meets the CDPHE Wastewater Treatment Unit Policy. Authority for management in the CWTF must be provided in the decision document.

The CERCLA Off-site Rule determinations and updates will be maintained by the RFETS contract representative for each off-site disposal contract.

Permit Waiver:

Permit waivers are available in the buffer zone. The basis for the permit waiver must be included in the decision document in accordance with RFCA ¶17.

RCRA Closure:

During decommissioning, the complete or phased closure of interim status units and of IHSSs designated as "RCRA" in RFCA Appendix 3, may, at CDPHE discretion, use a separate closure plan or an accelerated action decision document. There are three types of accelerated action decision documents that may act in lieu of a permit modification: 1) IM/IRAs, 2) PAMs, 3) RSOPs. The substantive and administrative requirements for closure of permitted units are found in the Part B permit; and the requirements for closure of interim status units are found in Attachment 10 of RFCA.

Requirements Analysis:

A requirements analysis must be performed. Pursuant to the NCP, removal actions must attain ARARs to the extent practicable considering the exigencies of the circumstance. If an accelerated action decision document is used in lieu of a permit modification the applicable closure requirements, including post-closure care must be addressed by the decision document.

Modifications:

Field modifications, minor modifications and major modifications are allowed. See Section 3.10 for a complete discussion.

Activity: DECOMMISSIONING (continued)
Location: BUFFER ZONE (continued)

Public Involvement:

PAMs require a thirty-day public comment period. IM/IRAs and RSOPs require a forty five to sixty-day public comment period except for Class 3 permit modifications. Any IM/IRA that requires a Class 3 permit modification will be subject to dual sixty-day comment periods. Once public comment on the RSOP is complete, the RSOP may be invoked by letter notification to the parties. For a complete description see Section 5.0 and the sample schedules provided for each type of decision document in the Appendices.

Exceptions/Comments:

As part of scoping also consider non-RFCA authorities, including NEPA, air, water, Fish and Wildlife and wetlands issues. See the discussions at Section 2.6. Performance monitoring is required for all groundwater remedies and should be noted in the decision document. Details of the monitoring will be developed and implemented through the IMP. Similarly, performance monitoring will be required for some soil remedies, and if appropriate should be identified in the decision document. (See Section 3.4.E of the ALF).

Soil data generated as part of the decommissioning must be formally transferred and incorporated in the SWD. In addition, existing data that are "No Longer Representative" must be flagged in the database.

Activity: ACCELERATED ACTIONS
Location: INDUSTRIAL AREA

Sources of RFCA Authority:

CERCLA/RCRA Corrective Action
NCP Removal Action Authorities
EE/CA Guidance
Proposed RCRA Corrective Action Rule (as guidance)
RCRA Corrective Action Guidance (March 1996)
CHWA/RCRA Interim Status Closure Requirements (RFCA Attachment 10)

Potential Authorities External to RFCA:

Colorado Hazardous Waste Act and Rules
CHWA/RCRA Part B Permit
CHWA/RCRA Interim Status Requirements
Generator and transporter CHWA/RCRA Hazardous Waste Management Requirements
NRC Licensing Requirements for Off-site Disposal Facilities
Atomic Energy Act
DOE Orders
Colorado Air Pollution Prevention and Control Act and Rules
Colorado Water Quality Control Act and Rules
NPDES Permit
Stormwater Permitting Requirements
NEPA
NESHAP
OSHA
TSCA

Decision making Responsibility:

For accelerated action performed in the industrial area-

CDPHE - Primary; EPA - Review and Comment

Waste Management:

Wastes generated pursuant to a RFCA accelerated action are remediation wastes. In the industrial area, accelerated action remediation wastes are fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA (PCBs); as solid waste; as low level waste; as TRU waste; or any combination. Although fully regulated, if a CAMU becomes operational at some future time, the wastes remain "remediation wastes" and may be managed in the CAMU. Accelerated Action remediation wastes may also be handled in CAMU waste piles and temporary units in the industrial area, but these units would required full permitting.

Activity: ACCELERATED ACTIONS (continued)
Location: INDUSTRIAL AREA (continued)

At any time the accelerated action remediation wastes are shipped off-site they are fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination.

The CERCLA Off-site Rule determinations and updates will be maintained by the RFETS contract representative for each off-site disposal contract.

Water Management:

Remediation wastewater generated during accelerated actions can be managed, as appropriate, by free release where surface-water quality ARARs are attained; in the sewage treatment plant in accordance with the NPDES permit requirements; or in the CWTF in B891 if the remediation wastewater meets the CDPHE Wastewater Treatment Unit Policy. Authority for management in the CWTF must be provided in the decision document.

Permit Waiver:

Permit waivers for accelerated actions are limited in the industrial area to actions involving materials that are not also hazardous wastes or hazardous constituents (ie. radionuclides that are not mixed wastes, PCB, constituents that are CERCLA hazardous substances not identified in RCRA).

RCRA Closure:

During accelerated action, the complete or phased closure of permitted units, of interim status units and of IHSSs designated as "RCRA" in RFCA Appendix 3, may, at CDPHE discretion, use a separate closure plan or the accelerated action decision document. There are three types of accelerated action decision documents that may act in lieu of a permit modification: 1) IM/IRAs, 2) PAMs, 3) RSOPs. The substantive and administrative requirements for closure of permitted units are found in the Part B permit; and the requirements for closure of interim status units are found in Attachment 10 of RFCA.

Requirements Analysis:

A requirements analysis must be performed. Pursuant to the NCP, removal actions must attain ARARs to the extent practicable considering the exigencies of the circumstance. If an accelerated action decision document is used in lieu of a permit modification the applicable closure requirements, including post-closure care must be addressed by the decision document.

Modifications:

Field modifications, minor modifications and major modifications are allowed. See Section 3.10 for a complete discussion.

Activity: ACCELERATED ACTIONS (continued)
Location: INDUSTRIAL AREA (continued)

Public Involvement:

PAMs require a thirty-day public comment period. IM/IRAs and RSOPs require a forty-five to sixty-day public comment period, except for Class 3 permit modifications. Any IM/IRA that requires a Class 3 permit modification will be subject to dual sixty-day comment periods. Once public comment on the RSOP is complete, the RSOP may be invoked by letter notification to the parties. For a complete description see Section 5.0 and the sample schedules provided for each type of decision document in the Appendices.

Exceptions/Comments:

As part of scoping also consider non-RFCA authorities, including NEPA, air, water, and ecological concerns. See the discussions at Section 2.6.

Note that the RFCA Action Level Framework requires that groundwater performance monitoring be conducted in conjunction with remedial activities. (See ALF, Section 3.4E.). Similarly, the Industrial Area IM/IRA imposes groundwater, surface-water and air monitoring obligations on "non-routine activities" conducted in the Industrial Area that may effect groundwater, surface water or air. As such, the Industrial Area IM/IRA obligations must be considered and addressed during project scoping. Implementaion of the performace monitoring will be accomplished in accordance with the IMP.

Soil data generated as part of the accelerated action must be formally transferred and incorporated in the SWD. In addition, existing data that are "No Longer Representative" must be flagged in the database.

Activity: ACCELERATED ACTIONS
Location: BUFFER ZONE

Sources of RFCA Authority:

CERCLA/RCRA Corrective Action
NCP Removal Action Authorities
EE/CA Guidance
Proposed RCRA Corrective Action Rule (as guidance)
RCRA Corrective Action Guidance (March 1996)
CHWA/RCRA Interim Status Closure Requirements (RFCA Attachment 10)

Potential Authorities External to RFCA:

Colorado Hazardous Waste Act and Rules
CHWA/RCRA Part B Permit
CHWA/RCRA Interim Status Requirements
Generator and transporter CHWA/RCRA Hazardous Waste Management Requirements
NRC Licensing Requirements for Off-site Disposal Facilities
Atomic Energy Act
DOE Orders
Colorado Air Pollution Prevention and Control Act and Rules
Colorado Water Pollution Control Act and Rules
NPDES Permit
Stormwater Permitting Requirements
NEPA
NESHAP
OSHA
TSCA (PCBs)

Decision making Responsibility:

For accelerated action performed in the buffer zone-

EPA - Lead/Primary; CDPHE - Support, Review and Comment

Waste Management:

Wastes generated in pursuant to a RFCA accelerated action are remediation wastes. In the buffer zone permits for waste management are not required (see "permit waiver," below), but the waste management must comply with the substantive requirements of RCRA. If the accelerated action remediation wastes are moved into the industrial area for storage or treatment the wastes become fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination, if the wastes are moved into the industrial area.

Activity: ACCELERATED ACTIONS (continued)
Location: BUFFER ZONE (continued)

Although fully regulated in the industrial area, if a CAMU becomes operational at some future time, the wastes remain "remediation wastes" and may be managed in the CAMU. Remediation waste may also be managed in CAMU waste piles and temporary units (as ARAR) in the buffer zone but these units would require full permitting to handle accelerated action remediation wastes in the industrial area.

At any time the accelerated action remediation wastes are shipped off-site they are fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination

The CERCLA Off-site Rule determinations and updates will be maintained by the RFETS contract representative for each off-site disposal contract.

Water Management:

Remediation wastewater generated during accelerated actions can be managed, as appropriate, by free release where surface-water quality ARARs are attained; in the sewage treatment plant in accordance with NPDES permit requirements; or in the CWTF in B891 if the remediation wastewater meets the CDPHE Wastewater Treatment Unit Policy. Authority for management in the CWTF must be provided in the decision document.

Permit Waiver:

Permit waivers are available in the buffer zone. The basis for the permit waiver must be included in the decision document in accordance with RFCA §17.

RCRA Closure:

During accelerated action, the complete or phased closure of permitted units, of interim status units and of IHSSs designated as "RCRA" in RFCA Appendix 3, may, at CDPHE discretion, use a separate closure plan or an accelerated action decision document. There are three types of accelerated action decision documents that may act in lieu of a permit modification: 1) IM/IRAs, 2) PAMs, 3) RSOPs. The substantive and administrative requirements for closure of permitted units are found in the Part B permit; and the requirements for closure of interim status units are found in Attachment 10 of RFCA.

Requirements Analysis:

A requirements analysis must be performed. Pursuant to the NCP, removal actions must attain ARARs to the extent practicable considering the exigencies of the circumstance. If an accelerated action decision document is used in lieu of a permit modification the applicable closure requirements, including post-closure care must be addressed by the decision document.

Activity: ACCELERATED ACTIONS (continued)
Location: BUFFER ZONE (continued)

Modifications:

Field modifications, minor modifications and major modifications are allowed. See Section 3.10 for a complete discussion.

Public Involvement:

PAMs require a thirty-day public comment period. IM/IRAs and RSOPs require a forty five to sixty-day public comment period except for Class 3 permit modifications. Any IM/IRA that requires a Class 3 permit modification will be subject to dual sixty-day comment periods. Once public comment on the RSOP is complete, the RSOP may be invoked by letter notification to the parties. For a complete description see Section 5.0 and the sample schedules provided for each type of decision document in the Appendices.

Exceptions/Comments:

As part of scoping also consider non-RFCA authorities, including waste management, NEPA, air, water, and ecological concerns. See the discussions at Sections 2.6. Note that the RFCA Action Level Framework requires that groundwater performance monitoring be conducted in conjunction with groundwater remedial activities and in conjunction with some activities involving soil remediation. (See ALF, Section 3.4E.). Implementation of the performance monitoring will be accomplished in accordance with the IMP.

Soil data generated as part of the accelerated action must be formally transferred and incorporated in the SWD. In addition, existing data that are "No Longer Representative" must be flagged in the database.

Activity: CAD/ROD
Location: INDUSTRIAL AREA OU

Sources of Authority:

CERCLA

NCP Remedial Action Authority

CHWA/RCRA Corrective Action Authority

Proposed RCRA Corrective Action Rule (as guidance)

RCRA Corrective Action Guidance (March 1996)

Potential Authorities External to RFCA:

Colorado Hazardous Waste Act and Rules

CHWA/RCRA Part B Permit

CHWA/RCRA Interim Status Requirements

Generator and transporter CHWA/RCRA Hazardous Waste Management Requirements

NRC Licensing Requirements for Off-site Disposal Facilities

Atomic Energy Act

DOE Orders

Colorado Air Pollution Prevention and Control Act and Rules

Colorado Water Pollution Control Act and Rules

NPDES Permit

Stormwater Permitting Requirements

NEPA

NESHAP

OSHA

TSCA (PCBs)

Decision making Responsibility:

For hazardous constituents-

CDPHE lead for hazardous constituents pursuant to CHWA/RCRA

For radionuclides and hazardous substances-

DOE is CERCLA lead with CDPHE providing review, and if appropriate, concurrence recommendation to EPA for radionuclides and hazardous substances, with EPA then concurring with the DOE remedial decision if it is consistent with CERCLA.

Waste Management:

Wastes generated during remedial actions conducted pursuant to the CAD/ROD are remediation wastes. Permits for CAD/ROD waste management are not required (see "permit waiver," below), but the waste management must comply with the substantive requirements of RCRA.

Activity: CAD/ROD (continued)
Location: INDUSTRIAL AREA OU (continued)

The CERCLA Off-site Rule determinations and updates will be maintained by the RFETS contract representative for each off-site disposal contract.

At any time the CAD/ROD remediation wastes are shipped off-site they are fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination.

Water Management:

Remediation wastewater generated during final actions under a CAD/ROD can be managed, as appropriate, by free release where surface-water quality ARARs are attained; in the sewage treatment plant in accordance with the NPDES permit requirements; or in the CWTF in B891 if the remediation wastewater meets the CDPHE Wastewater Treatment Unit Policy. Authority for management in the CWTF must be provided in the decision document.

Permit Waiver:

Available for Concurrence CAD/ROD. The basis for the permit waiver must be included in the decision document in accordance with RFCA §17.

RCRA Closure:

If RCRA closures are completed during the CAD/ROD a separate permit modification must be prepared, submitted and approved.

Requirements Analysis:

A requirements analysis must be performed. Pursuant to the NCP, remedial actions must attain ARARs or invoke one of the CERCLA waivers.

Modifications:

Field modifications, minor modifications and major modifications are allowed. See Section 3.10 for a complete discussion.

Public Involvement:

Public comment must be provided in accordance with the NCP.

Exceptions/Comments:

As part of scoping also consider non-RFCA authorities, including NEPA, air, water, and ecological concerns. See the discussions at Section 2.6. Note that the RFCA Action Level Framework requires that groundwater performance monitoring be conducted in conjunction with remedial activities. (See ALF, Section 3.4E.).

The need to incorporate soil data generated as part of the final action under a CAD/ROD into the SWD should be determined during project scoping.

Activity: CAD/ROD
Location: BUFFER ZONE and Off-site OU

Sources of Authority:

CERCLA
NCP Remedial Action Authority
CHWA RCRA Corrective Action Authority
Proposed RCRA Corrective Action Rule
RCRA Corrective Action Guidance (March 1996)

Potential Authorities External to RFCA:

Colorado Hazardous Waste Act and Rules
CHWA/RCRA Part B Permit
CHWA/RCRA Interim Status Requirements
Generator and transporter CHWA/RCRA Hazardous Waste Management Requirements
NRC Licensing Requirements for Off-site Disposal Facilities
Atomic Energy Act
DOE Orders
Colorado Air Pollution Prevention and Control Act and Rules
NPDES Permit
Stormwater Permitting Requirements
NEPA
NESHAP
OSHA
TSCA (PCBs)

Decision making Responsibility:

For CAD/RODs in the Buffer Zone and Off-site-

EPA lead; CDPHE review and if concurrence, a "concurrence CAD/ROD" will be issued

Waste Management:

Wastes generated during remedial actions conducted pursuant to the CAD/ROD are remediation wastes. Permits for CAD/ROD waste management are not required (see "permit waiver," below), but the waste management must comply with the substantive requirements of RCRA.

At any time the CAD/ROD remediation wastes are shipped off-site they are fully regulated (substantively and procedurally) as either RCRA hazardous waste; as TSCA waste (PCBs); as solid waste; as low level waste; as TRU waste; or any combination.

The CERCLA Off-site Rule determination and updates will be maintained by the RFETS contract representative for each off-site disposal contract.

Activity: CAD/ROD (continued)
Location: BUFFER ZONE and Off-site OU (continued)

Water Management:

Remediation wastewater generated during final actions under a CAD/ROD can be managed, as appropriate, by free release where surface-water quality ARARs are attained; in the sewage treatment plant in accordance with the NPDES permit requirements; or in the CWTF in B891 if the remediation wastewater meets the CDPHE Wastewater Treatment Unit Policy. Authority for management in the CWTF must be provided in the decision document.

Permit Waiver:

Available for Concurrence CAD/ROD. The basis for the permit waiver must be included in the decision document in accordance with RFCA §17.

RCRA Closure:

If RCRA closures are completed during the CAD/ROD a separate permit modification must be prepared, submitted and approved.

Requirements Analysis:

A requirements analysis must be performed. Pursuant to the NCP, remedial actions must attain ARARs or invoke one of the CERCLA waivers.

Modifications:

Field modifications, minor modifications and major modifications are allowed. See Section 3.10 for a complete discussion. Note that major modifications require additional public notice and opportunity for public comment.

Public Involvement:

Public comment must be provided in accordance with the NCP.

Exceptions/Comments:

As part of scoping also consider non-RFCA authorities, including NEPA, air, water, and ecological concerns. See the discussions at Sections 2.6.

The need to incorporate soil data generated as part of the final action under a CAD/ROD into the SWD should be determined during project scoping.

Activity: SITE-WIDE TREATMENT
Location: SITE-WIDE

Sources of Authority:
(reserved)

Potential Authorities External to RFCA:
(reserved)

Decision making Responsibility:
Joint.

Waste Management:
(reserved)

Permit Waiver:
(reserved)

RCRA Closure:
(reserved)

Requirements Analysis:
(reserved)

Modifications:
(reserved)

Public Involvement:
(reserved)

Exceptions/Comments:
(reserved)

Kaiser-Hill Environmental Compliance and Operations Group
ENVIRONMENTAL CHECKLIST
ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

1. Project Name:
2. Date Submitted:
3. NEPA Tracking No.:
4. Charge Number:
5. WAD Number:
6. Project Manager (company, bldg., ext.):
7. Kaiser-Hill Manager (bldg., ext.):
8. Prepared By (company, bldg., ext.):
9. Project Description (be as detailed and specific as possible, use the checklist as a guide for issues to be addressed in the description of the project, submit to K-H NEPA for review):

Reviewed for Classification/UCNI

By: _____

Date: _____

HHC
136

	<u>YES</u>	<u>NO</u>	<u>NOTES</u>
10. Will the project require a new or modified permit under the:			
A. Clean Air Act? (e.g., APENs, Rad-NESHAP, fugitive dust, etc.)	_____	_____	
B. Clean Water Act? (e.g., discharges, chemicals, etc.)	_____	_____	
11. Resource Conservation and Recovery Act (RCRA):			
A. Will the project generate, treat, store, or dispose of hazardous, radioactive, or mixed waste?	_____	_____	
B. Will the project involve a removal?	_____	_____	
C. Will the project include RCRA closure?	_____	_____	
-partial?	_____	_____	
-full?	_____	_____	
D. Will the project include excavation or capping to meet RCRA requirements?	_____	_____	
E. Will cost and duration stay within \$5 million and 60 months? (Explain in Section 9, Project Description)	_____	_____	
F. Will a RCRA permit or permit modification be required?	_____	_____	
12. Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)			
A. Is the project part of an activity required in the Rocky Flats Cleanup Agreement?	_____	_____	
B. If the answer to A. is YES, is the project described in a document that has been approved by EPA or CDPHE, or will be approved by at least one of those agencies before project work begins?	_____	_____	
C. If the answers to both A. and B. are YES, has that document been reviewed by the K-H NEPA group for inclusion of NEPA values?	_____	_____	
13. Monitoring			
A. Will the project require performance monitoring per RFCA or IA IM/IRA requirements?	_____	_____	
B. If the answer to A is YES, have appropriate steps been taken to implement those requirements through the Integrated Monitoring Plan?	_____	_____	

143

137

2/23/98

	<u>YES</u>	<u>NO</u>	NOTES
14. Toxic Substances Control Act			
A. Will the project require an Asbestos Abatement permit?	_____	_____	
B. Will the project generate PCB-containing waste?	_____	_____	
C. Will the project result in any potential PCB-containing material that would be available for commercial resale, reuse, or recycle?	_____	_____	
15. Have all steps been taken to ensure compliance with procedures 1-G98-EPR-END.04, Migratory Bird Evaluation and Protection, and 1-D06-EPR- END.03, Identification and Protection of Threatened, Endangered, and Special-Concern Species?	_____	_____	
16. Will the project be in or near an Individual Hazardous Substance Site (IHSS)? (If YES, discuss in Section 9, Project Description)	_____	_____	
17. Will the project construct or require a new or expanded waste disposal, recovery, storage, or treatment facility?	_____	_____	
18. Is the project part of an agreement between DOE and another federal or state agency? (Specify and explain any schedule urgency and deadlines in Section 9, Project Description.)	_____	_____	
19. Is the project:			
A. A new process, building, etc.?	_____	_____	
B. A modification to an existing process, building, etc.?	_____	_____	
C. An installation of capital equipment?	_____	_____	
20. Will the project be located in or adversely affect:			
A. Wetlands? (i.e., dredge or fill operations)	_____	_____	
B. Designated natural areas?	_____	_____	
C. Prime agricultural land?	_____	_____	
D. Special water sources?	_____	_____	
E. Historical, archaeological, or architectural sites or buildings? (NHPA, HUD)	_____	_____	
F. Impact surface water or groundwater	_____	_____	
G. Effect Preble's Mouse habitat (DOE contact USFWS)	_____	_____	

	<u>YES</u>	<u>NO</u>	NOTES
21. Will the project result in, or have the potential to result in, long term changes to the environment?	_____	_____	
22. Will the project result in changes or disturbances of the following existing conditions:			
A. Noise levels?	_____	_____	
B. Solid wastes?	_____	_____	
C. Radioactive wastes? (including disturbed or excavated contaminated soil)	_____	_____	
D. Hazardous waste?	_____	_____	
23. Will the project have effects on the environment which are likely to be publicly controversial?	_____	_____	
24. Will the project establish a precedent for future projects that will have significant effects, or represent a "decision in principle" about a future consideration?	_____	_____	
25. Is the project related to other projects or to a larger program?	_____	_____	
25. Have pollution prevention measures been considered? (Discuss in Section 9, Project Description.)	_____	_____	
26. Does/Will the project present a radiation health and safety concern during construction or operation? (Price-Anderson Act)	_____	_____	

NOTES:

Approved by Company's (RMRS, SSOC, K-H, WSI, or DCI) Environmental Manager:

Signature _____

Date _____

2/23/98

Best Available Copy

APPENDIX C

1.0 PREPARATION OF AN ER INTERIM MEASURE/INTERIM REMEDIAL ACTION DOCUMENT

RFCA ¶107 describes the IM/IRA process. That paragraph states:

The draft IM/IRA shall contain a brief summary of data for the site, a description of the proposed action, an explanation of how waste management considerations will be addressed, an explanation of how the proposed action relates to any long-term remedial action objectives, proposed performance standards, all ARARs and action levels related to the proposed action; and an implementation schedule and completion date for the proposed action.

1.1 IM/IRA Format and Content

IM/IRAs are utilized for accelerated actions that will require more than six months for project execution and/or where the remedy is not straightforward and multiple alternatives have been evaluated. Alternative evaluation and selection are not necessary if a presumptive remedy has been selected. The suggested format for an IM/IRA is outlined below. In general, for actions where a formal alternatives analysis is performed, the IM/IRA will follow the format of EPA Guidance on *Conducting Non-time Critical Removal Actions Under CERCLA*, (August 1993.) The EE/CA process is one method of performing a streamlined alternatives development and screening, and should be the upper bound of complexity for the IM/IRA Document. The intent of this guidance is to allow the complexity of the decision document to be based on the complexity of the project.

If an alternatives analysis is performed, the first part of the IM/IRA should describe the project to be performed using the selected remedy. The second part of the IM/IRA should describe the remedy selection process, and explain which remedy was selected and why.

The sections of an IM/IRA should include:

- Executive Summary (Optional)
- Purpose
- Project Description
- Project Approach
- Environmental Impacts
- Compliance with ARARs
- Implementation Schedule

The following sections are necessary if an alternatives analysis is performed:

- Initial Selection and Screening of Alternatives
- Analysis of Alternatives

- Comparative Analysis of Alternatives and Remedy Selection
- Responsiveness Summary

The selected remedy will be described in the first part of the IM/IRA. The Responsiveness Summary will be included in either case.

1.2 EXECUTIVE SUMMARY

The Executive Summary provides a general overview of the contents of the IM/IRA and is recommended only for complex problems where special issues are involved and/or where a formal alternative evaluation is performed. The summary should include a brief description of the IHSS or site, the nature of the contamination and related risks (or exceedence of action levels) and scope and objectives of the proposed removal action/interim measure. If a presumptive remedy has been selected, a short statement of why the presumptive remedy is appropriate should be included. If an alternatives analysis was performed, a brief discussion of the alternatives considered and basis for selection of the preferred alternative should be provided. Depending on the length and complexity of the IM/IRA, the Executive Summary is optional.

1.3 INTRODUCTION

The introduction should briefly state:

- The nature of the contamination
- The proposed action
- The intent or goal of the proposed action

The introduction should state whether a presumptive remedy was selected, and why the remedy is appropriate (e.g., a similar remedy has been used in the past for similar contamination or type of problem). If an alternative analysis was performed, the introduction should state why a presumptive remedy was not selected (e.g., the setting or combination of contaminants, special hazards or other project-specific issues).

1.4 SITE DESCRIPTION

The site description will provide IHSS/site information including the contamination history, geological and hydrogeological conditions, remedial investigation data, and a brief summary of risks posed by the contamination and how the action mitigates those risks. If the action is based on exceedence of the RFCA Action Levels, discuss how the action addresses these exceedences. This section will also include a brief description of how the proposed action is consistent with any long-term remedial objectives. If appropriate, the following Background,

General Conditions, and Data Summary subsections can be combined into one section: Existing Conditions and Conceptual Model.

1.4.1 Background

The background section will describe the nature and history of the contamination source. This may include historical information on spills or other releases, any waste operations associated with the contamination, and the relationship between the contamination and other IHSSs.

1.4.2 General Conditions

This summary describes the site-specific conditions or pertinent data to support the rationale for undertaking the action, such as the geological and hydrogeological conditions of the area to be remediated.

Only information relevant to the proposed action should be discussed. General discussions of the site geology, geographic setting, and other general physical characteristics should be referenced to existing documents, such as the sitewide geochemistry and hydrogeology reports.

1.4.3 Data Summary

This section summarizes past remedial investigations or any other available relevant data.

This would include, if relevant:

- Appropriate field investigations such as HPGe surveys, soil gas surveys, etc.
- Groundwater, surface water, soil and/or other relevant analytical results
- Field observations
- Waste disposal data and history
- Any other appropriate, available historical data

The information from the above sections may be presented in a plan view (map), a cross-section (if appropriate), tabular form, or narrative. Locations of relevant sampling points should be shown in relation to the site or area to be remediated. It is helpful to integrate the available data into a conceptual model showing the relationship of the contamination to groundwater, buildings and other structures, surface water, slopes, underground utilities, and other physical items that may impact the project execution.

1.5 PROJECT APPROACH

Proposed Action Objectives narrative remedial and numerical goals are described here. This should be a brief and concise statement of the intended objectives of the action. Remedial

action objectives will include meeting specified cleanup targets for the media being remediated.

If an alternatives analysis was performed, briefly state here specifically what the selected remedy is, and the basis for selection. Refer to the following sections for details on how this remedy will be implemented. If no alternatives analysis was performed, address the reason that the No Action Alternative was not selected (i.e., the site poses a risk, contaminants are above specified action levels, etc.).

1.5.1 Proposed Action

This section details the proposed action including the scope of the action, the proposed remediation methodology, cleanup levels, and site restoration. Where applicable, these details would include information on:

- The scope or extent of the action, including projected volumes of any environmental media to be removed and/or treated
- Excavation methods
- Material handling
- Groundwater or surface water containment and/or recovery methods
- Treatment methods for water, soils, sediments, debris, or other materials generated, including tabulated performance standards for treatment
- Transportation or staging requirements
- Any control measures to minimize the environmental impact of the proposed action (i.e., dust suppression, containment measures, surface water protection)
- Performance monitoring in accordance with the IMP
- Site restoration including any revegetation, backfilling, or regrading

Sampling and analysis requirements will be deferred to the project-specific SAP developed in accordance with the guidelines in Section 3.2 of the IGD.

1.5.2 Worker Health and Safety

This section will include a brief description of the basis for the health and safety requirements, the hazards, monitoring requirements, personal protective equipment (PPE), and actions to protect human health. Action-specific HASP and Hazards Analysis (HA) will be prepared separately.

1.5.3 Waste Management

This section will describe the storage requirements and final disposition of all waste streams that will be generated. Remediation wastes are defined in RFCA ¶25bf as:

Remediation waste means all:

- (1) Solid hazardous, and mixed wastes;*
- (2) All media and debris that contain hazardous substances, listed hazardous or mixed wastes that exhibit a hazardous characteristic; and*
- (3) All hazardous substances generated from activities regulated under this Agreement as RCRA corrective actions or CERCLA response actions, including decommissioning.*

Remediation waste does not include wastes generated from other activities. Nothing in this definition confers RCRA or CHWA authority over source, special nuclear, or byproduct material as those terms are defined in the Atomic Energy Act.

1.6 NEPA

This section is included to identify how NEPA values are incorporated into the decision document. Ideally the NEPA values will be woven throughout the decision document so that they are considered at all phases of the decision making. This section provides an opportunity to reiterate how NEPA values may have been considered in other parts of the decision document, and to touch upon other NEPA values that may not have been directly addressed. The NEPA values to be considered include:

- Air quality during construction and operation of the project
- Water quality (including both surface water, wetlands, and groundwater and the flow characteristics of each)
- Flora and fauna (including threatened and endangered species)
- Historic and cultural resources
- Human health
- Consideration of alternatives including no action
- Irreversible and ir retrievable commitment of resources
- Short-term versus long-term use of the proposed site
- Indirect effects
- Cumulative effects (effects from the current project added to the effects from other known projects affecting the same site)

1.7 COMPLIANCE WITH ARARS

This section consists of an analysis of Federal and State ARARs. Chemical-specific, location specific, and action-specific ARARs are identified and tabulated. Section 3.5 of the IGD discusses development and selection of ARARs.

1.8 IMPLEMENTATION SCHEDULE

This section will include a general schedule of when the project is to be implemented, including commencement of field activities and report generation. The format of the schedule will be project-specific. Milestones will be presented at a summary level with nonspecific dates, e.g., "field activities will commence in the second quarter of 1999."

2.0 INITIAL SELECTION AND SCREENING OF ALTERNATIVES

Only a limited number of alternatives (two to four) need to be considered for the IM/IRA. Only the most qualified technologies and/or alternatives that apply to the chemicals of concern (COCs) and affected media need be considered. To the extent possible, presumptive remedies or previous actions for similar situations should be used as a basis for decisions. In these cases, the decision document should reference previous decision documents whenever possible, with the intent of minimizing decision processes.

Each of the alternatives should be discussed in sufficient detail so that the entire process can be understood. For example, treatment and/or disposal of residuals resulting from the remedy should be addressed.

The selected alternatives are evaluated for effectiveness, implementability, and cost. This evaluation is based on the scope of the IM/IRA and each of its specific objectives. The evaluation encompasses the criteria addressed in a full scale CMS/FS, but is done in a much more streamlined manner. The following discussion provides more detailed descriptions of each criterion. The EPA *Guidance on Conducting Non-Time Critical Removal Actions under CERCLA* (EPA, 1993) should be consulted for a description of the alternative screening and evaluation process.

2.1 EFFECTIVENESS

This criteria considers whether or not the alternative provides protection of public health and the environment. Long-term effectiveness, short-term effectiveness, and compliance with ARARs are evaluated for overall protection of public health and the environment.

Short-term effectiveness relates to the protection provided during implementation and before the IM/IRA objectives have been met. It addresses such items as impacts due to fugitive dusts, transportation of hazardous materials, and toxic fumes produced during implementation. Impacts on the local community, the workers implementing the action, and the environment are included.

Long-term effectiveness addresses the level of risk remaining after the action has been completed and the need for addition of controls. The degree to which the alternative reduces toxicity, mobility or volume of contamination and how this in turn reduces risk or potential threats is also discussed.

This section must summarize ARARs for the proposed IM/IRA action. The requirements should be presented as a summary table in the IM/IRA Decision Document, with a brief discussion in the text of this section. The alternatives evaluation will include a discussion, in general terms, of whether or not they can be complied with and what cost and schedule impacts pertain to each alternative. A detailed ARARs evaluation will be included elsewhere in the IM/IRA.

2.2 IMPLEMENTABILITY

This criteria addresses the technical and administrative feasibility of implementing an alternative and the availability of the services and materials required. Technical feasibility relates to the maturity and complexity of the technology being evaluated. Construction feasibility, and operations and maintenance requirements are also considered.

Administrative feasibility relates to the need for coordination with other offices and agencies, such as requirements for building permits, easements, or zoning variances. Availability of services and materials relates to the need for skilled labor/technicians to operate the technology/process, offsite treatment/storage/disposal, utilities, and laboratory services.

Finally, the implementability criteria includes a consideration of the acceptability of the alternatives to the State and local community.

2.3 COST

Evaluation of costs should consider the capital costs to engineer, procure, and construct the required equipment and facilities, and the operating and maintenance costs associated with the alternative. The cost estimates can be "order-of-magnitude" with sufficient accuracy to allow comparison and ranking of the alternatives on a present worth basis for alternatives that involve more than one year of operation and maintenance. For the alternative evaluation section of the IM/IRA, the alternatives will be compared on a qualitative basis using descriptors such as high, medium, or low.

The results of the analysis will be presented in the IM/IRA Decision Document for each alternative evaluated. This analysis will be summarized in a table similar to Table 2-1.

Based on the analysis, a decision will be made as to whether or not each alternative considered should be retained for the comparative analysis, which is discussed in the next section. The reason for eliminating an alternative should also be discussed.

Table 2-1 Initial Screening of Alternatives

EFFECTIVENESS
Protectiveness
Public Health
Workers
Environment
Attains ARARs
Achieve Remedial Objectives
Level of treatment/containment
No residual effect concerns
Maintains control until long-term solution implemented
IMPLEMENTABILITY
Technical Feasibility
Construction and operation
Demonstrated performance
Adaptable to environmental conditions
Need for permits
Availability
Equipment
Personnel and services
Outside laboratory testing
Offsite treatment and disposal
Post-removal site control
Administrative Feasibility
Permits required
Easements of right-of-ways required
Impact on adjoining property
Ability to impose institutional controls

COST

Capital Cost

Operation and Maintenance

Present worth cost

2.4 COMPARATIVE ANALYSIS OF ALTERNATIVES

Alternatives that pass the initial screening based on effectiveness, implementability, and cost are now compared against each other. At this point a remedy may be selected if there is an obvious benefit to a single remedy during the initial screening. The purpose of the comparative analysis is to identify the advantages and disadvantages of each alternative relative to one another so that one of them can be identified as the recommended action.

The actual comparison may be made on a semi-quantitative ranking system based on effectiveness, implementability and cost. After each category has been scored, a total score (low, medium, high) is obtained. The alternative with the highest score would probably be the recommended alternative, assuming that it is cost effective. Generally, a matrix indicating the relative scores of the alternatives and the justifications for the scores is the best method for presentation.

If there is no best alternative by this method, it may be necessary to add additional criteria and/or weighing factors to the criteria to differentiate between the alternatives.

2.5 RESPONSIVENESS SUMMARY

The approved responsiveness summary from the public comment period will be attached to the final approved IM/IRA.

3.0 GENERIC IM/IRA SCHEDULE

The attached generic schedule is for the development of an IM/IRA. Variations for each IHSS may influence the duration of specific activities. This schedule may be used as a planning basis.


4.0 COMMENT RESPONSIVENESS SUMMARY

This section will be included to document responses to public and agency comments if a separate responsiveness summary is not created.

5.0 DECISION MODIFICATION PROCESS

The decision modification process for IM/IRAs is discussed in Section 3.10 of the IGD, and in Part 10 of the RFCA.

Generic IM/IRA Schedule



Task IM/IRA GENERIC SCHEDULE Progress Summary

APPENDIX D

1.0 PREPARATION OF AN ER PROPOSED ACTION MEMORANDUM

1.1 PAM FORMAT

RFCA ¶106 describes the PAM process:

The Draft PAM shall contain a brief summary of data for the site; a description of the proposed action; an explanation of how waste management considerations will be addressed; an explanation of how the proposed action relates to any long-term remedial action objectives; proposed performance standards; all ARARs and action levels related to the proposed action; and an implementation schedule and completion date for the proposed action.

The PAM is the decision document for accelerated response action requiring less than six months for project execution. The length and complexity of the PAM will depend on the complexity of the project. The development of the sections included in a PAM is discussed in the following sections.

The sections of a PAM include:

- Purpose
- Project Description
- Background
- Project Approach
- Environmental Impacts
- Compliance with ARARs
- Implementation Schedule
- Comment Responsiveness Summary

1.2 PURPOSE

This introduction briefly states:

- The nature of the contamination
 - The proposed action
-

153
162

- the intent or goal of the proposed action

1.3 SITE DESCRIPTION

The project description provides site information including history, geological and hydrogeological conditions, remedial investigation data, a brief summary of risks posed by the site and how the action will mitigate the risks. This section will also include a brief description of how the proposed action is consistent with any long-term remedial objectives. If appropriate, the Background, General Conditions, and Data Summary subsections can be combined into one section entitled Existing Conditions and Conceptual Model. The section would contain the same information and integrate it into a conceptual model of the site, including known and expected contaminant distribution and factors expected to impact the project (e.g., shallow groundwater).

1.3.1 Background

The background section describes the nature and history of the contamination source. This potentially includes historical information on spills or other types of releases, any waste operations associated with the contamination, and the relationship between the contamination and other IHSSs.

1.3.2 General Conditions

This summary describes site-specific conditions or pertinent data to support the rationale for undertaking the action such as the geological and hydrogeological conditions of the area to be mitigated. Information relevant to the action may include:

- Underlying stratigraphy
- Depth to groundwater
- Saturated thickness
- Mean hydraulic, conductivity, and gradient
- Seasonal effects
- Any relevant information on seeps or surface water locations

Only information relevant to the proposed action should be discussed. General discussions of the site geology, geographic setting, and other physical characteristics should be referenced to existing documents.

1.3.3 Data Summary

This section summarizes past remedial investigations. This would include, if relevant:

- Geophysical survey information
- Borehole sampling results
- Groundwater sample results
- Surface water sample results
- Surface soil, sludge, or sediment sample results
- Field screening results
- Free product samples and thickness measurements
- Samples and smears from tanks and pipelines
- Field observations
- Any other appropriate, available historical data

1.4 PROJECT APPROACH

This section provides a brief and concise statement of the intended objective of the accelerated action.

1.4.1 Proposed Action Objectives

This section details the proposed action including the scope of the action, the proposed remediation methodology, cleanup levels, and site restoration. Where applicable, these details would include information on:

- The scope or extent of the action including projected volumes of any environmental media removed and/or treated
 - Excavation methods
 - Material handling
 - Groundwater or surface water recovery methods
 - Treatment methods for water, soils, sediments, debris, or excess equipment, including tabulated performance standards for treatment
 - Transportation or staging requirements
 - Any control measures to minimize the environmental impact of the proposed action, (e.g., dust suppression, and containment measures)
-

- Performance monitoring in accordance with the IMP
- site restoration including any revegetation, backfilling, or regrading

Discussion of sampling and analysis will be deferred to the project-specific sampling and analysis plan developed as per the guidelines in Section 3.2 of the IGD.

1.4.2 Worker Health and Safety

This section will include a brief description of the basis for health and safety requirements, the hazards, monitoring requirements, PPE, and actions to protect human health. An action-specific HASP will be prepared separately.

1.4.3 Waste Management

This section will describe the storage and management requirements and final disposition of all waste streams that will be generated. Remediation wastes are defined in RFCA ¶25bf as:

Remediation waste means all:

- 1) *Solid hazardous, and mixed wastes;*
- 2) *All media and debris that contain hazardous substances, listed hazardous or mixed wastes that exhibit a hazardous characteristic; and*
- 3) *All hazardous substances generated from activities regulated under this Agreement as RCRA corrective Actions or CERCLA response actions, including decommissioning.*

Remediation waste does not include wastes generated from other activities. Nothing in this definition confers RCRA or CHWA authority over source, special nuclear, or byproduct material as those terms are defined in the Atomic Energy Act.

1.5 NEPA

This section is included to identify how NEPA values are incorporated into the decision document. Ideally the NEPA values will be woven throughout the decision document so that they are considered at all phases of the decision making. This section provides an opportunity to reiterate how NEPA values may have been considered in other parts of the

decision document, and to touch upon other NEPA values that may not have been directly addressed. The NEPA values to be considered include:

- Air quality during construction and operation of the project
- Water quality (including both surface water, wetlands, and groundwater and the flow characteristics of each)
- Flora and fauna (including threatened and endangered species)
- Historic and cultural resources
- Human health
- Limited consideration of alternatives including no action, as appropriate
- Irreversible and irretrievable commitment of resources
- Short-term versus long-term use of the proposed site
- Indirect effects
- Cumulative effects (effects from the current project added to the effects from other known projects affecting the same site)

1.6 COMPLIANCE WITH ARARS

This section consists of an analysis of federal and state ARARs. Chemical-specific, location-specific, and action-specific ARARs are identified and summarized in a table. Section 3.5 of the IGD discusses identification and evaluation of ARARs.

1.7 IMPLEMENTATION SCHEDULE

This is a general project schedule including commencement of field activities and report generation. The format of the schedule will be project-specific. Milestones will only be presented at a summary level with nonspecific dates (e.g., "field activities will commence in the second quarter of 1999"). The attached generic schedule for PAMs may be used as a starting point for project planning.

1.8 COMMENT RESPONSIVENESS SUMMARY

This section will be included if a separate responsiveness summary is not created. Written comments from the public comment process will be documented followed by responses to individual or group comments that have similar focus.

GENERIC PAM SCHEDULE

ID	Task Name	Duration	Month 1					Month 2					Month 3					Month 4					Month 5				
			1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22			
1	Scoping	30d	Depends on project complexity																								
2	PAM	110d	Depends on project complexity																								
3	Prepare Draft PAM	21d	Depends on project complexity																								
4	Internal Review Draft PAM	7d	Depends on project complexity																								
5	DOE Review Draft PAM	7d	Depends on project complexity																								
6	Revise Draft PAM	7d	Depends on project complexity																								
7	Submit Draft PAM for Agency/Public Comment	1d	Depends on project complexity																								
8	Agency/Public Comment Review	30d	Depends on project complexity																								
9	Incorporate Agency/Public Comments and Develop RS	14d	Depends on project complexity																								
10	Submit Revised PAM and Responsiveness Summary	1d	Depends on project complexity																								
11	LRA PAM Approval/Disapproval	7d	Depends on project complexity																								
12	Incorporate LRA Changes (if disapproved)	14d	Depends on project complexity																								
13	PAM Approval (if revised)	1d	Depends on project complexity																								

Based on good cause, LRA may extend 7 days

		GENERIC NFA SCHEDULE																																																							
ID	Task Name	Duration	Week 1					Week 2					Week 3					Week 4					Week 5					Week 6					Week 7					Week 8					Week 9					Week 10					Week 11				
			1	3	5	7	9	11	13	15	17	19	21	23	25	27	29	31	33	35	37	39	41	43	45	47	49	51	53	55	57	59	61	63	65	67	69	71																			
1	Prepare NFA Documentation	14d	[Gantt bar from Week 1 Day 1 to Week 2 Day 13]																																																						
2	Submit NFA to HRR	3d	[Gantt bar from Week 2 Day 15 to Week 2 Day 18]																																																						
3	Prepare HRR for Annual Agency Submittal	7d	[Gantt bar from Week 3 Day 17 to Week 3 Day 24]																																																						
4	Submit HRR to Agencies	1d	[Gantt bar from Week 4 Day 25]																																																						
5	Agency Review	21d	[Gantt bar from Week 4 Day 27 to Week 6 Day 17]																																																						
6	Receive Agency Comments	1d	[Gantt bar from Week 7 Day 47]																																																						
7	Resolve Agency Comments	7d	[Gantt bar from Week 8 Day 51 to Week 8 Day 58]																																																						
8	Revision	7d	[Gantt bar from Week 9 Day 61 to Week 9 Day 68]																																																						
9	Submit to Agencies for Approval	1d	[Gantt bar from Week 10 Day 71]																																																						
10	Agency Approval for Release	7d	[Gantt bar from Week 11 Day 75 to Week 11 Day 82]																																																						

Project Generic NFA Schedule


Task

Progress

Appendix F

PROPOSED PLAN AND CAD/ROD SCHEDULE

GENERIC CAD/ROD SCHEDULE



Project: Generic CAD/ROD Schedule Task Progress

Best Available Copy

GENERIC RF/IRI SCHEDULE

ID	Task Name	Duration	Month 1	Month 5	Month 9	Month 13	Month 17	Month 21	Month 25	Month 29
1	Develop RF/IRI Work Plan	30d								
2	Internal Review	14d								
3	Receive Comments	1d								
4	Revise Workplan	7d								
5	Submit to Agencies for Review and Comment	1d								
6	Agency Review	14d								
7	Receive Agency Comments	1d								
8	Resolve Agency Comments	14d								
9	Revise Workplan	14d								
10	Submit Workplan for Approval	1d								
11	Agency Review and Approval	7d								
12	Prepare for Fieldwork	90d								
13	Perform Fieldwork	60d								
14	Receive Analytical Results	0d								
15	Develop RF/IRI Report and HHRA	90d								
16	Preliminary Review RF/IRI Report	14d								
17	Revise Preliminary Draft	21d								
18	Document Production	114d								
19	Submit RF/IRI Report for Agency Review	1d								
20	Agency Review	30d								
21	Develop Comment Responses	14d								
22	Submit Comment Responses to Agencies	1d								
23	Agency Review of Comment Responses	14d								
24	Revise RF/IRI Report	30d								
25	Document Production	14d								
26	Submit Final RF/IRI to Agencies	1d								

Project: Generic RF/IRI Schedule

Task

Progress

APPENDIX G

1.0 GENERIC RCRA FACILITY INVESTIGATION/REMEDIAL INVESTIGATION SCHEDULE

Contents

The contents of an RFI/RI Report may include, but is not limited to the following:

- Description of the IHSS
- A summary of all field activities
- Presentation of all field data
- Location and characteristics and source(s) of contamination
- Definition on nature, extent, fate, and transport of contaminants
- Identification of sources which impact surface water
- Evaluation of risks

A generic schedule for the development of an RFI/RI Report is included. While actual activity durations may vary according to the complexity of the IHSSs, this schedule may be used for planning purposes.

APPENDIX H

1.0 CORRECTIVE MEASURES STUDY/FEASIBILITY STUDY PREPARATION

The CMS/FS report summarizes the results of the RFI/RI and the baseline risk assessment. Based upon that summary, risk and ARARs-based narrative remedial action objectives and where appropriate numeric remedial action goals are developed. Based upon the statement of objectives and goals, technologies are identified and evaluated for feasibility, screened against the criteria enumerated in the NCP, and ultimately compared one against another.

A suggested outline for the development of the CMS/FS is discussed in the following sections. It must be understood that the remedial action objectives control the types of technologies and process options considered.

The sections of a CMS/FS include:

- Executive Summary
- Introduction
- Site Characteristics
- Corrective/Remedial Action Objectives
- Identification and Screening of Alternatives
- Detailed Analysis of Alternatives
- Selected Alternative (Optional)

1.1 EXECUTIVE SUMMARY

The Executive Summary outlines the site characteristic, risk factors, and ARARs considerations essential to developing the remedial action objectives and then clearly presents the remedial action objectives. The processes and factors that proved crucial to identifying and framing alternatives are then highlighted and followed by a comparison of each alternative to the nine criteria. The selected alternative may then be presented with further discussion of relevant factors that demonstrate satisfaction of the criteria.

1.2 INTRODUCTION

The introduction provides information as to the framework to which the CMS/FS is being prepared, a list of acronyms and an outline of each section of the report.

1.3 SITE CHARACTERISTICS

This section describes the nature and history of the contamination source(s).

1.4 CORRECTIVE/REMEDIAL ACTION OBJECTIVES

This section summarizes the risk assessment, provides an overview of location and action specific ARARs, and defines chemical specific ARARs. The risk assessment results and ARARs are then used to develop narrative remedial action objectives, and, where appropriate, numeric remedial action goals.

1.5 IDENTIFICATION AND SCREENING OF ALTERNATIVES

Based upon the narrative remedial action objectives and numeric remedial action goals, remedial technologies and process options are first identified and screened. The remedial technologies and process options are then assembled into alternatives, and screened as to effectiveness, implementability and relative cost.

1.6 DETAILED ANALYSIS OF ALTERNATIVES

The alternatives which are retained following the screening are now further refined as to technical detail and cost. The refined alternatives are then evaluated against the nine evaluation criteria:

- Overall protection of human health and the environment
- Attainment of ARARs
- Long-term protectiveness
- Short-term effectiveness
- Implementability
- Cost
- State acceptance
- Community acceptance

GENERIC CMS/FS SCHEDULE

ID	Task Name	Duration	Month 1				Month 2				Month 3				Month 4				Month 5				Month 6				Month 7				Month 8				Month 9										
			1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40			
1	Prepare Draft CMS/FS	60d																																											
2	Internal Review Draft CMS/FS	14d																																											
3	Revise Draft CMS/FS	14d																																											
4	Submit Draft CMS/FS for Agency Review	1d																																											
5	Agency Review	30d																																											
6	Receive Agency Comments	1d																																											
7	Develop Comment Responses	14d																																											
8	Comment Resolution Meeting	1d																																											
9	CMS/FS Revision Per Comment Resolution Meeting	14d																																											
10	Agency Approval for Release	14d																																											
11	Public Comment Period	30d																																											
12	Incorporate Public Comments	14d																																											
13	Submit Revised CMS/FS	1d																																											
14	CMS/FS Approval	7d																																											
15	Incorporate Final Agency Comments	14d																																											
16	Final Agency Approval	0d																																											

APPENDIX I

1.0 OUTLINE OF SAMPLING AND ANALYSIS PLAN

The following SAP outline is based on *Guidance for Conducting Remedial Investigation and Feasibility Studies Under CERCLA* (EPA, 1988a) and reflects current RFETS usage. Each SAP will vary, however, depending on the data and sample requirements. SAPs will generally include information on the following topics:

- Background information
- Sampling rationale
- DQOs
- Sampling activities and methodology
- Data management
- Project organization
- Health and Safety Plan
- Quality Assurance
- Schedule

These outline topics are described in the following sections.

2.0 INTRODUCTION

The introduction will provide a brief project background and description including:

- Purpose/objectives of the SAP
- History of the site to be sampled (identify IHSSs, PACs or RCRA units in the area)
- Summary of existing data with an assessment of its adequacy
- Description of the project including planned field activities
- Hydrogeologic setting (if appropriate to the project).

3.0 SAMPLING RATIONALE

This section will discuss the reasons and justification used to develop sampling factors such as number of samples, location, depths, frequency, COCs, and analytical methods. Conditions of the physical setting which influence these factors can also be discussed.

This section should typically include a brief conceptual model to identify and document the potential field conditions, factors that may impact sampling results, and potential for free product to be present. The conceptual model is intended to show how the site works physically and chemically in terms of expected conditions. The model may be presented as a cross-section of the contaminant distribution and potential transport mechanisms or items, structures, and physical conditions that may impact the project (e.g., presence of drums, depth to bedrock, depth to groundwater, steep slopes, location of surface water).

4.0 DATA QUALITY OBJECTIVES

The DQO process, as described in Section 3.2, is a structured decision-making process that requires the identification of and agreement on decisions for which data are required. The process results in the full set of specifications needed to develop a protective and compliance sampling program (i.e., qualitative and quantitative statements that specify the type, quality, and quantity of the data required to support decision making). The formal DQO process is documented in two EPA documents (EPA, 1993; EPA, 1994). Specific steps in the DQO process include:

- Identify and define problem(s) to be solved
- Identify decision(s) to be made relative to the problem
- Identify inputs to the decision (data needed to make decision)
- Define study boundaries/scope of problem and decision
- Develop decision rule(s) [IF/THEN action statement(s)]
- Specify limits on decision errors (acceptable types and degrees of uncertainty)
- Develop and optimize design for obtaining data

These steps are described below.

4.1 The Problem

Implementation of a sampling plan requires identification and disposition of contaminated media, materials, and equipment that were produced in past processes, especially relative to free release (of materials) or management of particular waste types or streams. Adequate samples must be taken to properly characterize and manage the materials and/or equipment, whether it is waste or not.

Other decisions or subdecisions that support final project actions may be put forth in the form of following questions, provided that the answers or conclusions relate directly to project decisions, e.g:

- Why perform this characterization?
- What is the final disposition of the material, equipment, facility, or structure (free release, restricted use, low level waste, etc.)?

4.2 The Decisions

The critical technical decisions for a typical project are as follows, understanding that decisions may vary relative to goals of the project:

- What materials (e.g., paint, concrete, pipe insulation, etc), media (e.g., soil, water, oil, solid, sludge, etc), or equipment within the facility or area are contaminated or, conversely, not contaminated
- What are the generic classification categories by which the materials, equipment, and/or media will be managed, relative to an eventual assignment as contaminated (hazardous, radiological, or mixed) or not contaminated (nonhazardous)? In other words, what are the categories of waste streams that will result from the activity? What are the ultimate dispositions (i.e., waste classifications and treatment, storage, and disposal [TSD] facilities) of the waste streams, including quantities (e.g., a completed summary table)?

4.3 Inputs to the Decisions

Inputs to the decisions are data, both qualitative and quantitative. Qualitative information will typically consist of nominal data (e.g., paint color, texture, or equipment type, etc) derived from visual observation of the building's equipment and materials. Quantitative data may be produced from analytical, radiochemistry, radiation surveys or petrographic analysis (asbestos) of samples. Waste Acceptance Criteria (WAC) are typically the drivers for decision inputs where data will be used to characterize waste streams destined for a particular TSD facility (e.g., NTS, Envirocare or USA waste). Inputs to the decisions are COC-specific.

Inputs to the decision must also include, directly or in other subsections, the following:

- analytical/radiochemistry results
- radiation survey results
- method-specific sensitivities (detection limits or minimum detectable activities)
- error tolerances associated with the measurements (e.g., accuracy and precision)
- action levels (regulatory thresholds)

Although professional judgment is instrumental, sampling must err to the conservative (i.e., collecting more samples) if there is any doubt regarding homogeneity of the materials sampled.

Other decisions or subdecisions that support final project actions may be put forth in the form of following questions, provided that the answers or conclusions relate directly to project decisions:

- What information is required to make this decision?
- What source(s) can be used to obtain the information?
- Can the desired analysis be done at RFETS or will the samples be shipped off-site for analysis?
- What types and kind of sampling measurements are required?
- What type of instrumentation is required?
- Has facility structural data been reviewed?
- What suspect materials have been identified?
- What are the required instrumentation sensitivities?
- What method will be used to obtain the desired information?
- What Quality Assurance (QA) program requirements are there for these samples (i.e., blanks, duplicates)?
- What number of samples/measurements will provide the desired certainty?
- Have data quantity and quality control requirements for sampling been reviewed?

4.4 Project Boundaries

Project boundaries describe the geographic, three-dimensional areas, and temporal boundaries of the characterization activity. Other decisions or subdecisions that support final project actions may be put forth in the form of following questions, provided that the answers or conclusions relate directly to project decisions:

- What is the sample population of interest?
- Are there any constraints on data collection?

4.5 Decision Rules and Error Limits

Decision rules must be based on objective, reproducible, and verifiable, measurable criteria. If the decision is statistically based, decision error must address both the producer's (alpha) error and the consumer's (beta) error. "False Positive" error is usually equivalent to the alpha error while the "false negative" is equivalent with beta error, although this determination hinges on the way in which the hypothesis test is setup. Alpha and beta error typically range from 1% to 10% (i.e., confidences from 99% to 90%, respectively), based on standard statistical practice and historical acceptance by the regulators (public, CDPHE, and EPA Region VIII).

Decisions may also be based directly on protocols promulgated by the regulators, for example determination of asbestos. Other decisions or subdecisions that support final project actions may be put forth in the form of the following questions, provided that the answers or conclusions relate directly to project decisions.

- What is the basis for the decision?
- Are there any regulatory and statistical drivers for sampling frequency?
- What action levels are applicable to the discussion or parameter of interest?
- Define the discussions using "If ... then ..." statements (e.g., if paint containing >50 ppm PCBs is identified then all resulting waste material will be handled as TSCA waste)

4.6 Optimization of Design

Modifications to the DQOs are typically based on visual observations, new information revealing data gaps as the project progresses, and professional judgement,

all of which are documented and are discussed in the Data Quality Analysis section of the final report.

Acquisition of a sample directly depends on the sampling team's observations of the material, equipment, equipment components, or media of interest. If data gaps are identified subsequent to the characterization sampling and decisions described herein (i.e., the decision can not be made with confidence), additional sampling of source materials and/or waste streams will be conducted.

Analytical data collected in support of specific projects will be evaluated using the guidance established by the Rocky Flats Administrative Procedure 2-G32-ER-ADM-08.02, *Evaluation of ERM Data for Usability in Final Reports (RMRS 1994e)*. This procedure establishes the guidelines for evaluating analytical data with respect to PARCC parameters. Data validation will be performed according to the RFETS, Analytical Services Division (ASD) procedures and will be done after the data are used for their intended purpose.

5.0 SAMPLING ACTIVITIES AND METHODOLOGY

This section describes what information sampling methodology and the locations. Figures may be provided in the SAP for clarity, and available information may be presented about the samples, including:

- Number of samples in each media
- Grid spacing or sample location
- Sample depths
- Criteria for selection of additional samples
- Sample numbering
- Type and frequency of QA/QC samples
- Sample analysis (method numbers)

For each medium, describe the above information in the text and, as appropriate, provide a table enumerating the samples to be collected, rationale for each sample, analysis method (and method number), amount and types of QC samples, the type of container, preservative, and holding time. These tables should include project requirements and collection locations, where appropriate. The overall QA/QC requirements including field duplicates and blank samples analytical detection limits, and standards for accuracy and completeness are provided in the IMP.

Sample handling, including chain-of-custody and packaging procedures, should be performed according to ER procedure 4-B29-ER-OPS-FO.13 *Containerization, Preserving, Handling and Shipping of Soil and Water Samples* (RMRS, 1994c).

This section should briefly describe of how samples will be numbered and labeled in the field. Sample numbers are assigned by the SWD or ASD. It is strongly recommended that sample numbers be obtained from SWD and included in the SAP. Numbers from the assigned block of samples will be assigned if additional samples are needed. If only field-screening data will be collected, describe a systematic method that will be used to number sample locations, depths and analytical results.

6.0 DATA MANAGEMENT

A project field logbook should be created and maintained by the project manager or designee in accordance with site Procedures 2-S47 ER-ADM-05.14, *Use of Field Logbooks and Forms* (RMRS 1995b) and 4-B29-ER-OPS-FO.14 *Field Data Management* (RMRS, 1994d). The logbook should include time and date of all field activities, sketch maps of sample locations, or any additional information not specifically required by the SAP. The originator should legibly sign and date each completed original hard copy of data. Appropriate field data forms should also be utilized when required by operating procedures that govern the field activity. Sample designations will appear in the logbook and on the field data forms. A peer reviewer should examine each completed original hard copy of data. Any modifications will be indicated in ink, and initialed and dated by the reviewer. Logbooks will be controlled through RMRS Document Control.

Analytical data record storage for this project will be performed by ASD. Sample analytical results will be delivered directly from the laboratory to the APO in an Electronic Data Deliverable (EDD) format and archived in the SWD. Hard copy records of laboratory results will be obtained from the APO in the event that the analytical data is unavailable in EDD or SWD at the time of report preparation. Analytical results will be compiled into a sampling and analysis results report. Additional data management discussion is provided in Section 3.4 of the main text.

7.0 PROJECT ORGANIZATION

If the SAP is not part of a document which already includes a project organization section, it should be described here. An organization chart should be included, at a minimum, that will

include the project manager, sample team lead, and the appropriate quality assurance and safety personnel.

8.0 HEALTH AND SAFETY PLAN

The Health and Safety Plan (HASP) used to control work should be referenced. In addition to the site-wide HASP, a project-specific HASP will usually have been developed for the PAM or IM/IRA being implemented. If only sampling activities are to be performed, a separate HASP may be needed to cover the activity.

9.0 QUALITY ASSURANCE

This section should reference the site-wide Quality Assurance Project Plan and then address the project-specific quality requirements, including the following elements:

- The 10 DOE quality criteria (Per DOE Order 5700.6C or 10 CFR 830.120) and including relevant parts of American National Standards Institute/American Society of Quality Control (ANSI/ASQC) E4, as applicable
- Sampling method, including specialized or specific equipment or instrumentation
- Collecting Decision logic for fewer or greater numbers of samples than those specified in the SAP
- QC sample types and quantities
- Specific analytical and/or radiochemistry methods and method numbers [e.g., SW-846, ANSI/ASQC, and American Society of Testing and Material, etc]
- Sample management requirements, including preservation, chain of custody, and shipping
- Data management and reduction requirements, including hardcopies and digital data
- Modeling of software/hardware verification/validation

10.0 REFERENCES

Provide the references used to generate the SAP, if appropriate. This will include documents used to develop the background and site descriptions.

Requirement		Citation	Type	Comment
ATOMIC ENERGY ACT (AEA) [42 USC 2200 et. seq.]				
RADIATION PROTECTION OF THE PUBLIC AND THE ENVIRONMENT				
<ul style="list-style-type: none"> • Radiation Protection Standard - All Pathways • Radiation Protection Standard - Airborne Emissions • Radiation Protection Standard - TRU Waste Storage/Disposal ALARA Process • Effluent Discharges to Surface Waters • Effluent Discharges to Sanitary Sewer Systems • Residual Radioactivity Levels (Real Property, Materials, and Equipment) • Monitoring and Surveillance 		DOE Order 5400.5 (10 CFR 834, Proposed) Chapter II.1a and III (834.101) Chapter II.1b (834.102) Chapter II.1c (834.109) Chapter II.2 (834.11) Chapter II.3a (834.201) Chapter II.3d (834.203) Chapter II.5 and IV (834, Subpart D) Chapter II.6 (834.10)	TBC	This DOE Order establishes criteria for the protection of human health and the environment to ensure radiation exposure resulting from DOE activities does not exceed an effective equivalent dose for 100 mrem per year. This radiation dose limit also forms the basis for the release of radionuclides to the environment and the release of properties for unrestricted use.

183
201

Final RFCA: IGD
Appendix 3
July 20, 1998

Requirement	Citation	Type	Comment
ATOMIC ENERGY ACT (AEA) [42 USC 2200 et. seq.]			
RADIATION PROTECTION OF THE PUBLIC			
<ul style="list-style-type: none"> • Radiation Protection Standard - All Pathways • Effluent Discharges to Sanitary Sewer Systems • Treatment or Disposal by Incineration • Disposal of Specific Waste 	10 CFR 20 .1301 .2003 .2004 .2005	TBC	For onsite response actions, NRC requirements are not applicable to CERCLA activities conducted at the RFETS; DOE is required to and has established programs to manage radioactive operations and waste. Although NRC regulations may be relevant, these NRC standards are not considered to be appropriate if DOE Orders adequately establish standards of control for the management of radioactive materials to ensure protection of human health and the environment. In cases where a DOE Order specifies requirements that are inconsistent with NRC standards, the DOE requirement will be followed unless specifically waived by DOE in order to adopt the NRC standard. The status of these requirements is being evaluated pending issuance of NRC guidance.
<ul style="list-style-type: none"> • Radiological Criteria for Unrestricted Use • Criteria for License Termination under Restricted Condition • Alternate Criteria for License Termination 	.1402 .1403 .1404	TBD	
RULES AND REGULATIONS PERTAINING TO RADIATION CONTROL			
<ul style="list-style-type: none"> • Permissible Levels of Radioactive Material in Uncontrolled Areas 	6 CCR 1007-1, Part 4 4.60.1	TBC	

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

201
202

Final RFCA: IGD
Appendix 3
July 20, 1998

Requirement	Citation	Type	Comment
ATOMIC ENERGY ACT (AEA) [42 USC 2200 et. seq.]			
RADIOACTIVE WASTE MANAGEMENT	DOE Order 5820.2A	TBC	
<ul style="list-style-type: none"> • Management of Transuranic Waste • Temporary Storage at Generating Sites • Management of Low-Level Waste • Performance Objectives • Performance Assessment • Waste Characterization • Disposal • Disposal Site Closure/Post Closure • Environmental Monitoring 	Chapter II 3e Chapter III 3a 3b 3e 3f 3j 3k		
ENVIRONMENTAL RADIATION PROTECTION STANDARDS FOR MANAGEMENT AND DISPOSAL OF SPENT NUCLEAR FUEL, HIGH-LEVEL AND TRANSURANIC RADIOACTIVE WASTES	40 CFR 191	C	Standard applies to transuranic wastes only.
<ul style="list-style-type: none"> • Radiation Dose Standard 	.03		
OCCUPATIONAL RADIATION PROTECTION	10 CFR 835	TBC	

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
ATOMIC ENERGY ACT (AEA) [42 USC 2200 et. seq.]			
LICENSING REQUIREMENTS FOR LAND DISPOSAL OF RADIOACTIVE WASTE	10 CFR 61	TBC	
<ul style="list-style-type: none"> • Radiation Protection • Access Restrictions • Future Impacts • Site Siting/Stability • Drainage Controls/Floodplains • Final Cover • Buffer Zone • Groundwater Monitoring • Waste Disposal Requirements 	.41 & .52 .42 .50 .44 .51 .51 .52 .53 .56		
CLEAN AIR ACT (CAA) [42 USC 7401 et. seq.]			
AMBIENT AIR QUALITY STANDARDS	5 CCR 1001-14 [40 CFR 50]	C	<p>Ambient air quality standards are considered to be chemical-specific ARARs to assess the quality of ambient air and the need to remediate a particular IHSS to maintain the quality of the ambient air. RFETS is located in a non-attainment zone for particulate matter and ozone.</p> <p>Ambient air quality standards are not effluent discharge limitations; they are used in conjunction with air dispersion modeling to establish discharge limits that are protective of air quality.</p>
<ul style="list-style-type: none"> • Sulfur Dioxide • Particulate Matter (PM10) • Carbon Monoxide • Ozone • Nitrogen Dioxide • Lead • Total Suspended Particulates 			

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

185

Requirement	Citation	Type	Comment
CLEAN AIR ACT (CAA) [42 USC 7401 et. seq.]			
<p>COLORADO AIR POLLUTION REGULATIONS</p> <ul style="list-style-type: none"> Emission Control Regulations for Particulates, Smokes, Carbon Monoxide, and Sulfur Oxides <ul style="list-style-type: none"> Particulates Emission Monitoring Requirements for Existing Sources Sulfur Dioxide Emission Regulations Odor Emissions Air Pollutant Emissions Notices Standards of Performance for New Stationary Sources Emissions of Volatile Organic Compounds Control of Hazardous Air Pollutants Emissions of Ozone-Depleting Compounds 	<p>5 CCR 1001 [42 CFR 52, Subpart G]</p> <p>Regulation No. 1 [5 CCR 1001-3]</p>	A	<p>Regulation No. 1, Section III.D(2)(b), (e), (f), and (h) requires control measurements to be implemented for construction activities, haul roads, haul trucks, and demolition activities, respectively, to prevent the emission of fugitive particulates in excess of air standards. Other portions of Regulation No. 1 would be an ARAR only if the remedial action involves the specific emission source regulated.</p>
	<p>Regulation No. 2 [5 CCR 1001-4] Regulation No. 3 [5 CCR 1001-5] Regulation No. 6 [5 CCR 1001-8] Regulation No. 7 [5 CCR 1001-9] Regulation No. 8 [5 CCR 1001-10] Regulation No. 15 [5 CCR 1001-19]</p>		<p>Regulation No. 2 prohibits odorous air contaminants from any single source to be emitted in detectable odors which are measured in excess of the air standards.</p> <p>Regulation Nos. 6, 7, 8, and 15 would be an ARAR only if the remedial action involves the specific emission source regulated.</p>

Requirement	Citation	Type	Comment
CLEAN AIR ACT (CAA) [42 USC 7401 et. seq.]			
NATIONAL EMISSION STANDARDS FOR HAZARDOUS AIR POLLUTANTS			
<ul style="list-style-type: none"> National Emission Standards for Emissions of Radionuclides Other Than Radon From Department of Energy Facilities <ul style="list-style-type: none"> - Standard - Emission Monitoring and Test Procedures - Compliance and Reporting National Emission Standards for Radon Emissions from Department of Energy Facilities <ul style="list-style-type: none"> - Standard - Exemption from the Reporting and Testing Requirements of 40 CFR 61.10 	<p>40 CFR 61, Subpart H</p> <p>.92 .93 .94</p> <p>40 CFR 61, Subpart Q</p> <p>.192 .193</p>	C/A	Demonstration of compliance with 40 CFR 61.92 is performed on a site-wide basis taking into consideration all RFETS sources. Stack monitoring is required for all release points which could contribute greater than 0.1 mrem/yr.
FEDERAL WATER POLLUTION CONTROL ACT (aka Clean Water Act (CWA)) [33 USC 1251 et. seq.]			
WATER QUALITY CRITERIA - GOLD BOOK			
	33 USC 1314 (CWA Section 304)	C	<p>The "Gold Book" presents guidelines with respect to water quality criteria for toxic pollutants. Criteria are published for aquatic and human health. The water quality criteria are not promulgated standards; however, they are established guidelines used for developing NPDES permits and may be considered potentially relevant and appropriate. WQC should not be used as effluent limits, rather discharge limits should be established either through the NPDES or UIC permitting process.</p> <p>Although water criteria are non-promulgated and non-enforceable standards, Section 121(d)(2)(B)(i) of</p>

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Requirement	Citation	Type	Comment
FEDERAL WATER POLLUTION CONTROL ACT (aka Clean Water Act (CWA)) [33 USC 1251 et. seq.]			
			CERCLA as implemented by the NCP (40 CFR 300.430(e)(2)(i)(E)) specifies that WQC established under Sections 303 and 304 of the CWA shall be attained where relevant and appropriate under the circumstances of the release. The designated or potential use of the surface or groundwater, the environmental media affected, the purpose for which the WQC were developed, and the latest information are to be considered in determining the relevance and appropriateness of the WQC to the response action. Therefore, the need to comply with WQC as a relevant and appropriate requirement needs to be determined on a case-by-case basis using the factors listed above.
COLORADO BASIC STANDARDS AND METHODOLOGIES FOR SURFACE WATER	5 CCR 1002-3.1	C	Non-AEA radionuclides that have Statewide surface water standards will be considered potential ARARs. Site-specific standards not associated with a use classification and AEA regulated radionuclides are not ARARs because they do not meet the criteria of "general applicability" and/or enforceability in 40 CFR 300.400(g)(4) and are, therefore, not "promulgated."
<ul style="list-style-type: none"> • Antidegradation Rule • Water Quality-Based Designations • Basic Standards Applicable to Surface Waters of the State 	31.8		
<ul style="list-style-type: none"> - Descriptive Standards for Substances from Point and Nonpoint Sources - Standards for Radioactive Materials - Standards for Organics • Salinity and Suspended Solids • State Use Classifications - Classifications - Areas Requiring Special Protection • Testing Procedures - Introduction – Numeric Levels 	31.11 31.12 31.13 31.16,		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

188

Requirement	Citation	Type	Comment
FEDERAL WATER POLLUTION CONTROL ACT (aka Clean Water Act (CWA)) [33 USC 1251 et. seq.]			
<ul style="list-style-type: none"> - Standard Test Procedures - Bioassay Procedures 	31.16, (2)(a) 31.16, (2)(b)		
COLORADO BASIC STANDARDS FOR GROUNDWATER	5 CCR 1002-41,	C	Applicability or relevance and appropriateness to be resolved
<ul style="list-style-type: none"> • Classifications of Groundwater - Groundwater Classifications - Criteria Used to Identify Classifications for Groundwater - Specified Area • Groundwater Quality Standards - Narrative Standards - Numerical Standards - Statewide Standards • Point of Compliance 	41.4 41.5 41.5 (A) 41.5 (B) 41.5 (C) 41.6		
TOXIC POLLUTANT EFFLUENT STANDARDS		C	If the permitted point is used, then the NPDES permit discharge standards would have been met.
<ul style="list-style-type: none"> • Toxic Pollutants • Compliance 	40 CFR 129.4 40 CFR 129.5		
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM REGULATIONS		A	These subparts are applicable to storage and use of products that contain toxic and hazardous pollutants above reportable quantity limitations, at a facility covered by an NPDES permit. No Federal, State, or local permit shall be required for the portion of any removal or remedial action conducted entirely onsite, where such remedial action is selected and carried out in compliance with Section 121.
<ul style="list-style-type: none"> • Designation of Hazardous Substances • Determination of Reportable Quantities for Hazardous Substances • Applicability of Best Management Practices • Best Management Practices Programs 	40 CFR 116 40 CFR 117 40 CFR 125.102 40 CFR 125.104		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
FEDERAL WATER POLLUTION CONTROL ACT (aka Clean Water Act (CWA)) [33 USC 1251 et. seq.]			
DISCHARGES OF DREDGED OR FILL MATERIAL INTO WATERS OF THE UNITED STATES <ul style="list-style-type: none"> Discharges Requiring Permits 	33 USC 1344 33 CFR 323.3	A/L	Only substantive portions of the regulations are required under CERCLA actions for onsite activities.
DOE COMPLIANCE WITH FLOODPLAIN/WETLANDS ENVIRONMENTAL REVIEW REQUIREMENTS <ul style="list-style-type: none"> Floodplain/Wetlands Determination Floodplain/Wetlands Assessment Applicant Responsibilities 	10 CFR 1022 .11 .12 .13	A/L	
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
ENDANGERED SPECIES ACT (ESA) [16 USC 1531 et seq.]			
BIOLOGICAL ASSESSMENT <ul style="list-style-type: none"> Purpose Preparation Requirements Request for Information Director's Response <ul style="list-style-type: none"> No Listed Species or Critical Habitat Present Listed Species or Critical Habitat Present Verification of Current Accuracy of Species List Contents 	50 CFR 402.12	A/L	Substantive compliance with the ESA is the responsibility of each Federal agency. In cases where more than one Federal agency is involved in an action a lead Federal agency, as determined among the Federal agencies participating in the action, is designated. The burden of consultation as required under ESA Section 7 and subsequent preparation of a biological assessment if appropriate is the responsibility of the lead Federal agency. Federal agencies must use the consultation process to determine if their action poses an adverse impact to threatened and endangered species and their critical habitat. It is within the spirit of the act that Federal agencies also consider candidate species, especially those species that may be headed toward

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
BIOLOGICAL ASSESSMENT CONT.			listing, in their environmental planning.
<ul style="list-style-type: none"> • Identical/Similar to Previous Action • Permit Requirements • Completion Time 			
<ul style="list-style-type: none"> • Submission of Biological Assessment • Use of Biological Assessment 			
INTERAGENCY COOPERATION			
<ul style="list-style-type: none"> • Informal Consultation • Formal Consultation 	50 CFR 402 .13 .14	A/L	If an endangered species is found, then interagency cooperation is required. Otherwise, interagency cooperation is a TBC and the policy of DOE is that interagency cooperation will be complete. The U.S. Fish and Wildlife Service will be consulted as necessary to ensure that appropriate steps are taken pursuant to the ESA to protect Federal listed threatened and endangered species and their critical habitats.
LISTING ENDANGERED AND THREATENED SPECIES AND DESIGNATING CRITICAL HABITAT			
<ul style="list-style-type: none"> • Factors for Listing, Delisting, or Reclassifying Species • Criteria for Designating Critical Habitat 	50 CFR 424 .11 .12	A/L	
ENDANGERED AND THREATENED WILDLIFE AND PLANTS			
<ul style="list-style-type: none"> • List of Endangered and Threatened Wildlife • List of Endangered and Threatened Plants • Interagency Cooperation: Critical Habitats 	50 CFR 17 .11 .12 .94	A/L	Current lists of threatened and endangered species of animals and plants pertinent to the ESA and of concern to DOE-RFFO at the Site should be obtained from the U.S. Fish and Wildlife Service, Colorado Field Office.

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Requirement	Citation	Type	Comment
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
• Interagency Cooperation: Critical Habitats - Plants	.96		
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
MIGRATORY BIRD TREATY [16 USC 701-715]			
TAKING, POSSESSION, TRANSPORTATION, SALE, PURCHASE, BARTER, EXPORTATION, AND IMPORTATION OF WILDLIFE AND PLANTS	50 CFR 10	A/L	
<ul style="list-style-type: none"> • The Purpose of the Regulation • List of Migratory Birds • Law Enforcement Offices • Civil Procedures 	.1 .13 .22 11		
EAGLE PROTECTION ACTS [16 USC 668 et. seq.]			
BALD AND GOLDEN EAGLES		A/L	
<ul style="list-style-type: none"> • Prohibited Acts; Criminal Penalties • Civil Penalties • Cancellation of Grazing Agreements • Taking and Using of the Bald and Golden Eagle for Scientific, Exhibition, and Religious Purposes • Enforcement Provisions 	16 USC 668(a) 16 USC 668(b) 16 USC 668(c) 16 USC 668(a) 16 USC 668(b)		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Final RFCA: IGD
Appendix 3
July 20, 1998

Requirement	Citation	Type	Comment
COLORADO NONGAME, ENDANGERED, OR THREATENED SPECIES CONSERVATION ACT [CRS 33-1-115, 33-2-101 to 33-2-107]			
• Willful Destruction of Wildlife	CRS 33-6-117	A/L	
• Damage or Destruction of Dens or Nests - Harassment of Wildlife	CRS 33-6-128		
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
COLORADO NONGAME WILDLIFE			
• Protected Species	2 CCR 406-8	A/L	
• Endangered Wildlife - Designation of Species	Article I, #1000		
• Threatened Wildlife - Designation of Species	Article II, #1002		
• Nongame Wildlife - Designation of Species	Article III, #1003		
	Article IV, #1004		
FISH AND WILDLIFE COORDINATION ACT [16 USC 661 et seq.]			
• Purpose	16 USC 661	A/L	
• Impounding, Diverting, or Controlling of Waters	16 USC 662		
• Impoundment or Diversion of Waters	16 USC 663		
• Rules and Regulations	16 USC 664		
• Effects of Sewage and Industrial Waters	16 USC 665		
• Authorization of Appropriations	16 USC 666		
• Penalties	16 USC 666(a)		
• Definitions	16 USC 666(b)		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
NATIONAL HISTORIC PRESERVATION ACT (NHPA) [16 USC 470 et. seq.]			
IDENTIFYING HISTORIC PROPERTIES	36 CFR 800.4	L	
<ul style="list-style-type: none"> Assessing Information Needs Locating Historic Properties Evaluating Historical Significance When No Historic Properties Are Found Historic Property Found 			
ASSESSING EFFECTS OF THE ACTIVITY ON THE PROPERTY	36 CFR 800.5	L	
DOCUMENTATION REQUIREMENTS	36 CFR 800.8	L	
CRITERIA OF EFFECT AND ADVERSE EFFECT	36 CFR 800.9	L	
PROTECTING NATIONAL HISTORIC LANDMARKS	36 CFR 800.10	L	
HISTORIC PROPERTIES DISCOVERED DURING IMPLEMENTATION	36 CFR 800.11	L	
EMERGENCY UNDERTAKINGS	36 CFR 800.12	L	
PRESERVATION OF AMERICAN ANTIQUITIES	43 CFR 3	L	
PROTECTION OF ARCHEOLOGICAL RESOURCES	43 CFR 7	L	

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Requirement	Citation	Type	Comment
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
ARCHEOLOGICAL RESOURCES PROTECTION [16 USC 470, Chapter 1B]			
PROTECTION OF ARCHEOLOGICAL RESOURCES: UNIFORM REGULATIONS	36 CFR 296	L	
<ul style="list-style-type: none"> • Purpose • Authority • Definitions • Prohibited Acts • Permit Requirements and Exceptions • Application for Permits and Information Collection • Notification to Indian Tribes of Possible Harm to, or Destruction of, Sites on Public Lands Having Religious or Cultural Importance • Relationship to Section 106 of the National Historic Preservation Act • Custody of Archeological Resources • Determination of Archeological or Commercial Value and Cost of Restoration and Repair • Assessment of Civil Penalties • Civil Penalty Amounts • Other Penalties and Rewards • Confidentiality of Archeological Resource Information • Report 36 CFR 296 	<ul style="list-style-type: none"> .1 .2 .3 .4 .5 .6 .7 .12 .13 .14 .15 .16 .17 .18 .19 		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Requirement	Citation	Type	Comment
NATURAL RESOURCE AND WILDLIFE PROTECTION LAWS			
ARCHEOLOGICAL AND HISTORICAL PRESEVATION ACT (AHPA) [16 USC 469a-1]			
Notification and Request for Preservation of Data	16 USC 469a-1(a)	L	Differs from NHPA in that it encompasses a broader scope of resources than those listed on the National Register and requires only preservation of the data (including analysis and publication)
Survey of Sites; Preservation of Data; Compensation	16 USC 469a-1(b)		
SAFE DRINKING WATER ACT (SDWA) [42 USC 300f et. seq.]			
COLORADO PRIMARY DRINKING WATER REGULATIONS			
<ul style="list-style-type: none"> • MCL for Microbiological Contaminants • MCL for Turbidity • MCLs for Inorganic Chemicals • MCLs for Organic Chemicals <ul style="list-style-type: none"> - MCL for Volatile Organic Chemicals (VOCs) - MCL for Total Trihalomethanes (TTHMs) - MCLs for Synthetic Organic Chemicals (SOCs) • MCLs for Radioactivity <ul style="list-style-type: none"> - MCLs for Radium-226, Radium-228, and Gross Alpha Particle Activity in Community Water Systems - MCLs for Beta Particle and Photon Radioactivity From Man-Made Radionuclides in Community Water Systems 	5 CCR 1003-1, [40 CFR 141] 3.1.2 4.1.1 5.2.1 5.2.2 5.2.4 5.2.3 6.1.1 6.1.2	C	These regulations may be relevant and appropriate to surface water and groundwater under their current use classifications.
MAXIMUM CONTAMINANT LEVEL GOALS			
<ul style="list-style-type: none"> • MCLGs for Organic Contaminants • MCLGs for Inorganic Contaminants 	40 CFR 141 .50 .51 .52	C	Non-zero MCLGs would also be relevant and appropriate to surface water and groundwater possessing drinking water supply use classifications. MCLGs equal to zero establish unattainable goals and are therefore not ARARs according to the NCP.

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
SAFE DRINKING WATER ACT (SDWA) [42 USC 300F et. seq.]			
• MCLGs for Microbiological Contaminants			
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § § 25-15-101 to -217)]			
The State of Colorado is authorized to administer portions of the hazardous waste management program (e.g., RCRA) to regulate the generation, treatment, storage, and disposal of hazardous waste within Colorado. As such, the Colorado regulations that are more stringent than the federal counterparts would be applicable to the management of hazardous waste. These regulations may also be relevant and appropriate in situations where a remediation waste is "sufficiently similar" to a RCRA-listed waste (e.g., waste which was generated and disposed of prior to the effective date of regulation) or when the proposed remedial action is similar to a RCRA-regulated activity and would be appropriate to ensure that the activity is protective of human health and the environment. Although the Colorado hazardous waste management regulations are similar to the federal requirements, both the federal and state regulatory citations are provided for reference purposes and to denote that both federal and state requirements were considered in establishing the identifying the ARAR requirement adopted for the remediation of the RFETS. Only substantive portions of the regulations are required under CERCLA actions for onsite activities. The State has not verified that these are the only substantive standards. The final determination is predicated upon an analysis for a specific action.			
SITING OF HAZARDOUS WASTE DISPOSAL SITES	6 CCR 1007-2 Part 2.4 Part 2.5	L	
• Minimum Design Performance Criteria for Off-Site Hazardous Waste Disposal Sites and On-Site Hazardous Waste Landfills • Requirements for Siting and Design of Off-Site Hazardous Waste Disposal Sites and On-Site Hazardous Waste Landfills			
IDENTIFICATION AND LISTING OF HAZARDOUS WASTES	6 CCR 1007-3, 261 [40 CFR 261]	A	

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

212

Final RFCA: IGD
Appendix 3
July 20, 1998

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
GENERATOR STANDARDS <ul style="list-style-type: none"> • Hazardous Waste Determinations • Record Keeping and Reporting Requirements <ul style="list-style-type: none"> - Record Keeping and Reporting 	6 CCR 1007-3, 262 [40 CFR 262] .11 .40 to .43	A	Persons who generate solid wastes are required to determine if the waste is hazardous. The definition and procedures contained in 6 CCR 1007-3, 261 [40 CFR 261] are to be followed to make this determination.

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

J - 17

198

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § § 25-15-101 to -217)] GENERAL FACILITY STANDARDS			
• Waste Analysis	6 CCR 1007-3,264 Subpart B [40 CFR 264 Subpart B] .13	A/L	Existing security measurements will be used and, where necessary, upgraded to prevent unknowing access to hazardous wastes.
• Security	.14	A/L	Inspections will be conducted as a standard of control to prevent release of hazardous waste constituents to the environment or a threat to human health. Corrective actions will be taken resolve deficiencies.
• General Inspection Requirements	.15	A/L	Personnel will be properly trained to prevent mismanagement of hazardous waste and/or regulatory violations.
• Personnel Training	.16	C/A	Procedures will be implemented to prevent accidental ignition or reaction of ignitable or reactive waste, or the mixing of incompatible waste.
• General Requirements For Ignitable, Reactive, or Incompatible Wastes	.17	C/A	A construction QA program will be implemented for the construction of any new hazardous waste disposal site.
• Construction Quality Assurance Program	.19	C/A	Hazardous waste management facilities will not be located within a 100-year floodplain.
Installation Standards	.18	A/L	
• Seismic Considerations			
• Installation Standards			

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § § 25-15-101 to -217)]			
PREPAREDNESS AND PREVENTION <ul style="list-style-type: none"> • Design and Operation of Facility • Required Equipment • Testing and Maintenance of Equipment • Access to Communications or Alarm System • Required Aisle Space • Arrangements with local Authorities 	6 CCR 1007-3, 264, Subpart C [40 CFR 264, Subpart C] .31 .32 .33 .34 .35 .37	A/L	Hazardous waste facilities will be designed to minimize the potential for incidents. Equipment will be provided to respond to credible incidents and arrangements with emergency response units will be executed.
CONTINGENCY PLAN AND EMERGENCY PROCEDURES <ul style="list-style-type: none"> • Purpose and Implementation • Content of Plan • Emergency Coordinator • Emergency procedures 	6 CCR 1007-3, 264, Subpart D [40 CFR 264 Subpart D] .51 .52 .55 .56	A	The existing RFETS contingency plan will be reviewed and revised accordingly to ensure that the procedures are adequate to respond to any new conditions posed by the remedial actions and/or the operation of new hazardous waste management facilities

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
MANIFEST SYSTEM, RECORDKEEPING, AND REPORTING <ul style="list-style-type: none"> • Applicability • Operating Record • Availability, Retention, and Disposition of Records 	6 CCR 1007-3 Part 264, Subpart E [40 CFR 264, Subpart E] .70 .73 .74	A	
GROUNDWATER PROTECTION <ul style="list-style-type: none"> • Required Programs • Point of Compliance • Ground-Water Protection Standard • Hazardous Constituents • Concentration Limits 	6 CCR 1007-3, 264, Subpart F [40 CFR 264, Subpart F] .91 .95 .92 .93 .94	A/L C	Groundwater monitoring will be conducted for hazardous waste for hazardous waste management units to ensure that contaminants which could adversely impact human health or the environment are not migrating into groundwaters as measured at the point of compliance. As part of the RF/RJ and CMS/FS process, remediation goals which are protective of human health and the environment will be established for the cleanup of groundwater. The RCRA process for establishing groundwater protection standards will be incorporated when selecting the remedial goals. Included in the selection process are background concentrations, drinking water standards (e.g., MCLs), and alternative concentration limits (ACLs). The DOE may seek ACLs that will maintain the water quality that supports the designated use at the RFETS.

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
GROUNDWATER PROTECTION (continued)			
<ul style="list-style-type: none"> Compliance Period 	.96	A	For any hazardous waste remaining onsite following the completion of closure activities, groundwater monitoring will be performed to demonstrate protectiveness of the selected remedial actions. The compliance period is defined as equal to the actual life of the waste management unit as determined by the State in the facility permit. For monitoring that is being conducted as part of a RCRA corrective action, compliance period is extended until it can demonstrate that the ground-water protection standard has not been exceeded for a period of three consecutive years. The five-year review provisions of CERCLA Section 121c (see 40 CFR 300.430(f)(4)(ii)) will be considered in establishing the compliance period.
<ul style="list-style-type: none"> General Ground-Water Monitoring Requirements <ul style="list-style-type: none"> Number of Wells Casing Sampling and Analysis Procedures Statistical Methods Utilized 	.97		Any additional monitoring wells that are installed as a result of remedial activities for the monitoring of hazardous waste management sites will conform to existing approved RCRA groundwater monitoring program.

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
GROUNDWATER PROTECTION (continued)			
<ul style="list-style-type: none"> • Detection Monitoring Program <ul style="list-style-type: none"> - Parameters or Constituents - System and Procedures - Statistical Exceedences • Compliance Monitoring Program <ul style="list-style-type: none"> - Monitoring - Installation of System - Sampling Procedures and Statistical Methods - Evidence of Increased Contamination - Flow Rates • Corrective Action Program <ul style="list-style-type: none"> - Compliance with Groundwater Protection Standard - Prevent Hazardous Constituents from Exceeding Concentration Limits - Time Frame - Groundwater Monitoring - Corrective Action Measures 	<p>.98</p> <p>.99</p> <p>.100</p>	A	

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

203
224

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § § 25-15-101 to -217)]			
TANK SYSTEMS	6 CCR 1007-3, 264, Subpart J or, 6 CCR 1007.3, 265, Subpart J, as appropriate [40 CFR 264, Subpart J, or 40 CFR 265, Subpart J, as appropriate]	A	Either existing or new tank systems will be used to treat or store hazardous waste generated as a result of remedial activities. Existing tank systems will only be used if it is determined that the tank system is adequate and has sufficient integrity to prevent failure of the tank system during the proposed new use. Existing tank systems will be closed in accordance with approved closure plans or IM/TRA documents
<ul style="list-style-type: none"> • Design and Installation of New tank Systems or Components • Containment and Detection of Releases <ul style="list-style-type: none"> - Secondary Containment - Design and Construction - Secondary Containment Devices • General Operating Requirements • Inspections • Response to Leaks or Spills and Disposition of Leaking or Unfit-for-Use Tank Systems • Closure and Post-Closure Care • Special Requirements for Ignitable or Reactive Wastes • Special Requirements for Incompatible Wastes 	.192 .193 .194 .195 .196 .197 .198 .199		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered, TBD-To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § § 25-15-101 to -217)]			
CLOSURE AND POST-CLOSURE	6 CCR 1007-3, 264, Subpart G [40 CFR 264, Subpart G] .111 .114 .117 .117	A	
<ul style="list-style-type: none"> • Closure Performance Standards • Disposal or Decontamination of Equipment, Structures and Soils • Maintenance, Monitoring, Security, and Care • Post-Closure Use of Property 			
USE AND MANAGEMENT OF CONTAINERS		A	
<ul style="list-style-type: none"> • Condition of Containers • Compatibility of Waste with Containers • Management of Containers • Inspections • Containment <ul style="list-style-type: none"> - Containment System Design and Operation - Containment for Ignitable or Reactive Wastes - Containment for Incompatible Wastes • Closure 			

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

202
205

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENT [Colorado Hazardous Waste Act (CRS § § 25-15-101 to -217)]			
SURFACE IMPOUNDMENTS	6 CCR 1007-3, 264, Subpart K, or, 6 CCR 1007-3, 265, Subpart K, as appropriate [40 CFR 264, Subpart K, or, 40 CFR 265, Subpart K, as appropriate]	A	All existing hazardous waste surface impoundments (e.g., Solar Evaporation Ponds) have been removed from service and are currently being closed. The closure, post-closure, and construction inspection requirements are included as part of the OU4 IM/IRA. In the event surface impoundments units are identified as part of a potential remedy Subpart K may become an ARAR.
<ul style="list-style-type: none"> Monitoring and Inspection Closure and Post-Closure Care 	.226 .228		
WASTE PILES	6 CCR 1007-3, 264, Subpart L [40 CFR 264, Subpart L]	A	In the event waste piles are identified as part of a potential remedy, Subpart L may become ARAR.
LAND TREATMENT	6 CCR 1007-3, 264, Subpart M [40 CFR 264 Subpart M]	A	In the event land treatment units are identified as part of a potential remedy, Subpart M may become ARAR.
LANDFILLS	6 CCR 1007-3, 264, Subpart N, or 6 CCR 1007-3, 265, Subpart N, as appropriate	A	In the event land treatment units are identified as part of a potential remedy, Subpart N may become ARAR.

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
LANDFILLS (continued)	[40 CFR 264 Subpart N, or, 40 CFR 265, Subpart N, as appropriate]		
INCINERATORS	6 CCR 1007-3, 264, Subpart O [40 CFR 264, Subpart O] .341 .342 .343 .345 .347 .351	A	These regulations are ARARs for the closure and/or the design, construction, and operation of a new incinerator system.
<ul style="list-style-type: none"> Waste Analysis Principal Organic Hazardous Constituents Performance Standards Operating Requirements Monitoring and Inspections Closure 			
CORRECTIVE ACTION FOR SOLID WASTE MANAGEMENT UNITS	6 CCR 1007-3, 264, Subpart S [40 CFR 264, Subpart S] .552 .553	A	Colorado has adopted a CAMU/TU rule. The provisions for designating CAMUs and TUs will be followed to facilitate implementation of a corrective action.
<ul style="list-style-type: none"> Corrective Action Management Units - Standards for Designating a CAMU - Requirements for Groundwater Monitoring - Closure Requirements for CAMUs Temporary Units - Requirements for TUs - Factors for Establishing Standards for TUs 			

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENT [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
SOIL REMEDIATION POLICY DOCUMENT			
• Colorado Soil Remediation Objectives Policy Document	December, 1997	TBC	Cost effective, site-specific risk-based approach to establishing soil remediation objectives. Would be considered in manner compatible with ALF and RFCA Attachment 10.
MISCELLANEOUS UNITS	6 CCR 1007-3, 264, Subpart X [40 CFR 264, Subpart X]	A	These standards are being listed as ARARs in the event that a miscellaneous unit is selected for the treatment of hazardous waste pursuant to the CMS/FS process.
• Environmental Performance Standards	.601		
- Groundwater and Subsurface Protection			
- Surface Water, Wetland and Surface Soil Protection			
- Air Protection			
• Monitoring, Analysis, Inspection, Response, Reporting, and Corrective Action	.602		
• Post-Closure Care	.603		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
AIR EMISSION STANDARDS FOR PROCESS VENTS <ul style="list-style-type: none"> Standards: Process Vents Standards: Closed-Vent Systems and Control Devices Test Methods and Procedures Record Keeping Requirements Reporting Requirements 	6 CCR 1007-3, 264, Subpart AA [40 CFR 264 Subpart AA] .1032 .1033 .1034 .1035 .1036	A	These standards will be incorporated into the design of process vents associated with distillation, fractionation, thin-film evaporation, solvent extraction, or air or steam stripping operations that manage hazardous wastes with organic concentrations of at least 10-ppm (by weight).
AIR EMISSION STANDARDS FOR EQUIPMENT LEAKS <ul style="list-style-type: none"> Standards: Pumps in Light Liquid Service Standards: Compressors Standards: Pressure Relief Devices in Gas/Vapor Service Standards: Sampling Connecting Systems Standards: Open-Ended Valves or Lines Standards: Valves in Gas/Vapor or Light Liquid Service Standards: Pumps and Valves in Heavy Liquid Service, Pressure Relief Devices in Light or Heavy Liquid Service, Flanges, and Other Connectors Standards: Closed-Vent Systems and Control Devices 	6 CCR 1007-3, 264, Subpart BB [40 CFR 264, Subpart BB] .1052 .1053 .1054 .1055 .1056 .1057 .1058 .1060	A	These standards will be incorporated into the design of remediation equipment that contains or contacts hazardous wastes with organic concentrations of at least 10 percent by weight excluding equipment that is in vacuum service.

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

222

Final RFCA: IGD
Appendix 3
July 20, 1998

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENTC [Colorado Hazardous Waste Act (CRS § 25-15-101 to -217)]			
<ul style="list-style-type: none"> Alternative Standards for Valves in Gas/Vapor Service or in Light Liquid Service: Percentage of Valves Allowed to Leak Alternative Standards for Valves in Gas/Vapor Service or in Light Liquid Service: Skip Period Leak Detection and Repair Test Methods and Procedures Record Keeping Requirements Reporting Requirements 	.1061 .1062 .1063 .1064 .1065		
CONTAINMENT BUILDINGS <ul style="list-style-type: none"> Design and Operating Standards Closure and Post-Closure Care 	6 CCR 1007-3, 264, Subpart DD [40 CFR 264 Subpart DD] .1101 .1102	A	These standards will be incorporated into the design of a containment building that is built to facilitate the management of hazardous remediation waste.
Standards for the Management of Specific Hazardous Wastes and Specific Types of Hazardous Waste Management Facilities	6 CCR 1007-3.267 [40 CFR 266]	A	Waste management plans will be developed to ensure compliance with the specific classes of hazardous waste (e.g., Recyclable Materials Used In a Manner Constituting Disposal, Burning for Energy Recovery, Recyclable Materials Utilized for Precious Metal Recovery, and Spent Lead-Acid Batteries Being Reclaimed) identified in this regulation

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

210
222

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.] SUBTITLE C: HAZARDOUS WASTE MANAGEMENT [Colorado Hazardous Waste Act (CRS § § 25-15-101 to -217)]			
LAND DISPOSAL TREATMENT STANDARDS			
<ul style="list-style-type: none"> • General 	6 CCR 1007-3, 268 [40 CFR 268]	A	Waste management plans will be developed to ensure compliance with the Land Disposal Restrictions. The performance requirements for hazardous waste treatment systems will be based on the LDR Treatment Standards contained in Subpart C.
<ul style="list-style-type: none"> • Prohibitions on Land Disposal 	6CCR 1007-3, 268 Subpart A [40CFR268, SubpartA]		Applicability of LDRs will be addressed in decision document – mixed waste may be treated using treatment capacity developed in the mixed waste Site Treatment Plan.
<ul style="list-style-type: none"> • LDR Treatment Standards <ul style="list-style-type: none"> - Treatment Standards for Hazardous Wastes - Treatment Standards Expressed as Specified Technologies - Variance from Treatment Standard - Treatment Standards for Hazardous Debris - Universal Treatment Standards • Prohibition on Storage of Restricted Waste 	6 CFR 10007-3, 268, Subpart C [40CFR 268, Subpart C]		
	6 CFR 10007-3, 268, Subpart D [40 CFR 268, Subpart D]		
	6 CCR 1007-3, 268 Subpart E [40 CFR 268, Subpart E]		

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined
J - 30

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (AKA: RESOURCE CONSERVATION AND RECOVERY ACT) [42 USC § 6901 et. seq.] SUBTITLE D: STATE OR REGIONAL SOLID WASTE PLANS COLORADO SOLID WASTE SITES AND FACILITIES [6 CCR 1007-2, PART 1]			
CLOSURE AND POST-CLOSURE <ul style="list-style-type: none"> • Minimum Standards <ul style="list-style-type: none"> - Closure of Solid Waste Disposal Sites and Facilities - Post-Closure Care and Maintenance Standards • Standards for Solid Waste Disposal Landfill Sites and Facilities <ul style="list-style-type: none"> - Closure - Post-Closure Care and Maintenance 	6 CCR 1007-2, Part 1, Section 2.5.1 to 2.5.9 [40 CFR 258.60 (a)-(h)] 6 CCR 1007-2, Part 1, Section 2.6.1 to 2.6.2 [40 CFR 258.61 (a)-(e)] 6 CCR 1007-2, Part 1, Section 3.5.1 to 3.5.8 [40 CFR 258.60 (a)-(h)] 6 CCR 1007-2, Part 1, Section 3.6.1 to 3.6.3 [40 CFR 258.61 (a)-(e)]	A	These regulations have been identified as potential ARARs with respect to closure of solid waste disposal sites

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement	Citation	Type	Comment
SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act) [42 USC § 6901 et. seq.]			
SUBTITLE I: REGULATION OF UNDERGROUND STORAGE TANKS [CRS §§ 8-20-501 to -608; CRS §§ 25-18-101 to -109]			
UNDERGROUND STORAGE TANK REQUIREMENTS	7 CCR 1101-14	A	
TOXIC SUBSTANCES CONTROL ACT (TSCA) [15 USC 2601 et seq.]			
LABELING OF PCBs AND PCB ITEMS			
DISPOSAL REQUIREMENTS <ul style="list-style-type: none"> • Disposal Requirements • PCB Remediation Waste • Disposal of PCB bulk product waste 	40 CFR 761.40 and .45	A	
	40 CFR 761.50	A	
	40 CFR 761.60		
	40 CFR 761.61		
	40 CFR 761.62		Waste management plans will be developed to ensure compliance with the specific requirements for PCB waste identified in this regulation.
STORAGE REQUIREMENTS FOR PCBs			
<ul style="list-style-type: none"> • Time Limits • Facility Criteria • Temporary Storage • Inspections • Container Specifications • Marking • Laboratory Sample Exemption From Manifesting 	40 CFR 761.65	A	

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD - To Be Determined

Requirement	Citation	Type	Comment
TOXIC SUBSTANCES CONTROL ACT (TSCA) [15 USC 2601 et seq.]			
INCINERATION <ul style="list-style-type: none"> • Liquid PCBs - Operating Requirements • Nonliquid PCBs 	40 CFR 761.70	A	These regulations would only be ARARs for the construction and operation of an onsite PCB incinerator; it is envisioned that this will not occur.
CHEMICAL WASTE LANDFILLS <ul style="list-style-type: none"> • Technical Requirements - Soils - Synthetic Membrane Liners - Hydrologic Conditions - Flood Protection - Topography - Monitoring Systems - Leachate Collection 	40 CFR 761.75	A	These regulations would only be ARARs for the construction and operation of an onsite PCB disposal cell; it is envisioned that this will not occur.
DECONTAMINATION STANDARDS AND PROCEDURES <ul style="list-style-type: none"> • Decontamination standards • Self-implementing decontamination procedures • Decontamination solvents • Limitation of exposure and control of releases • Sampling and recordkeeping • Decontamination waste and residues 	40 CFR 761.79	A	

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined

Requirement		Citation	Type	Comment
TOXIC SUBSTANCES CONTROL ACT (TSCA) [15 USC 2601 et seq.]				
Sampling				
<ul style="list-style-type: none"> Cleanup Site Characterization sampling for PCB remediation waste in accordance with § 761.61 (a)(z) Sampling to verify completion of self-implementing cleanup and on-site disposal of bulk PCB remediation waste and porous surfaces in accordance with § 761.61 (a)(b) Sampling non-porous surfaces for measurement based use, reuse, and on-site or off-site disposal under § 761.61 (a)(6) and determination under § 761.79 (6)(3) 	<p>40 CFR 761.260 [Subpart N]</p> <p>40 CFR 761.280 [Subpart O]</p> <p>40 CFR 761.300 [Subpart P]</p>			
PCB SPILL CLEANUP				
<ul style="list-style-type: none"> Requirements for PCB Spill Cleanup <ul style="list-style-type: none"> Disposal of Cleanup Debris and Materials Determination of Spill Boundaries Spills of <500 ppm PCBs, Involve <1 lb of PCBs by wt. Spills of \$500 ppm PCBs, Involve \$1 lb of PCBs by wt. Time Limits and Actions Within the First 24 Hours Requirements for Decontaminating Spills in Outdoor Electrical Substations Requirements for Decontaminating Spills in Restricted Access Areas Sampling Requirements 	<p>40 CFR 761</p> <p>.125</p> <p>.130</p>	TBC		40 CFR 761 Subpart G is entitled PCB Spill Cleanup Policy and thus many of the sections in Subpart G, specifically for spills after May 4, 1987, are "to be considered" (TBC).

A - Action-Specific ARAR; C - Chemical-Specific ARAR; L - Location-Specific ARAR; TBC - To Be Considered; TBD-To Be Determined
J - 34

APPENDIX K

SUMMARY OF RISK ASSESSMENT METHODOLOGY FOR RFETS

1.0 HUMAN HEALTH RISK ASSESSMENT METHODOLOGY

A site-specific HHRAM was developed that differs from standard CERCLA guidance in some respects. The methodology has been documented in the *draft Human Health Risk Assessment Methodology for RFETS* (DOE, 1995b). The risk assessment methodology also includes the conservative screen, developed by the CDPHE and agreed to by the DOE, to ensure that the requirements of the RCRA are met. Several risk assessments for former OUs have been produced using this methodology. In the future, it is likely that it will be used for screening level risk assessment and as the basis for the CRA.

The HHRAM process, including the conservative screen, is shown in Figure K-1. Each step in the HHRAM process is done in consultation with the agencies and documented by a technical memorandum. Step 1 is the evaluation of data to determine if sufficient data of appropriate quality are available to perform a risk assessment or screen. Step 2 is the selection of potential chemicals of concern (PCOCs). Site data for inorganics and radionuclides have been compared to background values, using a battery of statistical test designed by Gilbert (1992), and accepted for use at RFETS by the DOE and the agencies. If the analyte was indicated to be above background by any of the tests it was considered a PCOC. This is a time consuming, costly, and statistically unsound (increased probability of a Type I error) process. For future risk assessments the Gilbert methodology will be treated as a statistical toolbox. The most appropriate test will be selected from the Gilbert toolbox for each analyte (inorganics and radionuclides) that has a maximum concentration greater than the background mean plus two standard deviations (M2SD). The selection of the statistical test will be a balance of the data characteristics (e.g., number of nondetects, distribution of data) of the analyte. A description of the statistical tests and their use is given in Attachment 1. All detected organics are considered to be PCOCs.

The RFCA changed the emphasis for environmental remediation to investigation, evaluation, and remediation of IHSSs and AOCs, instead of an OU by OU basis. The PCOC selection process will likely be applied to a particular source or associated sources grouped as an AOC. Fewer samples may be available for statistical analysis due to the change in emphasis to source areas. It will be very important that a sufficient number of samples be available for application of the Gilbert toolbox. After the determination of PCOCs, the conservative screen is applied to the data and the baseline risk assessment may be started.




Figure K-1 Human Health Risk Assessment Methodology

1.1 CONSERVATIVE SCREEN

The conservative screen has been accepted for use at the RFETS (DOE, 1994a). The purpose of the conservative screen is to help determine if a particular site is a candidate for no action, accelerated action, or further evaluation through the BRA process. The conservative screen is the basis of the NFA decision criteria presented in Attachment 6 of RFCA. A site that passes the conservative screen is a candidate for NFA status and free release with no land use restrictions.

The screen also provides methodologies for identifying source areas and grouping them into AOCs. The process is shown in Figure K-2. The conservative screen uses the residential PPRGs to calculate the ratios used in the decision criteria (DOE, 1995a). A letter report is submitted to the agencies to document the results.

1.2 CHEMICALS OF CONCERN

The next step in the HHRAM process is the selection of COCs. The selection process, as agreed to by the DOE and the agencies, is shown in Figure K-3.

The COCs have been selected on an OU-wide basis and then applied to each AOC within the OU. Now COC selection will often be done for single sources or sources grouped as an AOC as a result of an action level screen. It is very important that sufficient data be available for this analysis. The COC selection process for the CRA should be based on the present methodology, with COCs selected separately for the two site OUs (Buffer Zone and Industrial Area). The COCs are selected in consultation with the agencies and a TM is submitted to document the results.

1.3 EXPOSURE SCENARIOS AND PARAMETERS

Exposure scenarios and associated exposure factors, developed during negotiations among the DOE, the EPA, and the CDPHE, were transmitted to the agencies in June 1995 (DOE, 1995b). The exposure factors have been used in several BRAs for specific OUs (OUs 2, 3, 4, 5, and 6). The EPA and the CDPHE have accepted all of the exposure factors with the exception of the fraction ingested from contaminated source for the central tendency residential exposure by soil ingestion and the chemical-specific values for the soil ingestion matrix effect (EPA/CDPHE 1995). Chemical specific soil ingestion matrix values must be submitted to the agencies for approval before being used.

The two exposure scenarios to be used in the CRA to evaluate the on-Site risks and hazards to human health from environmental contamination under the RFCA will be the open-space recreational receptor for the BZ and the office worker for the IA. Off-Site risks and hazards will be evaluated using the residential scenario. Other scenarios may be evaluated in the CRA if agreed to by the DOE, EPA, and CDPHE.




Figure K-2 CDPHE Conservative Screen




Figure K-3 Chemical of Concern Identification

1.4 RISK CHARACTERIZATION

Exposure concentrations and risks will be calculated in accordance with EPA guidance (EPA, 1989a) as documented in the HHRAM (DOE, 1995b). Both radiological risk and dose will be estimated. Radiological doses will be calculated using methods and parameters employed for development of the ALF.

1.5 ECOLOGICAL RISK ASSESSMENT

Protection of ecological as well as human receptors is a central goal under CERCLA and the RFCA. The methodology for quantifying possible adverse effects to ecological receptors is similar to that for human receptors. A sitewide ERAM was developed that is consistent with the EPA's eight-step guidance (draft) on conducting ERAs at Superfund sites (EPA, 1994b). This methodology has been used for ecological risk assessments for the Walnut Creek and Woman Creek watersheds at RFETS (DOE, 1996c). The screening portion of this site-specific guidance is shown in Figure K-4 as described in the following documents:

- *ERAM Technical Memorandum, Sitewide Conceptual Model* (DOE, 1996a) helps identify environmental stressors and the potentially complete exposure pathways that will become the focus of the ERA.
- *ERAM Technical Memorandum, Ecological Chemicals of Concern Screening Methodology* (DOE, 1996b) describes a tiered screening process for identifying chemicals at potentially ecotoxic concentrations.

The purpose of a screening-level ERA is to detect whether a significant ecological threat exists in a geographic area. After PCOCs have been determined for a geographic area, risks are estimated by comparing maximum analyte concentrations with screening-level ecotoxicity benchmarks, with the subsequent generation of hazard quotient (HQ) values. The HQ is the result of the exposure estimate divided by the benchmark. This step is used to evaluate whether the preliminary screening is adequate to determine the presence of an ecological threat. If none of the PCOCs are present at ecotoxic concentrations, the site is considered to present a negligible or de minimis risk and a more detailed quantitative risk assessment is not warranted (EPA, 1994b). If a given IHSS or source area fails to pass the ERA screen ($HQ > 1$ for any analyte), the data are evaluated in more detail. This includes a much more comprehensive evaluation of exposure pathways and a more accurate method for estimating exposure than a screening-level ERA. The exposure estimation includes methods that account for factors which modify the frequency, duration, and intensity of contact between a receptor and the contaminated media. This evaluation results in a list of chemicals that are subjected to more detailed analysis in the ecological risk characterization.




Figure K-4 Screening-Level ERA

223
242

The characterization in the ERA integrates the exposure assessment and the effects assessment. It includes a description of risk in terms of the assessment endpoints, a discussion of the ecological significance of the effects, a summary of the overall confidence in the ERA, and a discussion of possible risk management strategies. The ERA performed for the Walnut Creek and Woman Creek watersheds will form the basis for the Ecological component of the CRA (DOE, 1996c).

ATTACHMENT 1

BACKGROUND COMPARISON (Adapted from Chromec et al., 1995)

Analytical results for metals, radionuclides, water-quality parameters, and selected organics, if appropriate, are compared to the chosen background data using one of the following five statistical tests.

Lognormal Upper Tolerance Level (UTL99/99) Each result is compared to the background 99% UTL on the 99th percentile of background. This hot measurement test assures that no hot spots in an area of concern are overlooked. If one or more measurements exceed the UTL99/99 the analyte is considered a PCOC pending application of professional judgment. UTLs cannot be reliably calculated for analytes with a very high rate (> 80%) of nondetects.

The Slippage Test This is a rapid screening test. The Slippage test is a nonparametric test and can be used for all data distributions. The test should not be used if the highest value in the data set is a nondetect. If the number of site measurements that exceed the background maximum value are greater than a critical number obtained from the appropriate table, then the analyte may be a PCOC.

The Quantile Test This is also a rapid screening, nonparametric test and can be used with all data distributions. If the number of site results that are among the largest r (number selected from a table of values) measurements exceeds a predetermined number, it may be concluded that the analyte is a PCOC. The test should only be used there are no nondetects among the largest measurements of the combined background and site data sets. A p -value of 0.05 or less is considered to indicate a significant difference from background concentrations.

The Gehan Test (nonparametric ANOVA) The Gehan test is a nonparametric test that can be used when multiple detection levels are present. It is applied without replacing nondetect values. The data are ordered, ranked and scored. A "Z" statistic is calculated and compared to values from a table at a chosen p -value. A p -value of 0.05 or less is considered to indicate a significant difference from background concentrations. Gilbert did not feel that the performance of this test had been sufficiently determined and suggested that it be evaluated at the earliest possible time.

The Student's t Test This is a common parametric test for determining if the means of two populations are different. The t test is the preferred test when the background and site data are normally and independently distributed, with equal variances and no nondetects. The test is applied on populations with at least 20 observations and less than 20% nondetects. A p-value of 0.05 or less indicates a significant difference between means.

Analytes with greater than 80% nondetects cannot be compared using statistical tests, and test results for analytes having 50-80% nondetects should be reviewed with caution.

If the selected statistical test indicates a statistical difference above background levels and it has been applied appropriately, the chemical will be considered a PCOC. Professional judgment will also be used to retain or eliminate chemicals. Graphics may be used to support such decisions.

Professional Judgment Professional judgment is narrowly defined. It can be used to include a chemical that did not appear to be significantly different from background based on the results of the statistical test, but for which there exists a preponderance of historical data suggesting that the chemical may have been released to the environment in significant quantities. Professional judgment can also be applied to exclude a chemical for which at least one of the statistical tests was significant, but the difference from background can be explained by spatial, temporal, or pattern-recognition concepts.

Professional judgment may also determine that there was an invalid application of the statistical tests; distributional assumptions were violated or nondetect rates were so high that the statistical tests actually compared replacement values; making the test results highly suspect or meaningless. The statistical comparison of data sets where one or both data sets have high nondetect rates or high value nondetects may be an invalid use of the statistical tests (Gilbert and Simpson 1992). For RFETS, various reports (DOE 1993a, 1994; and others) have used 80 percent as the cut-off value for nondetects. However, there is inherent uncertainty in statistical test results that are produced using data sets with greater than 50 percent nondetects.

Other potential pitfalls in the application of statistical tests include violation of distributional assumptions, variance assumptions, data independence assumptions. If such assumptions are violated, the results of such statistical tests are suspect. If the results are accepted as valid, the PCOCs identified continue through the COC selection process.

**ACTION LEVELS FOR RADIONUCLIDES IN SOILS
FOR THE
ROCKY FLATS CLEANUP AGREEMENT**

FINAL

**US DEPARTMENT OF ENERGY
US ENVIRONMENTAL PROTECTION AGENCY
COLORADO DEPARTMENT OF PUBLIC HEALTH AND THE ENVIRONMENT**

OCTOBER 31, 1996

TABLE OF CONTENTS

<u>Chapter</u>	<u>Page Number</u>
ES Executive Summary	ES - 1
1 Introduction	1 - 1
2 Radionuclide Working Group Formation and Goals	2 - 1
3 Regulatory Analysis of Radionuclides in Soil	3 - 1
3.1 Introduction	3 - 1
3.2 DOE Order 5400.5	3 - 2
3.3 Proposed 10CFR834	3 - 3
3.4 Preliminary Proposed 40CFR196	3 - 3
3.5 Proposed 10CFR-NRC	3 - 4
3.6 Rocky Flats Cleanup Agreement Basis	3 - 4
4 Site Conceptual Model	4 - 1
4.1 Introduction	4 - 1
4.2 Land Uses at RFETS	4 - 1
4.3 Surface Soil Assessment	4 - 2
4.4 Subsurface Soil Assessment	4 - 4
5 Action Level Development	5 - 1
5.1 Introduction	5 - 1
5.2 Computer Code Requirements	5 - 1
5.3 Computer Code Selection	5 - 2
5.4 RESRAD Parameter Input Development	5 - 4
5.5 RESRAD Modeling Results	5 - 4
5.6 Use of RESRAD Modeling Results	5 - 5
5.7 Action Level Uncertainties	5 - 7
6 References	6 - 1
 <u>Appendices</u>	
A) Parameter Justification and RESRAD Output	
B) Analysis of the Chemical Form of Plutonium in the Environment	
C) Analysis of Exposure Pathways For Use in Deriving Action Levels	
D) Analysis of Assessment Needs For Rocky Flats Plutonium	

ACRONYMS

ALARA	As Low As Reasonably Achievable
ALF	Action Levels and Standards Framework for Surface Water, Ground Water and Soils
ANL	Argonne National Laboratory
CAB	Citizens Advisory Board
CDPHE	Colorado Department of Public Health and the Environment
CERCLA	Comprehensive Environmental Response, Compensation and Liability Act
CFR	Code of Federal Regulations
DCF	Dose Conversion Factor
DOE	US Department of Energy
EPA	US Environmental Protection Agency
GI	Gastrointestinal
ICRP	International Commission on Radiological Protection
MCL	Maximum Contaminant Level
NESHAPS	National Emission Standards for Hazardous Air Pollutants
NRC	US Nuclear Regulatory Commission
RFCA	Rocky Flats Cleanup Agreement
RFETS	Rocky Flats Environmental Technology Site
RME	Reasonable Maximum Exposure
SCM	Site Conceptual Model

EXECUTIVE SUMMARY

INTRODUCTION

During the Rocky Flats Cleanup Agreement (RFCA) negotiations, the Action Levels and Standards Framework for Surface Water, Ground Water and Soils (ALF) Working Group realized that setting soil action levels and cleanup standards for radionuclides was a complex process and could not be completed before public notice of the draft RFCA. The RFCA Attachment 5 states that "The parties commit to expeditiously convene a working group to determine the derivation and application of the 15 mrem per year level as well as the derivation and potential application of the 75 mrem per year level." This summary explains the consensus recommendation of that Working Group.

The Working Group convened in early March 1996 and was composed of personnel from the Department of Energy (DOE), the Environmental Protection Agency (EPA), the Colorado Department of Public Health and Environment (CDPHE) and Kaiser-Hill, L.L.C. The Working Group agreed that its charter was to develop technically defensible standards which will not exceed the 15/75 mrem per year dose limits in ALF. The Working Group recognized that the 15/75 requirement was based on EPA's draft 40CFR196, Radiation Site Cleanup Regulations, which were intended for the release of government property. Because the RFCA preamble and the Rocky Flats Vision identify future land uses for the RFETS, which exclude release of government property and permit no residential land use, pertinent sections of the draft regulation were used as guidance for the Working Group.

Radiation dose was chosen as the primary criterion for assessing radionuclide action levels. The ALF called for the consideration of both radiation dose assessment and radiation risk assessment by the working group in making its recommendations. The use of radiation dose to develop action levels is consistent with EPA's draft 40CFR196, Nuclear Regulatory Commission decommissioning requirement, DOE Order 5400.5, "Radiation Protection of the Public and the Environment", and

DOE's proposed 10CFR834. Since these regulations are all radiation dose based, this is compelling evidence that the radiation protection community is recommending the use of radiation dose to limit environmental levels of radionuclides. In addition, the preamble to draft 40CFR196 compares the risks associated with remediation, transportation and disposal of contaminated soils against the risks of leaving contaminated soils in place at the 15/75 mrem per year dose limit. EPA concluded that the use of a 15/75 mrem dose limit to establish action levels is protective of the public. Furthermore, the dose assessment process incorporates all pertinent facets of EPA's CERCLA risk assessment process. The radionuclide working group agrees with the EPA draft regulation and is recommending the use of a radiation dose basis.

To translate the radiation dose requirements into soil action levels, it is necessary to first model radionuclide transport within the environment to a human receptor and then assess the receptor's radiation dose. The "RESRAD" computer code was chosen to model this complex process. RESRAD was specifically developed to calculate the radiation dose to an individual and also to derive action levels for radionuclides in soil. RESRAD has been verified and validated for use in assessing radioactive material in soils. An asset of the RESRAD code is its capability to assess contaminant transport to a human receptor in air, surface water, ground water and unsaturated zone soils over the 1,000 year modeling period as specified in the draft EPA regulation. This makes it possible to calculate radiation dose and action levels over any applicable exposure routes (e.g., ingestion, inhalation and external irradiation pathways) for a given receptor. RESRAD also has the capability to model multiple exposure scenarios (e.g., residential, open space and office worker) and to assess radioactive daughter products over the 1,000 year modeling period. The radionuclide working group recommends the use of RESRAD in calculating action levels for the RFETS.

SITE CONCEPTUAL MODEL

There are two separate soil types that need to be assessed at the RFETS: surface soils and subsurface soils. Surface soils are defined in the ALF from the surface to a depth of 15 cm. Consistent with the

RFCA preamble and the Rocky Flats Vision, ALF specifies that surface soil action levels would be derived using an open space exposure scenario in the buffer zone and an office worker exposure scenario in the industrial area. Subsurface soils are defined in the ALF from a depth of 15 cm to the top of the ground water table. Per the ALF, subsurface soil action levels are protective of surface water standards through ground water transport of contaminants to surface water. Ground water is not considered a potential drinking water source at RFETS as prescribed in the RFCA preamble and the Rocky Flats Vision.

Per the RFCA preamble and the Rocky Flats Vision, institutional controls may be applied at RFETS. Use of institutional controls may be considered under EPA's draft 40CFR196 when releasing a site. EPA's draft regulation states that any radioactive material in surface soils shall not impart an annual radiation dose to the appropriate human receptor (e.g. an open space receptor in the buffer zone or an office worker receptor in the industrial area) in excess of 15 millirem. Since radiation dose is being examined for a 1,000 year time period, the draft EPA regulation conservatively assumes that institutional controls fail in the future and that a hypothetical resident moves onto the site. Due to the long lived nature of radionuclides at Rocky Flats, the working group is recommending the assessment of a hypothetical future resident. This recommendation was a conscious decision by the working group despite the guidance in the vision which provides for no future residential uses. The annual radiation dose received by this hypothetical future resident will not exceed 85 millirem (Note: The annual radiation dose for this hypothetical individual in EPA's draft 40CFR196 recently changed from 75 mrem to 85 mrem)

There are two action levels that need to be calculated for surface soils. Tier I action levels are numeric levels that, when exceeded, trigger an evaluation, remedial action and/or management action, given the presence of institutional controls. Tier II action levels are numeric levels that, when met, do not require remedial action and/or institutional controls. The final action levels were derived by examining both the hypothetical future resident action levels and the action levels based on the most appropriate land use and then choosing the most conservative action level. The radionuclide working

group recommends adopting the Tier I and Tier II methodology outlined in the "Action Levels and Standards Framework for Radionuclides in Surface Water, Groundwater and Soils (ALF)." Proposed modifications to ALF and a discussion of put-back levels can be found in the document entitled, "Modifications to the Action Levels and Standards Framework." Table ES-1, "Tier I & II Soil Action Levels," outlines the Tier I and Tier II action levels being recommended by the radionuclide working group. The working group is recommending that the hypothetical future resident exposure scenario at the 85 mrem level be the Tier I action level for surficial soils in the buffer zone. The working group is also recommending that the office worker exposure scenario at the 15 mrem level be the Tier I action level for surficial soils in the industrial area. Further, the working group is recommending that the Tier II action level be the hypothetical future resident exposure scenario at the 15 millirem level.

Per the ALF, subsurface soil action levels must be protective of surface water standards through the transport of contaminants in ground water. The ALF requires that subsurface soil action levels be based on the leaching of contaminants to ground water, such that the ground water levels are protective of surface water standards. This concept was discussed by the radionuclide working group and not recommended for use at RFETS. Since the subsurface soils at RFETS are highly heterogeneous, it is not currently possible to accurately model radionuclide transport in these subsurface soils. Therefore, the radionuclide working group currently recommends a conservative approach by applying the Tier I and Tier II surface soil action levels to the subsurface soils. In addition, subsurface soil leaching of radionuclides to ground water is currently being investigated at the RFETS. If an accurate subsurface soil leaching model can be developed for RFETS in the future, and is agreed upon by the RFCA parties, the current working group recommendations may need to be updated.

RESRAD INPUT PARAMETERS

In the RESRAD computer code, there are approximately seventy different inputs that were discussed and agreed upon by the radionuclide working group for each exposure scenario. Site-specific values

were chosen for these inputs whenever possible so that the action levels could be tailored to RFETS. If a site-specific value was not available, the RESRAD default input was used. The RESRAD code was used to evaluate the office worker exposure scenario, the open space exposure scenario and the hypothetical future resident exposure scenario over the 1,000 year modeling period.

RECOMMENDATIONS

The working group recommends that the hypothetical future resident exposure scenario at the 85 mrem level be the Tier I action level for surficial soils in the buffer zone. The working group also recommends that the office worker exposure scenario at the 15 mrem level be the Tier I action level for surficial soils in the industrial area. Further, the working group is recommending that the Tier II action level for the entire site be the hypothetical future resident exposure scenario at the 15 millirem level. Soils with levels of radionuclides at or below the Tier II action level do not require remedial action and/or institutional controls. Although direct exposure to subsurface soils is not anticipated for the hypothetical future resident, open space or office worker exposure scenarios, the radionuclide working group currently recommends conservatively applying the Tier I and Tier II surface soil action levels to the subsurface soils. This subsurface soil recommendation may be updated in the future. Table ES-1 outlines these Tier I and Tier II action levels.

This working group acknowledges that in the future, new regulations, different guidance, improved calculation methods and models and better input parameters will likely become available. As this new information becomes available it will be considered in accordance with paragraph 5 of RFCA.

APPLICATION

Action levels as calculated above are only applicable when a single radionuclide is found in the environment. This is not the case at RFETS. In the environment at RFETS, the uranium (U) isotopes of U-234, U-235 and U-238 are found together, and the americium (Am) and plutonium (Pu)

isotopes of Am-241 and Pu-239/240 are found together. When multiple radionuclides are found in the environment, it must be ensured that the sum of the radiation doses from all radionuclides present does not exceed the action level basis (e.g., a hypothetical future resident assessed at the 15 mrem level).

The action levels for americium and plutonium together can also be calculated since the activity of Am-241 is about 18% of the Pu-239+Pu-240 (Pu-239/240) activity in the environment (Ibrahim, 1996). Given this activity ratio, the action level for Am-241 and Pu-239/240 can be computed so that the sum of their radiation doses equals either 15 or 85 millirem to the appropriate exposure scenario. Table ES-1 includes an example of these adjusted action levels for Am-241 and Pu-239/240 if they are the only radionuclides present in soil. Since the 18% ratio actually varies in the environment, site specific data will be used to make action level comparisons. If uranium is also present in the soil, then the contribution to the radiation dose from the uranium also needs to be assessed so that the Tier I and/or Tier II action level basis is not exceeded.

TABLE ES-1
TIER I & II SOIL ACTION LEVELS

Tier I Action Level For The Buffer Zone (Hypothetical Resident)

Radionuclide	Hypothetical Resident - 85 mrem Annual Radiation Dose (a) (pCi/gram)	Hypothetical Resident - Ratio Sum to 85 mrem Annual Radiation Dose (b) (pCi/gram)
Americium-241	215	117
Plutonium-239/240	1429	651
Uranium-234	1738	
Uranium-235	135	
Uranium-238	586	

Tier I Action Level for The Industrial Area (Office Worker)

Radionuclide	Office Worker - 15 mrem Annual Radiation Dose (a) (pCi/gram)	Office Worker - Ratio Sum to 15 mrem Annual Radiation Dose (b) (pCi/gram)
Americium-241	209	101
Plutonium-239/240	1088	562
Uranium-234	1627	
Uranium-235	113	
Uranium-238	506	

Tier II Action Level For RFETS (Hypothetical Resident)

Radionuclide	Hypothetical Resident - 15 mrem Annual Radiation Dose (a) (pCi/gram)	Hypothetical Resident - Ratio Sum to 15 mrem Annual Radiation Dose (b) (pCi/gram)
Americium-241	38	21
Plutonium-239/240	252	115
Uranium-234	307	
Uranium-235	24	
Uranium-238	103	

(a) - These values apply to single radionuclides only which does not occur in the environment at RFETS. The "Sum of Ratios" method will be applied at RFETS so that the total dose from multiple radionuclides are correctly assessed.

(b) - This example assumes that the Am-241/Pu-239 activity ratio equals 0.18 and that only Pu-239 and Am-241 are present

SECTION 1

INTRODUCTION

During the Rocky Flats Cleanup Agreement (RFCA) negotiations, the Action Levels and Standards Framework for Surface Water, Ground Water and Soils (ALF) Working Group realized that setting soil action levels and cleanup standards for radionuclides was a complex process and could not be completed before public notice of the draft RFCA. Therefore a radionuclide working group was formed to undertake this task. This report discusses the formation of a radionuclide working group, the radionuclide working group's application of the 15/75 mrem methodology as outlined in the draft RFCA and the radionuclide working group's recommendations concerning radionuclide action levels in soils.

Section 2 of this report discusses the formation of the radionuclide working group along with the goals of the working group. The working group members represent the US Department of Energy (DOE), the US Environmental Protection Agency (EPA), the Colorado Department of Public Health and the Environment (CDPHE) and Kaiser-Hill (K-H) , L.L.C.

Section 3 of this report is a regulatory analysis that describes the regulatory basis for deriving radionuclide action levels in soils. Regulations promulgated by the DOE, EPA and Nuclear Regulatory Commission (NRC) are examined

Section 4 of this report contains the site conceptual model for surface and subsurface soil assessment. The site conceptual model is the basis for the exposure scenarios used to derive action levels for soils.

Section 5 of this report discusses how the soil action levels were developed. The use of the RESRAD computer model is discussed and the action levels for all applicable exposure scenarios are given.

Appendix A of this report discusses the development of the parameter inputs to the RESRAD computer code for the hypothetical future resident exposure scenario, the open space exposure

scenario and the office worker exposure scenario. RESRAD computer code outputs are also in this appendix.

Appendix B of this report discusses the expected chemical form of plutonium in the environment. The chemical form of radioactive material is significant for assessing radiation dose.

Appendix C of this report is an exposure pathway analysis. The exposure pathways applicable to the hypothetical future resident exposure scenario, the open space exposure scenario and the office worker exposure scenario are discussed and delineated.

Appendix D of this report discusses the relative importance of different isotopes of plutonium with respect to human health. The decay of plutonium, the ingrowth of daughters and plutonium toxicity are examined.

SECTION 2

RADIONUCLIDE WORKING GROUP FORMATION AND GOALS

The radionuclide working group convened in early March 1996 and was composed of personnel from the DOE, the EPA, the CDPHE and the K-H Team. The Working Group agreed that its charter was to determine the derivation and application of the 15 mrem per year level as well as the derivation and potential application of the 75 mrem per year level as outlined in the Rocky Flats Cleanup Agreement. The Working Group recognized that the 15/75 requirement was based on EPA's preliminary proposed 40CFR196, Radiation Site Cleanup Regulations.

The goals of the Working Group were:

- To determine and recommend radionuclide action levels for soil;
- To determine and recommend radionuclide put-back levels for soil; and
- To prepare a draft technical justification document which would explain the Working Group's recommendations.

The Working Group believes its recommendations are based on a sound technical, scientific and regulatory foundation. The Working Group has consulted with the Citizens Advisory Board (CAB), the Cities of Broomfield, Westminster, Northglenn and Thornton, and the Rocky Flats Environmental Technology Site (RFETS) expert panel on radionuclide fate and transport concerning any recommendations. Proposed modifications to ALF and a discussion of put-back levels can be found in the document entitled, "Modifications to the Action Levels and Standards Framework."

SECTION 3
REGULATORY ANALYSIS OF RADIONUCLIDES IN SOILS

3.1 Introduction

In order to calculate action levels for radionuclides, a target radiation dose to an individual must be defined. This target radiation dose could be applicable to a current or future individual. After the target radiation dose is selected, the amount of radioactive material in the environment that corresponds to this target radiation dose can be calculated. This calculated value is the action level.

To select the target radiation dose, applicable regulations need to be reviewed so that regulatory requirements are met. Applicable regulations from the DOE, the EPA and the NRC were reviewed. The following radiation dose standards may apply to the assessment and remediation of radionuclides in the environment at the RFETS. These standards were evaluated so that the requirements of both current and proposed radiation protection standards could be assessed.

- * DOE Order 5400.5, "Radiation Protection of the Public and the Environment."
- * Proposed Title 10 of the Code of Federal Regulations, Part 834, "Radiation Protection of the Public and the Environment," revised August 25, 1995 (Proposed 10CFR834).
- * Draft Title 40 of the Code of Federal Regulations, Part 196, "Radiation Site Cleanup Regulations," dated October 21, 1993 (Draft 40CFR196).
- * Proposed Title 10 of the Code of Federal Regulations, Parts 20, 30, 40, 50, 51, 70 & 72, "Radiological Criteria for Decommissioning," dated August 22, 1994 (Proposed 10CFR-NRC).

None of the above regulations is based on assessing and remediating radioactive materials based on

risk assessment. EPA is promoting this departure from risk assessment with their draft 40CFR196. Since the DOE, EPA and NRC are promulgating regulations using radiation dose to assess and remediate radioactive material in the environment, risk assessment will not be the basis for calculating action levels.

The requirements of the National Emission Standards for Hazardous Air Pollutants (NESHAPS) are not being considered to develop action levels; however, DOE is obligated to comply with the requirements of NESHAPS as long as RFETS is a DOE site. The DOE currently has a NESHAPS program in place. If monitoring detects a significant increase in emissions of radionuclides to the ambient air that may be due to radionuclides in soils, a source evaluation and mitigating action may be required. The action levels should be consistent with the NESHAPS requirements, since even the worst areas of soil contamination do not currently cause ambient air to exceed the NESHAPS standards.

3.2 DOE Order 5400.5

DOE Order 5400.5 prescribes the use of a 100 millirem annual radiation dose limit as recommended by the International Commission on Radiological Protection (ICRP, 1977). This order includes a recommendation that a 30 mrem radiation dose limit be applied if the actual use of a site is being examined or if the likely future use of a site is being examined. The order states that acceptable levels of radionuclides in soil shall be derived based on an environmental pathway analysis with specific property data where available. The order further states that acceptable residual radionuclide concentrations will be derived using the RESRAD (Argonne, 1993) environmental transport and radiation dose computer code. An As Low As Reasonably Achievable (ALARA) analysis must be a part of the RESRAD analysis. An ALARA analysis tries to reduce the radiation dose limit taking into account economic, social and technical factors.

The actual use or the likely future use exposure scenario represents the individual that could receive

the largest radiation dose. For exposure scenarios considered to be less likely but plausible, the 100 millirem/year limit should not be exceeded. These exposure scenarios could include a resident, an industrial worker and/or a recreational user. Radiation dose is assessed for these exposure scenarios every year in a 1,000 year time period.

3.3 Proposed 10CFR834

The provisions of DOE Order 5400.5 are currently being proposed as 10CFR834. Proposed 10CFR834 reiterates the 100 millirem per year radiation dose standard and also states that the starting point for an ALARA analysis would be 25 to 30 millirem per year. This regulation requires an environmental pathway analysis using approved models such as RESRAD to derive acceptable levels of radionuclides in the soil. With respect to exposure scenarios, 10CFR834 states that the actual and likely use scenarios and the worst plausible use scenario shall be evaluated. The requirement to evaluate the worst plausible use is only a secondary check to ensure that application of the likely use scenario does not overlook an extremely hazardous situation or a very susceptible subgroup. 10CFR834 also recommends that the dose assessment be performed for a 1,000 year time period.

3.4 Draft 40CFR196

Draft 40CFR196 states that a remediation standard of 15 mrem/yr should be used at sites with radioactive material in all environmental media. This radiation dose limit would apply to sites where the future land use is either unrestricted or restricted following remediation activities. If the land use at a site is restricted (e.g., restricting land use to open space use), the 15 mrem/year limit would apply to the restricted land use. If the land use is restricted, draft 40CFR196 also requires the assessment of the unrestricted release exposure scenario (i.e., residential exposure scenario). The radiation dose to be received by an unrestricted release exposure scenario will not exceed 75 mrem/yr (This has recently been updated to 85 mrem/yr.) so that any individual will not receive more than the ICRP recommended dose limit of 100 millirem even if land use restrictions fail in the future. An

ALARA analysis is not required.

EPA performed an extensive regulatory review before promulgating draft 40CFR196. The preamble to draft 40CFR196 compares the risks associated with remediation, transportation and disposal of contaminated soils against the risks of leaving contaminated soils in place at the 15/75 mrem per year dose limit. EPA concluded that the use of a 15/75 mrem dose limit is protective of the public. EPA recognized that the dose assessment process incorporates all pertinent facets of a CERCLA risk assessment process.

A 1,000 year time period also needs to be assessed to comply with the requirements in draft 40CFR196. This requirement came from the fact that many sites contain radionuclides with very long half-lives. The use of this assessment period will ensure that the creation of decay products and the long-term integrity of any land use restrictions are adequately considered.

3.5 Proposed 10CFR-NRC

The proposed NRC decommissioning regulations are directly comparable to the EPA's draft 40CFR196 regulations. The NRC uses a 15 mrem/yr radiation dose limit for both unrestricted and restricted land uses at a site just like the EPA draft standard. If a site is implementing land use restrictions, the NRC allows an individual in the future to receive a radiation dose of 100 millirem instead of 85 millirem. The NRC uses a 1,000 year assessment period and requires that an ALARA analysis be performed.

3.6 Rocky Flats Cleanup Agreement Regulatory Basis

The Radionuclide Action Levels Working Group has decided to use the draft 40CFR196, "Radiation Site Cleanup Regulations," regulations to derive action levels at the RFETS. This decision was made by the working group for the following reasons:

- * Remediation activities at the RFETS follow EPA and State of Colorado remediation requirements as outlined in the Rocky Flats Cleanup Agreement (RFCA). For radionuclide remediation, EPA's most current regulations need to be addressed.
- * Draft 40CFR196 is based on an extensive review of available radiation protection information.
- * Draft 40CFR196 is expected to be promulgated in the near future.
- * Draft 40CFR196 is not inconsistent with the requirements of DOE Order 5400.5, proposed 10CFR834 and the proposed NRC decommissioning regulations.
- * NRC regulations do not apply to DOE facilities.

SECTION 4 SITE CONCEPTUAL MODEL

4.1 Introduction

The Site Conceptual Model (SCM) outlines the land uses that are expected to be present at the RFETS so that action levels can be calculated for these future land uses. The type of land use is very important since the amount of time an individual may contact radioactive material in the environment is directly related to the selected land use. This contact time is then transformed into an amount of radioactive material inhaled or ingested by the individual. Action levels are derived from the radiation dose associated with radioactive material inhaled and ingested, and from external gamma exposure.

4.2 Land Uses at RFETS

Future activities at RFETS include environmental restoration, decontamination and decommissioning, economic development and waste management. The Rocky Flats Local Impact Initiative is currently working with DOE and local development agencies to encourage business development at RFETS. The Rocky Flats Future Site Uses Working Group has also developed recommendations regarding future use of the RFETS property. Residential development at RFETS has not been recommended by this group or by other planning groups. Commercial and industrial uses of developed portions of the site are considered beneficial. Even though commercial development in undeveloped portions of the property has not been ruled out, preservation of this area as open space is consistent with DOE policy, the Rocky Flats Future Site Working Group recommendations and the Jefferson County Planning Department's recommendations. The Jefferson County Board of Commissioners has also adopted a resolution stating its support of maintaining, in perpetuity, the undeveloped buffer zone as open space (DOE, 1995). Open space use assumes no development in these areas.

The land uses for RFETS are prescribed by the Rocky Flats Cleanup Agreement (RFCA) in the

preamble to that document (RFCA, 1996). The preamble states that cleanup decisions and activities are to be based on open space use and limited industrial use at RFETS. These land uses are consistent with the direction of local government as outlined above. In the near-term condition, the inner and outer buffer zones will be managed and remediated to accommodate open space uses. At the beginning of the intermediate term condition, open space use in these areas will still be applicable. Industrial uses are applicable in the industrial area of the plant in the near and intermediate term conditions. The RFCA prescribes that specific future land uses and post-cleanup designations will be developed in consultation with local governments.

4.3 Surface Soil Assessment

To be consistent with the RFCA (RFCA, 1996), the basis for radionuclide action levels in surface soils is an open space exposure scenario in the buffer zone and an office worker exposure scenario in the industrial area of the plant. Consistent with 40CFR196, the working group agreed that the hypothetical future residential exposure scenario would also be evaluated. Although conservative, the assessment of a residential exposure scenario is inconsistent with current land use recommendations. Surface soils are defined as the top 15 cm of soil.

The open space exposure scenario assumes that an individual visits the buffer zone a limited portion of the year for recreational activities. This individual could hike on trails or wade in the creeks. This individual is assumed to be exposed to radioactive material in soils by directly ingesting the soils, by inhaling resuspended soils and by external gamma exposure from the soils. Appendix C, "Analysis of Exposure Pathways for use in Deriving Action Levels," contains a detailed discussion on the selection of these three exposure pathways. For an account of the amount of time the open space user spends at RFETS, see Appendix A, "Parameter Justification and RESRAD Output." The action level for the open space exposure scenario is the amount of a specific radioactive material in surface soil that would impart an annual radiation dose of 15 millirem to the open space user during the 1,000 year assessment period.

The office worker exposure scenario assumes that an individual works mainly indoors in a building complex surrounded by extensive paved areas or well maintained landscaping. This individual is assumed to breath outside air and ingest soil from outside the building. This individual is assumed to be exposed to radioactive material in soils by directly ingesting the soils, by inhaling resuspended soils and by external gamma exposure from the soils. Appendix C, "Analysis of Exposure Pathways for use in Deriving Action Levels," contains a detailed discussion on the selection of these three exposure pathways. For an account of the amount of time the office worker spends at RFETS, see Appendix A, "Parameter Justification and RESRAD Output." The action level for the office worker exposure scenario is the amount of a specific radioactive material in surface soil that would impart an annual radiation dose of 15 millirem to the office worker during the 1,000 year assessment period.

The hypothetical future residential exposure scenario assumes that an individual resides at RFETS. This individual lives at RFETS all year and eats homegrown produce. This individual is assumed to breath outside air and ingest soil from outside the residence. This individual is assumed to be exposed to radioactive material in soils by directly ingesting the soils, by inhaling resuspended soils, by external gamma exposure from contaminated soil and by ingesting produce grown in contaminated soil. Appendix C, "Analysis of Exposure Pathways for use in Deriving Action Levels," contains a detailed discussion on the selection of these four exposure pathways. For an account of the amount of time the resident spends at RFETS, see Appendix A, "Parameter Justification and RESRAD Output." The action level for the residential exposure scenario is the amount of a specific radioactive material in surface soil that would impart an annual radiation dose of 15 millirem or 85 millirem to the hypothetical resident during the 1,000 year assessment period.

In order to carry out the original weapon-building mission, personnel at RFETS handled plutonium (Pu), americium (Am) and uranium (U) in a number of different operations. Rocky Flats plutonium was composed of Pu-238, Pu-239, Pu-240, Pu-241, Pu-242 and Am-241 (DOE, 1980), and the isotopes of uranium handled at RFETS are U-234, U-235 and U-238. Action levels in soils have been derived for Pu-238, Pu-239, Pu-240, Pu-241, Pu-242, Am-241, U-234, U-235 and U-238 in the

environment.

To calculate the radiation dose to an individual, appropriate Dose Conversion Factors (DCF) must be chosen. These DCFs convert the radioactive material present in an exposure route to a radiation dose. The three exposure routes are the ingestion, inhalation and external gamma exposure from radioactive material in soil. DCFs are therefore available for the ingestion, inhalation and external exposure routes. The DCF for each exposure route differs with the chemical form of the radionuclide. The chemical form for americium, uranium and all daughter products were conservatively chosen so that the DCF would be maximized for each exposure route. The DCFs for plutonium were chosen based on the oxide form. For a detailed discussion of the chemical form of plutonium in the environment, see Appendix B, "Analysis of the Chemical Form of Plutonium in the Environment."

4.4 Subsurface Soil Assessment

Subsurface soils are defined from 15 cm below the ground surface to the top of the ground water table. There are no exposure pathways present for the open space, office worker or hypothetical resident exposure scenarios to subsurface soils. Therefore, these exposure scenarios are not appropriate for subsurface soils. For this reason, the RFCA (RFCA, 1996) states that action levels derived for subsurface soils will be protective of surface water standards via ground water transport of radionuclides leached from subsurface soils. The surface water standard for radionuclides is the Maximum Contaminant Level (MCL) as defined by the RFCA.

The SCM for subsurface soils is represented by radionuclides first leaching from subsurface soils to ground water. The radionuclides in ground water are then transported to surface water where the radionuclide concentration cannot exceed the MCL. The subsurface soil action level is the smallest amount of a specific radioactive material in subsurface soil that would impart an MCL in surface water over the 1,000 year assessment period.

This subsurface soil SCM was examined closely by the radionuclide working group. The geohydrology of the RFETS was examined along with the subsurface soil transport properties of plutonium, americium, uranium and their daughter products. Also, the relationship between the subsurface soil SCM and the surface soil SCM was examined. The radionuclide working group came to the conclusion that a subsurface soil action level for radionuclides could not be developed at this time with the subsurface soil SCM defined by the RFCA. This conclusion was based on the variable characteristics of the SCM. This variability is attributable to 1) a water infiltration rate into the soil which varies both areally across the site and within the subsurface soils, 2) radionuclide-specific distribution coefficients that vary spatially within the subsurface soil, 3) a variable distance from a source of radioactive material in the subsurface soil to surface water and 4) a variable soil unsaturated/saturated zone thickness across RFETS. For these reasons, the radionuclide working group has decided to conservatively apply surface soil action levels to subsurface soils.

Currently there are efforts proceeding that may reduce the variability in the subsurface soil SCM. In the future, this variability may be reduced sufficiently to allow the application of the prescribed subsurface soil SCM. If this occurs, the current recommendation of the radionuclide working group may be modified.

SECTION 5 ACTION LEVEL DEVELOPMENT

5.1 Introduction

All of the ingredients for developing action levels for radionuclides in surface soils have been delineated in the preceding sections. A radiation dose limit has been established, the applicable exposure scenarios have been defined and the type of soil to be assessed has been defined. All of these facets allow the calculation of a surface soil action level for the open space exposure scenario, the office worker exposure scenario and the hypothetical future residential exposure scenario. Due to the complex nature of action level development, a computer model must be utilized to derive the action levels. The RESRAD computer model was selected for use since it fulfills all modeling requirements. Action levels were developed for the given exposure scenarios in surface soils. These action levels will be used as Tier I and Tier II action levels in the Action Levels and Standards Framework for Surface Water, Groundwater and Soils (RFCA, 1996).

5.2 Computer Code Requirements

There are a number of different processes that need to be assessed to derive action levels. Due to the complexity of each of these processes, it would be beneficial to have a computer code that would assess each of the following processes. For efficiency and compatibility reasons, the ideal computer code would incorporate all of the following processes. It is also important that the computer code(s) be validated and verified.

The first process that has to be modeled is the transport of radioactive material in surface soil to an individual. This transport can include soil transport in air, surface water, ground water and/or unsaturated zone pore water. For assessing surface soil, the most important environmental transport process for deriving action levels is the air transport process. This is important for the inhalation exposure pathway. All other environmental transport processes serve to decrease the amount of

radioactive material present in surface soil. This decrease in radioactive material over time increases the action level over time. All environmental transport processes modeled must be able to assess the movement of radioactive material and their daughter products over the 1,000 year assessment period.

The second process that needs to be examined is the exposure of a receptor to the radioactive material in the soil. There are four exposure pathways that need to be assessed by the chosen computer code. These pathways include incidental ingestion of soil, inhalation of resuspended soil, external gamma exposure from radionuclides in the soil and ingestion of homegrown produce.

The next process to be concerned with is radiation dosimetry. Once the radioactive material enters the body, a radiation dose must be calculated so that an action level can be derived. There are three modes through which radioactive material can impart radiation dose to an individual. These are through the ingestion of radioactive material, the inhalation of radioactive material and external gamma exposure from radioactive material in soil. All three of these radiation dose modes need to be assessed for each radionuclide. Since a 1,000 year assessment period is required, the radiation dose from daughter products must also be assessed.

5.3 Computer Code Selection

The RESRAD computer code (Argonne, 1993) was selected for use in deriving surface soil action levels because it meets all modeling requirements. RESRAD was developed at Argonne National Laboratory for the US Department of Energy (DOE) so that radiation dose to an individual as well as action levels could be derived for radioactive material in soils. RESRAD can model all four of the above processes in an integrated manner and can assess daughter products over the 1,000 year modeling period. RESRAD has also been validated and verified (Argonne, 1994).

Surface soils can be physically modeled by the RESRAD code. Soils are broken down into layers within the code, and the top layer, at the ground surface, can be a cover or a contaminated zone. For

deriving surface soil action levels, the contaminated zone is considered to be the surface soils with no cover. Underneath the contaminated zone, RESRAD has the capacity to model five separate uncontaminated/unsaturated layers before reaching ground water. This configuration meets the requirements for deriving action levels at the RFETS.

RESRAD can model the required environmental transport processes. It contains an air transport algorithm that looks at resuspension of radioactive material in soils and transport to an individual. The assessment of the air transport pathway is essential to calculating surface soil action levels. Unsaturated zone transport and ground water transport processes are also assessed within the RESRAD code. These two algorithms will allow leaching of radioactive material out of the surface soils for the 1,000 year assessment period. These unsaturated zone transport and ground water transport algorithms could be used in the future to model the leaching of contaminants from subsurface soils at the RFETS. With respect to environmental transport requirements, RESRAD meets the requirements for deriving action levels at RFETS.

The RESRAD code can model the four exposure pathways: incidental ingestion of soil, inhalation of resuspended soil, external gamma exposure from radionuclides in the soil and ingestion of homegrown produce. RESRAD can assess nine exposure pathways in total. These exposure pathways are external gamma exposure, soil inhalation, plant ingestion, meat ingestion, milk ingestion, aquatic food ingestion, drinking water ingestion, soil ingestion and radon exposure. This shows the flexibility of the RESRAD code in assessing many different situations. Exposure pathways can be turned on and off in RESRAD depending on the specific situation. Concerning exposure pathways, this meets the requirements for deriving action levels at the RFETS.

The RESRAD code also has an extensive library of radionuclides in their radiation dosimetry module. This allows the calculation of radiation dose and action levels on the radionuclides of interest and on their daughter products over the 1,000 year modeling period. The radionuclide database includes inhalation, ingestion and external exposure Dose Conversion Factors (DCF). These DCFs are also



available within RESRAD for the different chemical forms of radionuclides. Concerning the use of DCFs, this meets the requirements for deriving action levels at the RFETS.

5.4 RESRAD Parameter Input Development

There were four separate RESRAD computer runs that needed to be performed to obtain all required action levels. These included the following:

- * An Open Space Exposure Scenario Assessed at the 15 Millirem Level
- * An Office Worker Exposure Scenario Assessed at the 15 Millirem Level
- * A Hypothetical Future Resident Assessed at the 15 Millirem Level
- * A Hypothetical Future Resident Assessed at the 85 Millirem Level

There were 53 separate input parameters to the RESRAD code for the open space and office worker exposure scenarios. The hypothetical future resident had 83 separate input parameters. The parameters for all of these exposure scenarios were chosen to be as site specific as possible to satisfy the requirements of the site conceptual model. When a site specific parameter was not available, the RESRAD default parameter was used. For a discussion of all parameter inputs with their selected values, see Appendix A, "Parameter Justification and RESRAD Output."

5.5 RESRAD Modeling Results

Table 5-1, "Single Radionuclide Soil Action Levels," outlines the Tier I and Tier II action levels developed using RESRAD. The action levels in this table represent the radionuclide-specific activity in the soil that would impart a maximum radiation dose of either 15 millirem or 85 millirem to the given exposure scenario over the 1,000 year modeling period.

254
289

To assure that the soil action levels will be protective of human health when multiple radionuclides are present, the sum of the radiation doses from all radionuclides in soil must not exceed the Tier I or Tier II dose limit of 15 millirem or 85 millirem. A "Sum of Ratios" method will be used when more than one radionuclide is present in soils. Table 5-3, "Sum of Ratios Example," outlines this method. First, a ratio is formed for each radionuclide by dividing the activity of the radionuclide found in soils by the appropriate soil action level. This ratio actually represents the fraction of the radiation dose from the action level. In Table 5-3, the action level chosen for comparison is the Tier II action level for RFETS which is the hypothetical future resident assessed at the 15 millirem level. In this example, the radiation dose from U-235 is 1% of 15 millirem or 0.15 millirem at a soil activity of 0.3 pCi/gram. Therefore, when the ratio from each radionuclide is summed, this ratio sum is the fraction of the radiation dose limit for the action level. In Table 5-3, the sum of the ratios is 0.22 or 22% of 15 millirem. In this example, the Tier II action level is not exceeded since the sum of ratios is less than or equal to 1.0. If the sum of ratios exceeded 1.0, the action level would be exceeded.

The action levels for americium and plutonium together can also be calculated since the activity of Am-241 is about 18% of the Pu-239+Pu-240 (Pu-239/240) activity in the environment (Ibrahim, 1996). Given this activity ratio, the action level for Am-241 and Pu-239/240 can be computed so that the sum of their radiation doses equals either 15 or 85 millirem to the appropriate exposure scenario. Table 5-2 includes an example of these adjusted action levels for Am-241 and Pu-239/240 if they are the only radionuclides present in soil. Since the 18% ratio actually varies in the environment, site specific data will be used to make action level comparisons. If uranium is also present in the soil, then the contribution to the radiation dose from the uranium also needs to be assessed so that the Tier I and/or Tier II action level basis is not exceeded.

Chemical action levels are risk-based, and chemical risk is considered additive when multiple chemicals are present. Radionuclide action levels are dose-based, and radiation dose is considered additive when multiple radionuclides are present. Chemicals and radionuclides will be assessed independently on a project-specific basis using methodology that is protective of human health and

5.6 Use of RESRAD Modeling Results

The action levels outlined above need to be applied in the field. To do this, a number of simplifying assumptions can be made while still assuring the protectiveness of the action levels. This simplification allows implementation of these action levels in an efficient manner.

The first simplification is that the number of radionuclides needing assessment at RFETS can be reduced. All uranium (U) radionuclides present at RFETS (e.g., U-234, U-235 and U-238) in the environment will be assessed with respect to their action levels. Appendix D, "Analysis of Assessment Needs for Rocky Flats Plutonium," outlines the reasons why the only constituents from Rocky Flats plutonium that need to be assessed in the environment are Pu-239, Pu-240 and Am-241. All isotopes of Rocky Flats plutonium were initially assessed for completeness since plutonium in the nuclear fabrication process was composed of Pu-238, Pu-239, Pu-240, Pu-241 and Pu-242 (DOE, 1980). Am-241 is also contained in this mix of plutonium due to its ingrowth from Pu-241 (DOE, 1980). The plutonium found in the environment though will have different activities of plutonium and americium than what is found in the fabrication process because of radionuclide decay and ingrowth over time. In examining this decay and ingrowth with regard to radionuclide toxicity, it is shown in Appendix D that it is necessary to only assess Pu-239, Pu-240 and Am-241 in the environment.

The number of exposure scenarios that need to be examined can also be reduced. The more conservative of the Tier I action level for the open space exposure scenario and the Tier I action level for the hypothetical future resident will be applied in the buffer zone at RFETS. Also, the more conservative of the Tier I action level for the office worker exposure scenario and the Tier I action level for the hypothetical future resident will be applied in the industrial area at RFETS. These comparisons were made and the result is that the Tier I action level in the buffer zone will be based on the hypothetical future resident exposure scenario and that the Tier I action level in the industrial area will be based on the office worker exposure scenario. Table 5-2, "Tier I & II Soil Action Levels," outlines the soil action levels after the above simplifications are made.

the environment. The cumulative effects of chemicals and radionuclides will be assessed on a project-specific basis if the chemical risk and the radionuclide dose are near their respective Tier I action levels.

5.7 Action Level Uncertainties

The calculated values recommended as action levels are based on several assumptions which have associated limitations. These include:

1. The regulatory basis for developing these action levels is EPA's draft rule, 40CFR196, which is not yet final and may be changed before it is promulgated.
2. Any environmental computer model, including the RESRAD model, has inherent limitations with regard to precise simulation of the actual environment. Some of these limitations involve which input parameters are chosen to represent the complex natural setting which may vary across a large site. Environmental transfer factors and dose conversion factors used in the model may not always reflect site-specific conditions.
3. There are inherent uncertainties in estimating either dose or risk from ionizing radiation.
4. Institutional controls will eliminate the ground water ingestion pathway by establishing specific land uses and controls on ground water use. A basic assumption of RFCA is that ground water from contaminated areas of the site is captured, controlled and measured within the surface water system before leaving the site. An additional assumption is that the small amount of shallow ground water is not a sustainable, viable source of residential drinking water.
5. Attachment 5 of RFCA requires subsurface soil action levels to be protective of surface water

standards via ground water, and surface soil action levels to be protective of surface water standards via runoff. Existing data supports the proposition that radionuclides in soil are stable and relatively immobile. This is the basis for determining not to include these transport pathways in the modeling done to develop the proposed action levels. It is also assumed that actions required by the proposed action levels for radionuclides in soil (removals and/or stabilization) will provide sufficient protection for surface water. Those actions will control the worst areas of radiological contamination in soils, and so far, even these areas have not impacted surface water above the 0.15 pCi/L level at the point of compliance.

6. The proposal to set subsurface soil action levels equal to surface soil action levels assumes there will be no uncontrolled human exposure to subsurface soils and presumes that surface soil action levels will be protective of surface water via ground water. It is also assumed that the proposed surface soil action levels are lower than values that any subsurface soil modeling would produce.

This working group acknowledges that in the future, new regulations, different guidance, improved calculation methods and models and better input parameters will likely become available. As this new information becomes available it will be considered in accordance with paragraph 5 of RFCA.

TABLE 5-1
SINGLE RADIONUCLIDE SOIL ACTION LEVELS

Radionuclide	<u>TIER I</u> <u>ACTION</u> <u>LEVEL</u> Open Space Exposure Scenario, Surficial Soils Exposure, 15 Millirem Dose Limit (pCi/gram)	<u>TIER I</u> <u>ACTION</u> <u>LEVEL</u> Office Worker Exposure Scenario, Surficial Soils Exposure, 15 Millirem Dose Limit (pCi/gram)	<u>TIER I</u> <u>ACTION</u> <u>LEVEL</u> Hypothetical Residential Exposure Scenario, Surficial Soils Exposure, 85 Millirem Dose Limit (pCi/gram)	<u>TIER II</u> <u>ACTION</u> <u>LEVEL</u> Hypothetical Residential Exposure Scenario, Surficial Soils Exposure, 15 Millirem Dose Limit (pCi/gram)
Americium-241	1283	209	215	38
Plutonium-238	10580	1164	1529	270
Plutonium-239	9906	1088	1429	252
Plutonium-240	9919	1089	1432	253
Plutonium-241	48020	7801	19830	3499
Plutonium-242	10430	1145	1506	266
Uranium-234	11500	1627	1738	307
Uranium-235	1314	113	135	24
Uranium-238	5079	506	586	103

* The action levels in this table apply to single radionuclides only which does not exist at RFETS. See text for application of these action levels

TABLE 5-2
TIER I & II SOIL ACTION LEVELS

Tier I Action Level For The Buffer Zone (Hypothetical Resident)

Radionuclide	Hypothetical Resident - 85 mrem Annual Radiation Dose (a) (pCi/gram)	Hypothetical Resident - Ratio Sum to 85 mrem Annual Radiation Dose (b) (pCi/gram)
Americium-241	215	117
Plutonium-239/240	1429	651
Uranium-234	1738	
Uranium-235	135	
Uranium-238	586	

Tier I Action Level for The Industrial Area (Office Worker)

Radionuclide	Office Worker - 15 mrem Annual Radiation Dose (a) (pCi/gram)	Office Worker - Ratio Sum to 15 mrem Annual Radiation Dose (b) (pCi/gram)
Americium-241	209	101
Plutonium-239/240	1088	562
Uranium-234	1627	
Uranium-235	113	
Uranium-238	506	

Tier II Action Level For RFETS (Hypothetical Resident)

Radionuclide	Hypothetical Resident - 15 mrem Annual Radiation Dose (a) (pCi/gram)	Hypothetical Resident - Ratio Sum to 15 mrem Annual Radiation Dose (b) (pCi/gram)
Americium-241	38	21
Plutonium-239/240	252	115
Uranium-234	307	
Uranium-235	24	
Uranium-238	103	

(a) - These values apply to single radionuclides only which does not occur in the environment at RFETS. The "Sum of Ratios" method will be applied at RFETS so that the total dose from multiple radionuclides are correctly assessed.

(b) - This example assumes that the Am-241/Pu-239 activity ratio equals 0.18 and that only Pu-239 and Am-241 are present

TABLE 5-3
SUM OF RATIOS EXAMPLE

15 mrem Residential Action Level Comparison

Radionuclide	Action Level (pCi/gram)	Soil Activity (pCi/gram)	Soil Activity to Action Level Ratio
Americium-241	38	2.6	0.07
Plutonium-239	252	13.8	0.05
Uranium-234	307	6.8	0.02
Uranium-235	24	0.3	0.01
Uranium-238	103	6.4	0.06
SUM OF RATIOS			0.22

Decision Criteria

SUM OF RATIOS \leq 1: ACTION LEVEL MET
SUM OF RATIOS $>$ 1: ACTION LEVEL EXCEEDED

SECTION 6 REFERENCES

References

Argonne, 1993 - Manual for Implementing Residual Radioactive Material Guidelines Using RESRAD, Version 5.0, Environmental Assessment and Information Sciences Division, Argonne National Laboratory, ANL/EAD/LD-2, September 1993

DOE, 1980 - Final Environmental Impact Statement, Rocky Flats Plant Site, Golden, CO, US Department of Energy, DOE/EIS-0064, April 1980

DOE, 1995 - Phase II RFI/RI Report, 903 Pad, Mound and East Trenches Area, Operable Unit Number 2, Draft Final, US Department of Energy, May 1995

Ibrahim, 1996 - Comparative Distribution of Am-241 and Pu-239/240 in Soils Around the Rocky Flats Environmental Technology Site, Health Physics, Vol. 70, No. 4, April 1996

ICRP, 1977 - International Commission on Radiological Protection (ICRP), Recommendations of the ICRP, ICRP Publication 26, 1977

RFCA, 1996 - Rocky Flats Cleanup Agreement, Joint Agreement between the US Department of Energy, the US Environmental Protection Agency, the Colorado Department of Public Health and Environment and the State of Colorado, dated July 19, 1996

Appendix M

PROCESS DESCRIPTION FOR EVALUATING IMPACTS TO SURFACE WATER AND ECOLOGICAL RESOURCES

APPENDIX M

Process Description for Evaluating Groundwater Impacts to Surface Water and Ecological Resources

1.0 INTRODUCTION

The purpose of this appendix is to provide a "process description" to integrate the goals and objectives of groundwater monitoring, hydrogeologic characterization, and remedial actions at RFETS. The intent of this process description is not to prescribe specific analyses that must be performed, but to present a general approach that defines how groundwater contamination at RFETS will be assessed and addressed. By developing an integrated process, it is expected that the basis for decisions regarding the need for remediation and the evaluation of remediation performance will be consistent and will effectively protect surface water and ecological resources. A description of the groundwater plume management and remediation strategy is provided in the IMP Background Document. This appendix encompasses the content of the strategy in the IMP.

In essence, the groundwater contamination assessment and remediation evaluation process consists of the following phases:

- Initial determination of actual or potential groundwater contamination
- Development of a conceptual model based on adequate characterization of the source, nature, and extent of groundwater contamination
- Evaluation of whether contaminated groundwater has or will adversely impact surface water and ecological resources
- Evaluation of alternatives for mitigating groundwater contamination which impacts surface water or ecological resources, and the selection of an appropriate remedial action
- Verification of the appropriateness or effectiveness of the selected remedial action

In the following sections, each of these phases is discussed in more detail

1.1 INITIAL DETERMINATION OF GROUNDWATER CONTAMINATION

This phase is intended to determine whether there is a potential contamination problem. During this phase, no attempt will be made to determine the cause of contamination or how the groundwater contamination is distributed. The evaluation of the presence of groundwater contamination, and if the contamination could impact surface water, is the first threshold when determining if further action is required.

Previous groundwater monitoring programs such as the OU RI/RFI and site-wide characterization activities have made an initial determination of the areas where groundwater

is contaminated. The IMP provides for continued monitoring to assess changes in these areas of groundwater contamination and to identify new problem areas.

1.2 CHARACTERIZATION OF THE GROUNDWATER CONTAMINATION AREA (PLUME EVALUATION)

The primary purpose for characterizing and evaluating the nature and extent of groundwater contamination is to obtain sufficient data to support the development of a conceptual model of the problem area and to support the analyses necessary to evaluate the impact to surface water or ecological resources. Characterization may include, but is not limited to:

- Defining the extent of groundwater contamination
- Identifying potential source areas and contaminants of concern
- Defining plume extent through determining the linear and areal extents of the pathway through subsurface correlation of standard thickness and permeable lithologies
- Recharge and discharge through quantification of water balance, flow velocity, gradient, and direction of groundwater
- Concentration loadings and mass flux of contaminants to surface water
- Effects due to seasonal variations, natural attenuation of contaminants, or changes in discharge due to construction/removal of containment structures, treatment systems or removal of sources

Decisions with respect to plume evaluations will be made with consultation from the groundwater workgroup during various stages of the process. Results of the characterizations will be used to update the ER ranking process under RFCA to ensure that the available budget will be allocated to areas with the highest potential for contamination.

1.2.1 Evaluation of Existing Data

Once the available data have been compiled they can be used to develop a conceptual model of the groundwater contamination area. As the conceptual model is being formulated, ongoing evaluations will be performed to determine whether the data set is of sufficient quantity and quality to support the conceptual model. Some of the questions that should be answered include:

- Are the types of data adequate for the conceptual model (e.g., hydraulic conductivity, stratigraphic, and geologic, piezometric, water quality analyses for the contaminants of concern)
- Is the quantity of data sufficient (e.g., spatial or temporal coverage)
- Is the quality of the data set sufficient to address the program objectives (e.g., use of accepted analytical methods, meeting QA/QC objectives)

If a consideration of these questions shows that the available data are inadequate, then additional data should be collected to fill the data gaps.

1.2.2 Collection of Additional Data

Prior to collecting any additional data, the DQOs should be defined to provide a clear purpose for collecting the additional characterization data. For example, an objective might be to better delineate groundwater flow direction, or to determine concentration trends within specific wells. Once the DQOs have been defined, then the appropriate sampling program may be developed and implemented. At this stage, the new data are incorporated and the conceptual model refined. The data questions outlined above should be addressed to determine whether the conceptual model is valid.

1.2.3 Establishing Baseline Conditions

The baseline assessment may have either of two purposes. The first purpose is to establish the current level of impacts to surface water or ecological resources. The second purpose may be to establish hydrogeologic conditions at specified locations prior to, during, or immediately after remediation.

In the first instance, the baseline case is used to determine whether changes in upgradient conditions will have an adverse or beneficial impact on downgradient surface water or ecological resources. In addition, the first type of baseline case can factor into the decision whether remediation or continued monitoring is the appropriate course of action to protect surface water or ecological resources. In the second instance, the baseline assessment will be the basis for evaluating how downgradient conditions change in response to upgradient remedial actions.

1.3 EVALUATION OF IMPACTS TO SURFACE WATER OR ECOLOGICAL RESOURCES

Pursuant to the RFCA, "[p]rotection of all surface water uses with respect to fulfillment of the Intermediate and Long-Term Site Conditions will be the basis for making soil and ground water remediation and management decisions." Therefore, it is necessary to evaluate the current and future impacts of groundwater on surface water or ecological resources to ensure that these resources are protected.

The evaluation of impacts to surface water will focus on three areas: the direct discharge of groundwater or seeps to surface water; the impact of groundwater to a specified reach of the stream (surface water and alluvium) downgradient from the point of discharge; and the concentration of contaminants at downstream surface water monitoring locations.

Ecological impact assessments will be based on site-specific conditions. The impact evaluations may either be supported directly by the data, by the use of analytical methods, or, if necessary, through the application of numerical models. The determination of which method of analysis to use will be based on the issues that are to be addressed, the limitations inherent in the data, the accuracy of the desired results, or available resources.

1.4 EVALUATION OF ALTERNATIVE REMEDIAL ACTIONS

Upon determination that contaminated groundwater has or may potentially impact surface water or ecological resources, alternative remediation scenarios should be evaluated.

Alternative remedial actions include, but are not limited to:

- No action
- Source removal
- Source containment
- Plume containment
- Plume interception

Alternatives will be developed and considered on a site-by-site basis. The evaluation of alternatives will generally consist of the following steps:

- Definition of remediation objectives
- Determination of whether the data and conceptual model will support the analyses necessary to evaluate the different alternatives
- Completion of an alternatives assessment including the evaluation of surface-water or ecological impacts during remedy implementation, and in the future, considering the compatibility with other RFETS closure activities
- Selection of an alternative that is protective of surface water and ecological resources

The results of the alternatives analysis will be presented in a RFCA decision document. In essence, the documentation should summarize:

- The conceptual model describing hydrogeologic conditions
- The analytical tools used to evaluate the data
- The basis for selecting the parameters used for assessing system performance
- The type of impact, if any, to surface water or ecological resources
- How impacts have changed and may change with time
- The assessment of alternatives if remedial action is necessary
- Outline of remedial design/construction and/or monitoring actions as necessary

Development and consideration of alternatives will involve consultation with the groundwater working group during key phases of the process. Within this context, the parties should reach a consensus regarding specific contaminant source areas, groundwater plumes, and the appropriate response. Once an alternative has been selected, a remediation/management project will be developed with its own scope, schedule, and budget.

1.5 REMEDIAL DESIGN/CONSTRUCTION

If a remedial action decision has been reached, additional information may be needed to aid the design and construction of the remedial system. A DQO process, as defined in the IMP, will be employed to establish the decision, and data needs to aid in the construction of the remedial system. The remedial system may consist of a groundwater containment or treatment system, or a source removal action. Components of this step may include:

- Preparation and presentation of design documents and construction workplans
- Preparation and presentation of additional sampling and analysis plans
- Determination of performance monitoring requirements

Development and consideration of alternatives will involve consultation with the groundwater workgroup during key phases of the project.

1.6 VERIFICATION OF THE SELECTED REMEDIAL ACTION

Once a selected remedial action has been implemented, it may be necessary to demonstrate that the action meets the prescribed remediation goals. To verify the adequacy of a remedial action, the performance criteria must be clearly defined. For example, the performance criteria for a source removal remedy would be quite different than the performance criteria for a plume intercept remedy. The effectiveness of the former could be easily demonstrated by a trend showing a reduction with time of contaminant concentrations in and immediately downgradient of the remediated area; whereas the effectiveness of a plume intercept system might be evaluated relative to water quality criteria at a point of compliance. The performance criteria will need to be defined on a case-by-case basis, accounting for the site- and contaminant-specific characteristics of different plumes. Decisions will require consultation of the groundwater working group during key phases of the evaluation, and performance monitoring will be implemented through the IMP process.

Appendix N

METHODOLOGY FOR UPDATED ENVIRONMENTAL RESTORATION RANKING

APPENDIX N

METHODOLOGY FOR UPDATED ENVIRONMENTAL RESTORATION RANKING

1.0 FISCAL YEAR 1996 - UPDATE ENVIRONMENTAL RESTORATION RANKING

This document presents the fiscal year 1996 (FY96) update to the methodology presented in the RFCA Attachment 4, which contains the 1995 prioritized list of ER sites developed to select the top priority sites for remediation (DOE, 1995a). The ER ranking was developed to be used as an aid in planning and prioritizing remedial actions at RFETS. The sequence of remediation activities at RFETS has generally followed the prioritization. Other factors that also influence the remediation sequence are funding, project cost, resource availability, data sufficiency, and integration with other remedial and Site activities. Prioritization accelerates the cleanup process of the worst sites first, and more quickly reduces risks to human health and the environment. The prioritization of cleanup targets also results in cost reductions by allowing better planning, and more efficient utilization of resources.

The 1995 prioritization methodology was developed by a working group of the EPA, CDPHE, DOE, Kaiser-Hill, and RMRS staff and was implemented by RMRS. The result was a prioritized list of ER sites, including a list of ranked sites that require more information (DOE, 1995a). In accordance with RFCA Attachment 4, the ranking has been updated during FY96. The evaluation process is essentially the same as was used in the September 1995 ranking, with the following exceptions:

- ALF for Surface Water, Groundwater, and Soils (RFCA Attachment 5) values were used
- The scoring scale was adjusted to reflect the greater range in ALF ratios
- Impact to surface water was evaluated instead of mobility
- A professional judgment factor was added to account for process knowledge
- Groundwater plumes were evaluated and ranked separately from the contaminant source
- The secondary evaluation, which included project cost and schedule estimates, has been omitted due to other planning activities ongoing at the RFETS

1.1 METHODOLOGY

The ranking process detailed in RFCA Attachment 4 was slightly modified in 1996 to incorporate the ALF and process knowledge. This ranking was generated by using concentrations of contaminants present at different sites, action levels for the appropriate media and location, and factors for impact to surface water, potential for further release, and professional judgment to develop a score for each site. The scores were then ranked to determine which sites have the highest priority. This methodology is conservative and is used only to generate a list to prioritize remedial actions, and pre-remediation investigations. It is not meant to replace a formal risk assessment.

Ecological risk was also considered during the ranking. The recently completed ecological risk assessment was considered during evaluation of the Buffer Zone. There is no unacceptable ecological risk from Buffer Zone IHSSs under present conditions and exposure pathways. An ecological risk assessment has not been completed for the Industrial Area. Ecological factors were not considered when ranking IHSSs in this area.

The following steps were used in the 1996 ranking process:

- The existing analytical data were compared to background data
- Data exceeding background were compared to the ALF Tier I and Tier II values
- Ratios of Tier II ALF values to contaminant concentrations/activities were used for the ranking, unless Tier II values were not available
- A column was added to the ranking sheet to note Tier I exceedances
- The resulting ratios were converted to a score of 1 to 10
- The impact to surface water was evaluated, and assigned a factor of 1 to 3
- The potential for further release was evaluated, and a factor of 1 to 3 applied
- Process knowledge of the site was evaluated, and a professional judgment factor of 0.5 to 2 applied
- The results of the previous steps were multiplied to generate a score per site; this score was used to rank the ER sites

Analytical data in the SWD from 1990 to the present were evaluated for three media; surface soils, subsurface soils, and groundwater. The analytical data were extracted from the SWD and compiled into data sets by media and analytical suite. The media-specific analytical data were compared to the media- and chemical-specific background mean plus two standard deviations (M2SD). All data above the background M2SD were then compared to the appropriate Tier I and Tier II ALF values in RFCA. The draft radiological ALF values for surface soils (See Appendix L) were applied to both surface and subsurface soils. The ALF values for metals in subsurface soils were not agreed upon in time to be included in the 1996 ranking and metals data from subsurface soils were not used in the ranking. A review of the data suggests that this will not effect the ranking significantly.

All exceedances of the Tier I and II ALF values were tabulated for groundwater, subsurface soils, and surface soils at each sample location. The locations were plotted on maps using available survey information. Where no survey data is available, approximate locations were derived from work plan maps. The sample locations were assigned to areas-of-concern, IHSSs, and groundwater plumes based on the media, location of the exceedance, and the analyte.

Media Specific Evaluations

Groundwater - Sitewide groundwater data were compared to background M2SD values presented in the 1993 *Background Geochemical Characterization Report* (DOE, 1993a). Groundwater data were then compared to the Tier I and Tier II ALF values. All well locations where a chemical concentration exceeds a Tier I or Tier II ALF value were plotted. The locations were then associated with the most probable source area and known groundwater plumes. Ratios of analyte concentrations to the Tier II ALF values were used in the scoring.

Subsurface Soil - All available subsurface soil data collected since 1990 were compared to subsurface soil background M2SD values (DOE, 1993a). The data for volatile organic compounds were compared to the Tier I ALF values (there are no Tier II values), the radiological activities were compared to the surface soil Tier I and Tier II ALF values. The ALF values for metals in subsurface soils are in ALF. The locations of all borings where a chemical concentration exceeded an ALF value were plotted and associated with the most likely source area.

Surface Soil - All available surface soil data for metals and radiologicals were compared to M2SD background values computed from data presented in the *Geochemical Characterization of Background Surficial Soils, Background Soils Characterization Program, May 1995* (DOE, 1995c). The inorganic and radiological results above background and all data for organic compounds were compared to the Tier I and Tier II ALF values for surface soil. Within the boundaries of the Industrial Area OU, the surface soil data were compared to office worker ALF values. In the Buffer Zone OU, the surface soil data were compared to open space ALF values. The ALF exceedances were plotted to determine the most likely source area, IHSS or group of IHSSs, using the most common wind patterns. Ratios of analyte concentrations to the Tier II ALF values were used in the scoring.

Chemical Score Tabulation

All ALF exceedances were tabulated by IHSS, group of IHSSs, or source area. The chemical score was calculated for each media, within each site, by adding the maximum ratio for each analyte per media. The groundwater, subsurface soil, and surface soil scores were then summed to generate a total score per site. This is a conservative approach that allows the sites to be judged on a uniform basis.

A separate score was derived for each groundwater plume by evaluating only the groundwater exceedances. A risk score was calculated for each plume, as above, by adding the maximum ALF ratios for groundwater contaminants associated with all sites within the estimated plume area. This method results in groundwater being used twice; once in the scoring of sources, and again for the scoring of groundwater plumes. The total chemical scores were graded according to the following table so that the risk component of the ranking system would be weighted similarly to the other components. This table has been adjusted from the 1995 methodology due to the increase in the range of the scores.

Total Chemical Score	ALF Score
>20001	10
10001-20000	9
5001-10000	8
1001-5000	7
501-1000	6
251-500	5
126-250	4
75-125	3
26-75	2
1-25	1

Surface Water Impacts

The impact of contamination at a site on surface water quality was evaluated and each site was assigned a factor of 1 to 3 to indicate the impact on surface water from each site. The impact to surface water factors were assigned on a scale of 1 to 3 as follows:

1. Contaminants that are immobile in the environment or for which there is no pathway to surface water. Radionuclides and metals were given a score of one unless adjacent to surface water, or on a steep slope bordering surface water. This rating was used where engineered structures are in place that prevent the spread of contaminants.
2. This rating was applied where contaminants have or are expected to have an impact on surface water at the Tier II ALF level (MCL).
3. This rating will apply where there is a documented or probable impact to surface water above the Tier I ALF value (100 x MCL).

Potential for Further Release

This factor takes into account the potential for additional release of contaminants into the environment and includes cross-media movement of contaminants within the environment. Sites were assigned a value of 1 to 3 based on the following criteria:

1. Assigned to a location when contamination were not present as free product, very high concentrations, and/or show no cross contamination of environmental media.
2. Any location where free product may be present in the ground and/or where there is a potential for cross contamination.

3. Locations where there is indication or certainty that free product exists in the ground, where significant levels of contamination exist, and/or where cross contamination of environmental media is present.

Professional Judgment

A professional judgment factor was added to the FY97's ranking based on process knowledge not represented by the other factors. The reasons for assigning the professional judgment factor are given in the comment column of the ranking. The values for this factor are:

- 0.5 The ranking overestimates the priority of a site. This was used if a risk assessment or conservative screen has been completed indicating an acceptable risk, but the site ranks high on the priority listing.
- 1 The ranking reflects process knowledge of a site.
- 2 The ranking underestimates the priority of a site. This may be due to a lack of data, coupled with process knowledge of significant releases.

Total Score and Ranking

The total score was calculated by multiplying the ALF score times the impact to surface water, potential for further release, and professional judgment factors. A formal risk assessment is a more precise evaluation of the same data, and, where risk assessment data exist, they were used to refine the ranking of the sites through the use of the professional judgment factor.

Where insufficient data currently exist to rank sites, these sites were assigned to the category of needs further investigation (INV) and ranked using the professional judgment factor. This placed them on the ranking above known low-risk sites. As data become available, the ranking for these sites will be updated.

The Solar Ponds groundwater score was calculated without using data from an upgradient well which shows the effects of an upgradient plume. Instead, this well was used in the calculations for the groundwater score for IHSS 118.1 and the carbon tetrachloride spill plume.

Where analytical data and process knowledge indicate that there are localized areas of contamination, the associated data were eliminated from site evaluation, and assigned to a hot spot list. These sites will be evaluated to verify that these are hot spots. Most of the localized extent sites are PCB sites, including a PCB site in IHSS 150.6 and those surrounding Bowman's Pond. The Old Landfill has analytical data indicating the presence of small radiological anomalies at the surface. Best management practices will be used on these hot spots as part of the final remedy for the Old Landfill.

Radium 226 and 228 data were not evaluated for the following reasons:

- Radium 226 and 228 are not listed as having been used at RFETS in either the *Historical Release Report* (DOE, 1992a) or the *Project Task 3/4 Report: Reconstruction of Historical Rocky Flats Operations and Identification of Release Points* (ChemRisk, 1992)
- The decay chains and half-lives of decay products make it highly unlikely that significant amounts of radium 226 or 228 would have accumulated by radioactive decay of radionuclides known to have been used at RFETS
- The soils and groundwater in the foothills to the west of RFETS are known to have high levels of both uranium (total) and radium 226
- The background amount for radium 226 in surface soil has a PPRG ratio of 48. Therefore, any surface soil analytical result above background would skew the prioritization score to a higher result. This is not justified given the information on usage and natural occurrence

Appendix O

EXAMPLE OF HISTORICAL RELEASE REPORT UPDATE

Figure 1

1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 26

75

12

APPENDIX O

1.0 EXAMPLE OF HISTORICAL RELEASE REPORT UPDATE

PAC REFERENCE NUMBER: NW-195

IHSS Reference Number: 195, Operable Unit 16
Unit Name: Nickel Carbonyl Disposal
Approximate Location: N754,500; E2,083,000

Date(s) of Operation or Occurrence

March through August 1972

Description of Operation or Occurrence

From March through August 1972, cylinders of nickel carbonyl were disposed in a dry well located in the buffer zone. The cylinders were opened inside the well and vented with small arms fire to allow decomposition in air (DOE 1994b).

Physical/Chemical Description of Constituents Released

Nickel carbonyl vapors are denser than air. Consequently, the vapors collected and decomposed in the bottom of the well. Because these vapors ignite spontaneously, ignition occurred either immediately after release into the well or sometime after collection at the bottom of the well (DOE 1992a, 1992b).

Response to Operation or Occurrence

After 24 hours of placement in the well, the cylinders were removed from the hole, vented by small arms fire, and buried in the Present Landfill. Two cylinders became stuck in the hole and were buried in place. A minimal amount of nickel carbonyl was probably released to the atmosphere during disposal. Samples (presumably of air) from the lip of the well taken after the initial disposal indicated nickel carbonyl concentrations of approximately 10 parts per million being released during disposal (DOE 1992a, 1992b). This IHSS was then studied in accordance with the IAG as part of OU 16 (DOE 1992b).

Fate of Constituents Released to the Environment

Nickel carbonyl is highly volatile and readily decomposes in the presence of oxygen, forming nickel oxide. Nickel oxide is highly insoluble in groundwater. For every gram (0.002 pound) of nickel oxide in contact with typical groundwater, approximately 10–26 microgram of

nickel per liter is transferred to solution. Wind dispersion subsequently disseminated the nickel oxide particles, which therefore would not be detected at concentrations exceeding background. IHSS 195 does not pose a risk to human health and the environment because there are no viable transport pathways.

Action/No Action Recommendation

Based on information presented in the *Final No Further Action Justification Document for Operable Unit 16, Low-Priority Sites* (DOE 1992b), a CAD/ROD recommending no action under CERCLA for IHSS 195 was prepared, and received final approval on October 28, 1994 (see attached declaration).

Comments

None.

APPENDIX 9

PROPOSED REMEDIATION
23A00

This page intentionally left blank
"Final Rocky Flats Cleanup Agreement"

1.0 INTRODUCTION

DOE developed risk-based PPRGs in 1995 to establish initial site-wide cleanup targets for contaminants for each environmental medium. The PPRGs are currently used in RFCA Attachment 5, as action levels for the following mediums:

- Groundwater Action Levels: PPRGs based on residential groundwater ingestion scenario are used where no Maximum Contaminant Level (MCL) is available from EPA;
- Surface Soil Action Levels: For non-radionuclides, PPRGs are used as action levels for the appropriate land use, e.g., industrial use or open space use; and
- Subsurface Soil Action Levels: For non-radionuclide inorganics, PPRGs are used as action levels for the appropriate land use, e.g., industrial use or open space use.

PPRGs are reviewed and updated, as necessary, on an annual basis.

2.0 EXPOSURE PATHWAYS

In order to standardize the risk-based PPRGs across RFETS, programmatic exposure pathways and receptors were established. The following tables identify the receptors and exposure pathways selected for each environmental medium:

- Table 1: Residential Groundwater Exposure Scenario
- Table 2: Office Worker Surface Soil Exposure Scenario
- Table 3: Open Space Surface Water Exposure Scenario
- Table 4: Open Space Surface Soil Exposure Scenario

Standard assumptions given in Risk Assessment Guidance for Superfund (RAGS), Part B (USEPA, 1991) were used in developing risk-based PPRG pathways where available. For situations not addressed by RAGS, Part B, standard assumptions given in RAGS, Part A (USEPA, 1989) were used. In addition, site-specific information was used where appropriate to supplement assumptions given in EPA guidance. Best professional judgement was applied when default values differed from site-specific information.

In addition to EPA and site-specific information, CDPHE guidance (*Interim Final Policy and Guidance on Risk Assessments for Corrective Action at RCRA Facilities*) was consulted for exposure pathways and parameters. While this guidance has not been finalized, it was reviewed and CDPHE was consulted on its use during development of the risk-based PPRG pathways.

3.0 METHODOLOGY, EQUATIONS, AND ASSUMPTIONS

Risk-based PPRGs were developed for all Target Analyte List metals, Target Compound List organics and 13 radionuclides for the residential groundwater exposure scenario; the office worker surface soil exposure scenario; the open space surface water exposure scenario; and the open space surface soil exposure scenario. Separate risk-based equations were developed to account for the carcinogenic, noncarcinogenic, and/or radiological effects of the contaminant. Risk-based PPRGs for carcinogens (including radionuclides) were calculated by setting the carcinogenic target risk level at 10^{-6} . A target risk level of 10^{-6} means that an individual has a one-in-one million probability of developing cancer over a lifetime as a result of exposure to a specific contaminant. This risk is in addition to the probability of an individual developing cancer from some other factors such as those associated with heredity or lifestyle. Similarly, risk-based PPRGs for toxicants (noncarcinogens) were calculated by setting the hazard quotient equal to 1 for each contaminant. A hazard quotient is the ratio of a single substance exposure level of a chemical contaminant over a specified period to the reference dose for the chemical. The reference dose represents an estimate of an exposure level for the human population, including sensitive subpopulations that is likely to be without appreciable deleterious effects during a lifetime. For some of the contaminants both carcinogenic and noncarcinogenic toxicity information was available. For these contaminants, both a carcinogenic and noncarcinogenic risk-based concentration was calculated and the more restrictive value was selected as the risk-based PPRG. The risk-based equations for radiological effects were used to calculate the risk-based PPRGs for the 13 radionuclides.

The risk-based PPRG exposure scenarios and equations provided in Tables 1 through 4 include all of the exposure pathways (e.g., direct ingestion of soils) identified for the exposure scenario; separate risk-based PPRGs were not calculated for each exposure pathway.

4.0 CHEMICAL TOXICITY INFORMATION

The chemical-specific toxicity values used for the calculation of the risk-based PPRGs are presented in Table 5. The toxicity information used to calculate the risk-based PPRGs included the slope factor and unit risk for evaluating carcinogenic effects; the reference dose (RfD); and the reference concentration (RfC) for evaluating noncarcinogenic effects. Toxicity values were obtained from the latest information in EPA's Integrated Risk Information System (IRIS) files and the 1997 EPA Health Effects Assessment Summary Tables. Values for polycyclic aromatic hydrocarbons were calculated using EPA's Provisional Guidance for Quantitative Risk Assessment of Polycyclic Aromatic Hydrocarbons.

5.0 RFETS PPRGs

Table 6 is a summary of the PPRGs for each exposure scenario.

Table 1 - Residential Exposure Scenario RFETS PPRGs

The Residential Groundwater Exposure Scenario consists of the following pathway: ingestion of groundwater (which includes radiation exposure while ingesting groundwater) for an adult resident living at the site for 30 years. This scenario includes only pathways that were evaluated in the Rocky Flats Cleanup Agreement (RFCA) to derive action levels.

Exposure Parameter	Variable	Unit	Value	Source
General Assumptions				
Target hazard index	THI	--	1	EPA, 1991a
Target excess lifetime cancer risk	TR	--	1E-06	EPA, 1991a
Adult body weight	BW	kg	70	EPA, 1991b
Residential Exposure Scenario Assumptions				
Averaging time - noncarcinogenic	AT_NC	yr	30	EPA, 1991b
Averaging time - carcinogenic	AT_C	yr	70	EPA, 1991b
Exposure frequency	EF	day/yr	350	EPA, 1991b
Exposure duration	ED	yr	30	EPA, 1991b
Daily water ingestion rate	IRw	L/day	2	EPA, 1991b
Toxicity Values				
Oral reference dose	RfDo	mg/kg-day	chemical-specific	--
Oral slope factor	SFo	(mg/kg-day) ⁻¹	chemical-specific	--
Ingestion slope factor - radiological effects	SFO _{RAD}	risk/pCi	chemical-specific	--
Risk-Based PPRG				
Residential Groundwater Exposure Scenario-Noncarcinogenic Effects				
PPRG (mg/L) = (THI x BW x AT_NC x 365d/yr)/(EF x ED x IRw x 1/RfDo)				
Residential Groundwater Exposure Scenario-Carcinogenic Effects				
PPRG (mg/L) = (TR x BW x AT_C x 365d/yr)/(EF x ED x IRw x SFo)				
Residential Groundwater Exposure Scenario-Radiological Effects				
PPRG (pCi/L) = TR/(EF x ED x IRw x SFO _{RAD})				

Notes:

-- Not applicable

Sources:

EPA, 1991a = U.S. Environmental Protection Agency. 1991. Risk Assessment Guidance for Superfund, Volume I, Human Health Evaluation Manual, Part B. Development of Risk-Based Preliminary Remediation Goals. Interim. Office of Emergency and Remedial Response, Washington, D.C.
 Publication 9285.7-01B. December.
 EPA, 1991b = U.S. Environmental Protection Agency. 1991. Human Health Evaluation Manual, Supplemental Guidance: Standard Default Exposure Factors. Office of Solid Waste and Emergency Response, Washington, D.C. OSWER Directive 9285.6-03. March 25.

Table 2 - Office Worker Exposure Scenario RFETS PPRGs

The Office Worker Surface Soil Exposure Scenario consists of the following pathways: incidental ingestion of surface soil and indoor inhalation of surface soil particulates for an adult office worker at the site for 25 years. This scenario includes only pathways that were evaluated in the Rocky Flats Cleanup Agreement (RFCA) to derive action levels			
Exposure Parameter	Variable	Unit	Value
General Assumptions			
Target hazard index	THI	--	1
Target excess lifetime cancer risk	TR	--	1E-06
Adult body weight	BW	kg	70
Office Worker Exposure Scenario Assumptions			
Averaging time - noncarcinogenic	AT_NC	yr	25
Averaging time - carcinogenic	AT_C	yr	70
Exposure frequency	EF	day/yr	250
Exposure duration	ED	yr	25
Daily indoor inhalation rate	IRa	m ³ /day	8.8
Particulate Emission Factor	PEF	m ³ /kg	1.32E+09
Soil ingestion rate	IRs	mg/day	50
Gamma shielding factor	Se	--	0.2
Gamma exposure factor (annual) = (EF / 365 day/yr) [a]	Te_A	--	6.85E-01
Gamma exposure factor (daily) = (8 hr/day / 24 hr/day)	Te_D	--	3.33E-01
Toxicity Values			
Oral reference dose	RfDo	mg/kg-day	chemical-specific
Oral slope factor	SfO	(mg/kg-day) ⁻¹	chemical-specific
Ingestion slope factor - radiological effects	SfO _{RAO}	risk/pCi	chemical-specific
Inhalation reference dose	RfDi	mg/kg-day	chemical-specific
Inhalation slope factor	SfI	(mg/kg-day) ⁻¹	chemical-specific
Inhalation slope factor - radiological effects	SfI _{RAD}	risk/pCi	chemical-specific
External exposure slope factor	SFe	(risk/yr per pCi/g)	chemical-specific
Risk-Based PPRG			
Office Worker Surface Soil Exposure Scenario-Noncarcinogenic Effects			
PPRG (mg/kg) = (THI x BW x AT_NC x 365d/yr)/(EF x ED x ((1/PEF x IRa x 1/RfDi) + (1E-06 kg/mg x IRs x 1/RfDo)))			
Office Worker Surface Soil Exposure Scenario-Carcinogenic Effects			
PPRG (mg/kg) = (TR x BW x AT_C x 365d/yr)/(EF x ED x ((1/PEF x IRa x SfI) + (1E-06 kg/mg x IRs x SfO)))			
Office Worker Surface Soil Exposure Scenario-Radiological Effects			
PPRG (pCi/g) = TR / [ED x ((EF x 1/PEF x 10 ³ g/kg x IRa x SfI _{RAD}) + (EF x 1E-03 g/mg x IRs x SfO _{RAO}) + (SFe x (1-Se) x (Te_A x Te_D))]			

Notes:

-- Not applicable

[a] Extrapolated to calculate annual exposure

Sources:

EPA, 1991a = U.S. Environmental Protection Agency, 1991. Risk Assessment Guidance for Superfund, Volume I, Human Health Evaluation Manual, Part B, Development of Risk-Based Preliminary Remediation Goals. Interim. Office of Emergency and Remedial Response, Washington, D.C. Publication 9285.7-01B, December.

EPA, 1991b = U.S. Environmental Protection Agency, 1991. Human Health Evaluation Manual, Supplemental Guidance: Standard Default Exposure Factors. Office of Solid Waste and Emergency Response, Washington, D.C. OSWER Directive 9285.6-03, March 25.

EPA, 1996 = U.S. Environmental Protection Agency, 1996. Soil Screening Guidance: Technical Background Document. Office of Emergency and Remedial Response, Washington, D.C. EPA/540/R-95/128, May.

ICRP 66, 1993 = International Commission on Radiological Protection (ICRP), 1993. Human Respiratory Tract Model for Radiological Protection. ICRP Publication 66.

Table 3 - Open Space Surface Water Exposure Scenario RFETS PPRGs

The Open Space Surface Water Exposure Scenario consists of the following pathway: incidental ingestion of surface water for an open space visitor who recreates at the site for 30 years. The open space receptor visits the site 100 times per year. This scenario includes only pathways that were evaluated in the Rocky Flats Cleanup Agreement (RFCA) to derive action levels.

Exposure Parameter	Variable	Unit	Value	Source
General Assumptions				
Target hazard index	THI	--	1	EPA, 1991a
Target excess lifetime cancer risk	TR	--	1E-06	EPA, 1991a
Adult body weight	BW	kg	70	EPA, 1991b
Open Space Exposure Scenario Assumptions				
Averaging time - noncarcinogenic	AT_NC	yr	30	EPA, 1991b
Averaging time - carcinogenic	AT_C	yr	70	EPA, 1991b
Contact rate	CR	L/hr	0.05	(1)
Exposure time	ET	hr/day	1	(2)
Exposure frequency	EF	day/yr	100	JeffCo, 1996
Exposure duration	ED	yr	30	EPA, 1991b
Toxicity Values				
Oral reference dose	RfDo	mg/kg-day	chemical-specific	--
Oral slope factor	SfO	(mg/kg-day) ⁻¹	chemical-specific	--
Ingestion slope factor - radiological effects	SFO _{RAD}	risk/pCi	chemical-specific	--
Risk-Based PPRG				
Open Space Surface Water Exposure Scenario-Noncarcinogenic				
$PPRG(mg/L) = \{THI \times BW \times AT_NC \times 365 \text{ d/yr}\} / \{CR \times ET \times EF \times ED \times 1/RfDo\}$				
Open Space Surface Water Exposure Scenario-Carcinogenic				
$PPRG(mg/L) = \{TR \times BW \times AT_C \times 365 \text{ d/yr}\} / \{CR \times ET \times EF \times ED \times SfO\}$				
Open Space Surface Water Exposure Scenario-Radiological Effects				
$PPRG(pCi/L) = \{TR\} / \{CR \times ET \times EF \times ED \times SFO_{RAD}\}$				

Sources:

- (1) Ingestion Rate based upon open-space recreational user wading at Denver's Lowry Landfill Superfund Site (50 mL/day, RME; 25 mL/day, CT). For comparison, a single value of 35 mL/day is specified for DOE's Fernald Site (wading in shallow Paddy's Run).
 - (2) Exposure Time based upon DOE's Fernald Site recreational use (0.5 hr/day, CT) and on the Clear Creek/Central City Superfund Site recreational user (1.0 hr/day, RME, assuming that wading time would be the same as swimming time)
- EPA, 1991a = U.S. Environmental Protection Agency, 1991. Risk Assessment Guidance for Superfund, Volume I, Human Health Evaluation Manual, Part B, Development of Risk-Based Preliminary Remediation Goals, Interim. Office of Emergency and Remedial Response, Washington, D.C. Publication 9285.7-01B, December.
- EPA, 1991b = U.S. Environmental Protection Agency, 1991. Human Health Evaluation Manual, Supplemental Guidance: Standard Default Exposure Factors, Office of Solid Waste and Emergency Response, Washington, D.C. OSWER Directive 9285.6-03, March 25.
- JeffCo, 1996 = Jefferson County Parks and Open Space Study. Jefferson County, CO, 1996.

Table 4 - Open Space Surface Soil Exposure Scenario RFETS PPRGs

The Open Space Surface Soil Exposure Scenario consists of the following pathways: Inhalation of surface soil particulates and incidental ingestion of surface soil for an open space visitor who recreates at the site for 30 years including six years as a child. The open space receptor visits the site 100 times per year. This scenario includes only pathways that were evaluated in the Rocky Flats Cleanup Agreement (RFCA) to derive action levels.				
Exposure Parameter	Variable	Unit	Value	Source
General Assumptions				
Target hazard index	THI	--	1	EPA, 1991a
Target excess lifetime cancer risk	TR	--	1E-06	EPA, 1991a
Adult body weight	BW	kg	70	EPA, 1991b
Child body weight	BWc	kg	15	EPA, 1991b
Open Space Exposure Scenario Assumptions				
Averaging time - noncarcinogenic	AT_NC	yr	30	EPA, 1991b
Averaging time - carcinogenic	AT_C	yr	70	EPA, 1991b
Exposure time	ET	hr/day	2.5	JeffCo, 1996
Exposure frequency	EF	day/yr	100	JeffCo, 1996
Exposure duration (adult and child, combined)	ED	yr	30	EPA, 1991b
Exposure duration (adult)	EDa	yr	24	EPA, 1991b
Exposure duration (child)	EDc	yr	6	EPA, 1991b
Inhalation rate	IRa_h	m ³ /hr	1.7	EPA, 1997; JeffCo, 1996
Inhalation rate = [(IRa_h x ET)]	IRa	m ³ /day	4.25	Calculated
Particulate Emission Factor	PEF	m ³ /kg	1.32E+09	EPA, 1996
Soil ingestion rate (adult)	IRs_a	mg/day	50	EPA, 1995
Soil ingestion rate (child)	IRs_c	mg/day	100	(1)
Age-adjusted soil ingestion factor = [(IRs_a x EDa) / BW] + [(IRs_c x EDc) / BWc]	IRs	mg-yr/kg-day	57	EPA, 1991a
Gamma shielding factor	IFS_RAD	mg-yr/kg-day	1,800	EPA, 1991a
Gamma exposure factor (annual) = (EF / 365 day/yr) [a]	Se	--	0	EPA, 1991a
Gamma exposure factor (daily) = (ET / 24 hr/day)	Te_A	--	2.74E-01	EPA, 1991a; JeffCo, 1996
Oral reference dose	Te_D	--	1.04E-01	EPA, 1991a; JeffCo, 1996
Toxicity Values				
Oral slope factor	RfDo	mg/kg-day	chemical-specific	--
Ingestion slope factor - radiological effects	SfDo	(mg/kg-day) ⁻¹	chemical-specific	--
Inhalation reference dose	SfDoRad	risk/pCi	chemical-specific	--
Inhalation slope factor	RfDi	mg/kg-day	chemical-specific	--
Inhalation slope factor - radiological effects	SfDi	(mg/kg-day) ⁻¹	chemical-specific	--
External exposure slope factor	SfRad	risk/pCi	chemical-specific	--
Risk-Based PPRG	Sfe	(risk/yr per pCi/g)	chemical-specific	--
Open Space Surface Soil Exposure Scenario-Noncarcinogenic Effects				
PPRG (mg/kg) = (THI x AT_NC x 365 day/yr) / (EF x [(IRa x ED x 1/IRDi) x 1/BW x 1/PEF] + (1/IRDo x 1E-06 kg/mg x IFS))				
Open Space Surface Soil Exposure Scenario-Carcinogenic Effects				
PPRG (mg/kg) = ((TR x AT_C x 365 day/yr) / EF x ((SfI x IRa x ED x 1/BW x 1/PEF) + (1E-06 kg/mg x IFS x SfDo)))				
Open Space Surface Soil Exposure Scenario-Radiological Effects				
PPRG (pCi/g) = TR / ((ED x EF x IRa x SFI _{Rad} x 10 ³ g/kg x 1/PEF) + (EF x SFI _{Rad} x 1E-03 g/mg x IFS _{Rad}) + (ED x SFe x (1-Se) x (Te_A x Te_D)))				

Notes:

[a] Extrapolated to calculate annual exposure.

Sources:

- (1) Based on the assumption that outdoor ingestion of soil accounts for one-half the daily residential intake (200 mg/day for children, as cited in EPA (1991b)). Preliminary Remediation Goals Interim. Office of Emergency and Remedial Response, Washington, D.C. Publication 9285.7-01B, December.
- EPA, 1991a = U.S. Environmental Protection Agency, 1991. Risk Assessment Guidance for Superfund, Volume I, Human Health Evaluation Manual, Part B, Development of Risk-Based Emergency Response, Washington, D.C. OSWER Directive 9285.8-03, March 25.
- EPA, 1995 = U.S. Environmental Protection Agency, Baseline Human Health Risk Assessment for the California Gulch Superfund Site, Part C, Screening-level Soil Concentrations for Workers and Recreational Site Visitors Exposed to Lead and Arsenic, February, Prepared for EPA Region VIII, Denver, CO by Roy F. Weston, Inc.
- EPA, 1996 = U.S. Environmental Protection Agency, 1996. Soil Screening Guidance: Technical Background Document, Office of Emergency and Remedial Response, Washington, D.C.
- JeffCo, 1996 = Jefferson County Parks and Open Space Study, Jefferson County, CO, 1996.

Table 5 - Toxicity Values used for the RFETS PPRGs [a]

Target Analyte List Chemical	CAS Number	Oral RfD (mg/kg-day)	Oral/Ingestion Slope Factor (mg/kg-day) ⁻¹	Inhal RfC (mg/m ³)	Inhalation Unit Risk (m ⁻³ /μg)	Inhalation RfD (mg/kg-day)	Inhalation Slope Factor (mg/kg-day) ⁻¹	External Slope Fac (risk/yr per
Acenaphthene	(V) 83-32-9	6.00E-02						
Acenaphthylene	(V) 208-96-8							
Acetone	(V) 67-64-1	1.00E-01						
Aldrin	309-00-2	3.00E-05	1.70E+01		4.90E-03	1.00E-03	1.70E+01	b
Aluminum	7429-90-5	1.00E+00						
Anthracene	(V) 120-12-7	3.00E-01						
Antimony	7440-36-0	4.00E-04						
Aroclor 1016	12674-11-2	7.00E-05	2.00E+00	c,q	5.70E-04	c,q	2.00E+00	c,q
Aroclor 1221	11104-28-2		2.00E+00	c,q	5.70E-04	c,q	2.00E+00	c,q
Aroclor 1232	11141-16-5		2.00E+00	c,q	5.70E-04	c,q	2.00E+00	c,q
Aroclor 1242	53469-21-9		2.00E+00	c,q	5.70E-04	c,q	2.00E+00	c,q
Aroclor 1248	12672-29-6		2.00E+00	c,q	5.70E-04	c,q	2.00E+00	c,q
Aroclor 1254	11097-69-1	2.00E-05	2.00E+00	c,q	5.70E-04	c,q	2.00E+00	c,q
Aroclor 1260	11098-82-5		2.00E+00	c,q	5.70E-04	c,q	2.00E+00	c,q
Arsenic	7440-38-2	3.00E-04	1.50E+00	i	4.30E-03		1.51E+01	
Barium	7440-39-3	7.00E-02				1.43E-04	b	
Benzene	(V) 71-43-2		2.90E-02		8.30E-06		2.90E-02	
alpha-BHC	319-84-6		6.30E+00		1.80E-03		6.30E+00	
beta-BHC	319-85-7		1.80E+00		5.30E-04		1.80E+00	
delta-BHC	319-86-8							
gamma-BHC (Lindane)	58-89-9	3.00E-04	1.30E+00	b				
Benzo(a)anthracene	56-55-3		7.30E-01	k				
Benzo(a)pyrene	50-32-8		7.30E+00					
Benzo(b)fluoranthene	205-99-2		7.30E-01	k				
Benzo(g,h,i)perylene	191-24-2							
Benzo(k)fluoranthene	207-08-9		7.30E-02	k				
Benzoic Acid	65-85-0	4.00E+00						
Benzyl Alcohol	100-51-6	3.00E-01		b				
Beryllium	7440-41-7	2.00E-03	4.30E+00	w	2.40E-03	5.71E-06	8.40E+00	b
bis(2-chloroethoxy)methane	(V) 111-91-1		1.10E+00					
bis(2-chloroethyl)ether	(V) 111-44-4		7.00E-02	b,u	3.30E-04		1.10E+00	b
bis(2-chloroisopropyl)ether	(V) 39638-32-9	4.00E-02	1.40E-02		1.00E-05	b,u	3.50E-02	b,u
bis(2-ethylhexyl)phthalate	(V) 117-81-7	2.00E-02	6.20E-02				1.40E-02	y
Bromodichloromethane	(V) 75-27-4	2.00E-02	7.9E-03		1.10E-06		3.90E-03	
Bromoflorm	(V) 75-25-2	2.00E-02						
Bromomethane	(V) 74-83-9	1.40E-03				1.43E-03		
4-Bromophenyl phenyl ether	101-55-3							
2-Butanone	(V) 78-93-3	6.00E-01				2.86E-01		
Butylbenzylphthalate	85-68-7	2.00E-01						
Cadmium (water)	7440-43-9	5.00E-04		r	1.80E-03	5.71E-05	6.30E+00	
Cadmium (food)	7440-43-9	1.00E-03		r	1.80E-03	5.71E-05	6.30E+00	
Calcium	7440-70-2							
Carbon disulfide	(V) 75-15-0	1.00E-01				2.00E-01		
Carbon tetrachloride	(V) 56-23-5	7.00E-04	1.30E-01		1.50E-05	5.71E-04	5.25E-02	
Cesium	7440-46-2							
alpha-Chlordane	5103-71-9	5.00E-04	3.50E-01	d	1.00E-04	d	3.50E-01	d
beta-Chlordane	5103-74-2	5.00E-04	3.50E-01	d	1.00E-04	d	3.50E-01	d
gamma-Chlordane	12189-03-6	5.00E-04	3.50E-01		1.00E-04		3.50E-01	
4-Chloroaniline	106-47-8	4.00E-03						
Chlorobenzene	(V) 108-90-7	2.00E-02				5.71E-03	b	
Chloroethane	(V) 75-00-3	4.00E-01		y		2.86E+00		
Chloroform	(V) 67-66-3	1.00E-02	1.30E-02	d	2.30E-05		8.05E-02	
4-Chloro-3-methylphenol	59-50-7				1.80E-06	b	6.30E-03	b
2-Chloronaphthalene	(V) 91-58-7	8.00E-02						
2-Chlorophenol	(V) 95-57-8	5.00E-03						
4-Chlorophenyl phenyl ether	7005-72-3							
Chromium III	16065-83-1	1.00E+00				5.71E-07	w,y	
Chromium VI	18540-29-9	5.00E-03			1.20E-02		4.20E+01	

Table 5 - Toxicity Values used for the RFETS PPRGs [a]

Target Analyte List Chemical	CAS Number	Oral RfD (mg/kg-day)	Oral Ingestion Slope Factor (mg/kg-day) ⁻¹	Inhal RIC (mg/m ³)	Inhalation Unit Risk (m ⁻³ /μg)	Inhalation RID (mg/kg-day)	Inhalation Slope Factor (mg/kg-day) ⁻¹	External Slope Fac (risk/yr per
Chrysene	218-01-9							
Cobalt	7440-48-4	6.00E-02	7.30E-03				3.10E-03	Y
Copper	7440-50-8	3.70E-02						
Cyanide	57-12-5	2.00E-02						
4,4-DDO	72-54-8							
4,4-DDO	72-55-9		2.40E-01					
4,4-DDT	50-29-3	5.00E-04	3.40E-01					
Dibenz(a,h)anthracene	53-70-3		7.30E+00		9.70E-05		3.40E-01	
Dibenzofuran	132-64-9	4.00E-03					3.10E+00	Y
Dibromochloromethane	124-48-1	2.00E-02						
Di-n-butylphthalate	84-74-2	1.00E-01						
1,2-Dichlorobenzene	95-50-1	9.00E-02		2.00E-01		4.00E-02		
1,3-Dichlorobenzene	541-73-1							
1,4-Dichlorobenzene	106-46-7							
3,3-Dichlorobenzidine	91-94-1			8.00E-01		2.30E-01		
1,1-Dichloroethane	75-34-3	1.00E-01	4.50E-01					
1,2-Dichloroethane	107-06-2	3.00E-02		5.00E-01		1.43E-01		
1,1-Dichloroethene	75-35-4	9.00E-03	9.10E-02		2.60E-05	1.40E-03	9.10E-02	
1,2-Dichloroethene (total)	540-59-0	9.00E-03	6.00E-01		5.00E-05		1.75E-01	
2,4-Dichlorophenol	120-83-2	3.00E-03						
1,2-Dichloropropane	78-87-5		6.80E-02	4.00E-03		1.14E-03		
cis-1,3-Dichloropropene	10061-01-5	3.00E-04	1.80E-01	2.00E-02	3.70E-05	5.71E-03	1.30E-01	b,e
trans-1,3-Dichloropropene	10061-02-6	3.00E-04	1.80E-01	2.00E-02	3.70E-05	5.71E-03	1.30E-01	b,e
Dieldrin	60-57-1	5.00E-05	1.60E+01		4.60E-03		1.60E+01	
Diethylphthalate	84-86-2	8.00E-01						
2,4-Dimethylphenol	105-67-8	2.00E-02						
Dimethylphthalate	131-11-3	1.00E-01						
4,6-Dinitro-2-methylphenol	534-52-1	1.00E-04						
2,4-Dinitrophenol	51-28-5	2.00E-03						
2,4-Dinitrotoluene	121-14-2	2.00E-03						
2,6-Dinitrotoluene	606-20-2	1.00E-03	6.80E-01					
Di-n-octylphthalate	117-84-0	2.00E-02						
Endosulfan I	959-98-8	6.00E-03						
Endosulfan II	33213-65-9	6.00E-03						
Endosulfan sulfate	1031-07-8	6.00E-03						
Endosulfan (technical)	115-29-7	6.00E-03						
Endrin kelone	53494-70-5							
Endrin (technical)	72-20-8	3.00E-04						
Ethylbenzene	100-41-4	1.00E-01						
Fluoranthene	206-44-0	4.00E-02	1.00E+00		2.86E-01			
Fluorene	86-73-7	4.00E-02						
Heptachlor	76-44-8	5.00E-04						
Heptachlor epoxide	1024-57-3	1.30E-05	4.50E+00		1.30E-03		4.50E+00	
Hexachlorobenzene	118-74-1	8.00E-04	9.10E+00		2.60E-03		9.10E+00	
Hexachlorobutadiene	87-68-3	2.00E-04	1.60E+00		4.60E-04		1.60E+00	
Hexachlorocyclopentadiene	77-47-4	7.00E-03	7.80E-02		2.20E-05		7.70E-02	
Hexachloroethane	67-72-1	1.00E-03	1.40E-02	7.00E-05	2.00E-05		1.40E-02	
2-Hexanone	591-78-6				4.00E-06			
Indeno(1,2,3-cd)pyrene	193-39-5							
Iron	7439-89-6	3.00E-01	7.30E-01					
Isophorone	78-59-1	2.00E-01					3.10E-01	Y
Lead	7439-92-1		9.50E-04					
Lithium	7439-93-2	2.00E-02						
Magnesium	7439-95-4							
Manganese	7439-96-5	4.70E-02						
Mercury	7439-97-6	3.00E-04		5.00E-05				
Methoxychlor	72-43-5	5.00E-03		3.00E-04		1.43E-05	8.60E-05	I
Methylene chloride	75-09-2	6.00E-02						
2-Methylnaphthalene	91-57-6	4.00E-02	7.50E-03	3.00E+00	4.70E-07	8.57E-01	1.65E-03	

Table 5 - Toxicity Values used for the RFETS PPRGs [a]

Target Analyte List Chemical	CAS Number	Oral RfD (mg/kg-day)	Oral/Ingestion Slope Factor (mg/kg-day) ⁻¹	Inhal RIC (mg/m ³)	Inhalation Unit Risk (m ³ /μg)	Inhalation RfD (mg/kg-day)	Inhalation Slope Factor (mg/kg-day) ⁻¹	External Slope Fac (risk/yr per
4-Methyl-2-pentanone	108-10-1	8.00E-02 b		8.00E-02 b		2.29E-02		
2-Methylphenol	95-48-7	5.00E-02						
4-Methylphenol	106-44-5	5.00E-03 b						
Molybdenum	7439-98-7	5.00E-03						
Naphthalene	91-20-3	4.00E-02 w,y						
Nickel	7440-02-0	2.00E-02						
2-Nitroaniline	88-74-4	6.00E-05 w,y		2.00E-04		5.71E-05		
3-Nitroaniline	99-09-2							
4-Nitroaniline	100-01-6							
Nitrobenzene	98-95-3	5.00E-04		2.00E-03 b		5.70E-04 j		
2-Nitrophenol	88-75-5							
n-Nitrosodiphenylamine	100-02-7	8.00E-03 y						
n-Nitrosodipropylamine	86-30-6		4.90E-03					
Pentachlorophenol	621-84-7		7.00E-02					
Phenanthrene	87-86-5	3.00E-02	1.20E-01					
Phenol	85-01-8							
Potassium	108-96-2	6.00E-01						
Pyrene	7440-09-7							
Selenium	129-00-0	3.00E-02						
Silver	7782-49-2	5.00E-03						
Sodium	7440-22-4	5.00E-03						
Strontium	7440-23-5							
Styrene	7440-24-6	6.00E-01		1.00E+00		2.86E-01	2.00E-01 b	
1,1,2,2-Tetrachloroethane	100-42-5	2.00E-01			5.80E-05		2.03E-03 i	
Tetrachloroethene	79-34-5				5.80E-07 i			
Thallium	127-18-4	1.00E-02	5.20E-02 i					
Tin	7440-28-0							
Toluene	7440-31-5	6.00E-01 b		4.00E-01		1.14E-01	1.10E+00	
Toxaphene	8001-35-2	2.00E-01	1.10E+00		3.20E-04	5.71E-02 j		
1,2,4-Trichlorobenzene	120-82-1	1.00E-02		2.00E-01 b		2.86E-01 w,y		
1,1,1-Trichloroethane	71-55-6	2.00E-02 y						
1,1,2-Trichloroethane	79-00-5	4.00E-03	5.70E-02		1.60E-05		5.60E-02	
Trichloroethene	79-01-6	6.00E-03 y	1.10E-02 w		1.70E-06 i		6.00E-03 i	
2,4,5-Trichlorophenol	95-95-4	1.00E-01			3.10E-06		1.00E-02	
2,4,6-Trichlorophenol	88-06-2		1.10E-02					
Vanadium	7440-62-2	7.00E-03 b						
Vinyl acetate	108-05-4	1.00E+00 b		2.00E-01		5.71E-02		
Vinyl chloride	75-01-4							
Xylene (total)	1330-20-7	2.00E+00	1.90E+00 b		8.40E-05 b		3.00E-01 b	
Zinc	7440-66-6	3.00E-01						
Nitrate	14797-55-8	1.60E+00						
Nitrite	14797-55-0	1.00E-01						
Sulfide	18496-25-8							
Ammonium (as Ammonia)	7664-41-7	9.70E-01 x		1.00E-01		2.86E-02		
Bicarbonate	71-52-3							
Bromide	24959-67-9							
Carbonate	3812-32-6							
Chloride	16887-00-6							
Fluoride (as Fluorine)	7782-41-4	6.00E-02						
Orthophosphate	14265-44-2							
Silica (as Si and SiO ₂)	7631-86-9							
Sulfate	14808-79-8							
Am-241	14596-10-2		(Risk/pCi)				(Risk/pCi)	
Cs-137-D	10045-97-3(*D)		3.28E-10 b				3.85E-08 b	4.59E-09 b
Pu-239	15117-48-3		3.16E-11 b				1.91E-11 b	2.09E-06 b
			3.16E-10 b				2.78E-08 b	1.26E-11 b

Table 5 - Toxicity Values used for the RFETS PPRGs [a]

Target Analyte List Chemical	CAS Number	Oral RfD (mg/kg-day)	Oral Ingestion Slope Factor (mg/kg-day) ⁻¹	Inhal RfC (mg/m ³)	Inhalation Unit Risk (m ³ /ug)	Inhalation RfD (mg/kg-day)	Inhalation Slope Factor (mg/kg-day) ⁻¹	External Slope Fac (risk/yr per (ug/kg-day)) ⁻¹
Pu-240	14119-33-6		3.15E-10				2.78E-08	1.87E-11
Ra-226-D	13982-83-3(+D)		2.96E-10				2.75E-09	6.74E-06
Ra-228-D	15262-20-1(+D)		2.48E-10				9.94E-10	3.28E-06
Sr-89	14158-27-1		1.03E-11				3.88E-12	5.38E-10
Sr-90-D	10098-97-2(+D)		5.59E-11				6.93E-11	0.00E+00
Tritium	10028-17-8		7.15E-14				9.59E-14	0.00E+00
U-233	13968-55-3		4.48E-11				1.41E-08	3.52E-11
U-234	13966-29-5		4.44E-11				1.40E-08	2.14E-11
U-235-D	15117-96-1(+D)		4.70E-11				1.30E-08	2.65E-07
U-238-D	7440-61-1(+D)		6.20E-11				1.24E-08	5.25E-08

Notes:

- (V) = Chemicals listed are volatile.
a = All toxicity values and notes are from IRIS, 1998 unless otherwise noted. Several inhalation slope factors have been derived by multiplying the inhalation unit risk from IRIS by a conversion factor of 3500: [SFI = (Inh Unit Risk x 70kg x 1,000 ug/mg) / 20 m³/d].
Several inhalation reference doses have been derived by multiplying the inhalation reference concentration by a conversion factor of 0.2857: [RfD] = (RfC x 20 m³/d) / 70 kg
Several oral slope factors have been derived by multiplying the drinking water unit risk by a conversion factor of 35,000: [SfD] = (DW Unit Risk x 70 kg x 1,000 ug/mg) / 2 L
b = Value from HEAST, 1997.
c = Values given are for PCBs.
d = Values given are for chlordane (CAS no. 12789-03-6).
e = Values given are for 1,3-dichloropropene.
f = Value given for arsenic is calculated from an oral unit risk of 5E-05 (L/ug).
j = Values given for chemicals were calculated from HEAST, 1997.
k = Values given for PAHs were found in EPA, 1993.
l = Value given is from an EPA memo from the Office of Research and Development, National Center for Environmental Assessment (NCEA).
o = Value based on the copper drinking water standard of 1.3 mg/L.
q = The upper-bound slope factor for high risk and persistence is recommended by EPA for the oral slope factor of PCB environmental mixtures.
r = Dual oral RfDs available for cadmium. 5E-04 is representative of pathways involving water and 1E-03 is representative of pathways involving food (soil).
s = According to IRIS, 1998, the oral RfD of 0.14 represents total oral intake of manganese. It is recommended that a modifying factor of three be applied (resulting oral RfD = 0.047) if oral RfD is used for assessments involving non-dietary exposures (ingesting soil or drinking water).
u = Values given for 70 percent bis(2-chloro-1-methyl ethyl) ether and 30 percent bis(2-chloroisopropyl) ether.
w = Value given has been withdrawn by EPA; greater uncertainty is associated with this toxicity value than values listed in IRIS and HEAST.
x = Ammonia oral RfD specifically related to organoleptic threshold.
y = NCEA (as referenced in EPA, 1997).
z = Values given for Endosulfan (technical)

References:

- EPA, 1993 = U.S. Environmental Protection Agency. 1993. Research and Development-Provisional Guidance for Quantitative Risk Assessment of Polycyclic Aromatic Hydrocarbons. Prepared for the Office of Health and Environmental Assessment by the Environmental Criteria and Assessment Office, Office of Health and Environmental Assessment, Cincinnati, OH. Final Draft. ECAO-CIN-842. March.
EPA, 1997 = U.S. Environmental Protection Agency. 1997. Region III Risk-Based Concentration Table. Philadelphia, PA. October 22.
HEAST, 1997 = U.S. Environmental Protection Agency. 1997. Health Effects Assessment Summary Tables, FY-1997 Annual. Office of Solid Waste and Emergency Response, Washington, D.C. EPA/540/R-97/036. July.
IRIS, 1998 = U.S. Environmental Protection Agency. 1998. Integrated Risk Information System. On-line database. Office of Research and Development, Cincinnati, OH.

Table 6 - Programmatic Preliminary Risk-Based Remediation Goals For RFETS

Target Analyte List Chemical	Residential Groundwater (mg/L or pCi/L)	Office Worker Soil (mg/kg or pCi/g)	Open Space Surface Water (mg/L or pCi/L)	Open Space Soil (mg/kg or pCi/g)
Acenaphthene	(V) 2.19E+00	1.23E+05	3.07E+02	1.15E+05
Acenaphthylene	(V)	-	-	-
Acetone	(V)	-	-	-
Aldrin	3.65E+00	2.04E+05	5.11E+02	1.92E+05
Aluminum	5.01E-06	3.37E-01	7.01E-04	2.64E-01
Anthracene	3.65E+01	>1E+06	5.11E+03	>1E+06
Antimony	(V) 1.10E+01	6.13E+05	1.53E+03	5.76E+05
Aroclor 1016	1.46E-02	8.18E+02	2.04E+00	7.68E+02
Aroclor 1221	4.26E-05	2.86E+00	5.96E-03	2.24E+00
Aroclor 1232	4.26E-05	2.86E+00	5.96E-03	2.24E+00
Aroclor 1242	4.26E-05	2.86E+00	5.96E-03	2.24E+00
Aroclor 1248	4.26E-05	2.86E+00	5.96E-03	2.24E+00
Aroclor 1254	4.26E-05	2.86E+00	5.96E-03	2.24E+00
Aroclor 1260	4.26E-05	2.86E+00	5.96E-03	2.24E+00
Arsenic	5.68E-05	3.81E+00	7.95E-03	2.99E+00
Barium	2.56E+00	1.34E+05	3.58E+02	1.33E+05
Benzene	(V) 2.94E-03	1.97E+02	4.11E-01	1.55E+02
alpha-BHC	1.35E-05	9.08E-01	1.89E-03	7.11E-01
beta-BHC	4.73E-05	3.18E+00	6.62E-03	2.49E+00
delta-BHC	-	-	-	-
gamma-BHC (Lindane)	6.55E-05	4.40E+00	9.17E-03	3.45E+00
Benzo(a)anthracene	1.17E-04	7.84E+00	1.63E-02	6.14E+00
Benzo(a)pyrene	1.17E-05	7.84E-01	1.63E-03	6.14E-01
Benzo(b)fluoranthene	1.17E-04	7.84E+00	1.63E-02	6.14E+00
Benzo(g,h,i)perylene	-	-	-	-
Benzo(k)fluoranthene	1.17E-03	7.84E+01	1.63E-01	6.14E+01
Benzoic Acid	1.46E+02	>1E+06	2.04E+04	>1E+06
Benzyl Alcohol	1.10E+01	6.13E+05	1.53E+03	5.76E+05
Beryllium	1.98E-05	1.33E+00	2.77E-03	1.04E+00
bis(2-chloroethoxy)methane	(V)	-	-	-
bis(2-chloroethyl)ether	(V)	-	-	-
bis(2-chloroisopropyl)ether	(V)	5.20E+00	1.08E-02	4.07E+00
bis(2-ethylhexyl)phthalate	(V)	8.18E+01	1.70E-01	6.40E+01
Bromodichloromethane	(V)	4.09E+02	8.52E-01	3.20E+02
		9.23E+01	1.92E-01	7.23E+01

Table 6 - Programmatic Preliminary Risk-Based Remediation Goals For RFETS

Target Analyte List Chemical	Residential Groundwater (mg/L or pCi/L)	Office Worker Soil (mg/kg or pCi/g)	Open Space Surface Water (mg/L or pCi/L)	Open Space Soil (mg/kg or pCi/g)
Bromoform	(V)			
Bromomethane	1.08E-02	7.24E+02	1.51E+00	5.67E+02
4-Bromophenyl phenyl ether	5.11E-02	2.86E+03	7.15E+00	2.69E+03
2-Butanone	-	-	-	-
Butylbenzylphthalate	2.19E+01	>1E+06	3.07E+03	>1E+06
Cadmium (water)	7.30E+00	4.09E+05	1.02E+03	3.84E+05
Cadmium (food)	1.83E-02	NA	2.56E+00	NA
Calcium	NA	2.04E+03	5.11E+00	1.92E+03
Carbon disulfide	-	-	-	-
Carbon tetrachloride	3.65E+00	2.04E+05	5.11E+02	1.92E+05
Cesium	6.55E-04	4.40E+01	9.17E-02	3.45E+01
alpha-Chlordane	-	-	-	-
beta-Chlordane	2.43E-04	1.63E+01	3.41E-02	1.28E+01
gamma-Chlordane	2.43E-04	1.63E+01	3.41E-02	1.28E+01
4-Chloroaniline	2.43E-04	1.63E+01	3.41E-02	1.28E+01
Chlorobenzene	1.46E-01	8.18E+03	2.04E+01	7.68E+03
Chloroethane	7.30E-01	4.09E+04	1.02E+02	3.84E+04
Chloroform	2.94E-02	1.97E+03	4.11E+00	1.55E+03
Chloromethane	1.40E-02	9.38E+02	1.95E+00	7.35E+02
4-Chloro-3-methylphenol	6.55E-03	4.40E+02	9.17E-01	3.45E+02
2-Chloronaphthalene	-	-	-	-
2-Chlorophenol	2.92E+00	1.64E+05	4.09E+02	1.54E+05
4-Chlorophenyl phenyl ether	1.83E-01	1.02E+04	2.56E+01	9.61E+03
Chromium III	-	-	-	-
Chromium VI	3.65E+01	8.72E+03	5.11E+03	4.43E+04
Chrysene	1.83E-01	1.02E+03	2.56E+01	4.41E+03
Cobalt	1.17E-02	7.84E+02	1.63E+00	6.14E+02
Copper	2.19E+00	1.23E+05	3.07E+02	1.15E+05
Cyanide	1.35E+00	7.56E+04	1.89E+02	7.11E+04
4,4-DDD	7.30E-01	4.09E+04	1.02E+02	3.84E+04
4,4-DDE	3.55E-04	2.38E+01	4.97E-02	1.87E+01
4,4-DDT	2.50E-04	1.68E+01	3.51E-02	1.32E+01
Dibenz(a,h)anthracene	2.50E-04	1.68E+01	3.51E-02	1.32E+01
Dibenzofuran	1.17E-05	7.84E-01	1.63E-03	6.14E-01
Dibromochloromethane	1.46E-01	8.18E+03	2.04E+01	7.68E+03
	1.01E-03	6.81E+01	1.42E-01	5.34E+01

Table 6 - Programmatic Preliminary Risk-Based Remediation Goals For RFETS

Target Analyte List Chemical	Residential Groundwater (mg/L or pCi/L)	Office Worker Soil (mg/kg or pCi/g)	Open Space Surface Water (mg/L or pCi/L)	Open Space Soil (mg/kg or pCi/g)
Di-n-butylphthalate	3.65E+00	2.04E+05	5.11E+02	1.92E+05
1,2-Dichlorobenzene	3.29E+00	1.84E+05	4.60E+02	1.73E+05
1,3-Dichlorobenzene	-	-	-	-
1,4-Dichlorobenzene	3.55E-03	2.38E+02	4.97E-01	1.87E+02
3,3-Dichlorobenzidine	1.89E-04	1.27E+01	2.65E-02	9.96E+00
1,1-Dichloroethane	3.65E+00	2.04E+05	5.11E+02	1.92E+05
1,2-Dichloroethane	9.36E-04	6.29E+01	1.31E-01	4.93E+01
1,1-Dichloroethene	1.42E-04	9.54E+00	1.99E-02	7.47E+00
1,2-Dichloroethene (total)	3.29E-01	1.84E+04	4.60E+01	1.73E+04
2,4-Dichlorophenol	1.10E-01	6.13E+03	1.53E+01	5.76E+03
1,2-Dichloropropane	1.25E-03	8.42E+01	1.75E-01	6.59E+01
cis-1,3-Dichloropropene	4.73E-04	3.18E+01	6.62E-02	2.49E+01
trans-1,3-Dichloropropene	4.73E-04	3.18E+01	6.62E-02	2.49E+01
Dieldrin	5.32E-06	3.58E-01	7.45E-04	2.80E-01
Diethylphthalate	2.92E+01	>1E+06	4.09E+03	>1E+06
2,4-Dimethylphenol	7.30E-01	4.09E+04	1.02E+02	3.84E+04
Dimethylphthalate	3.65E+02	>1E+06	5.11E+04	>1E+06
4,6-Dinitro-2-methylphenol	3.65E-03	2.04E+02	5.11E-01	1.92E+02
2,4-Dinitrophenol	7.30E-02	4.09E+03	1.02E+01	3.84E+03
2,4-Dinitrotoluene	1.25E-04	8.42E+00	1.75E-02	6.59E+00
2,6-Dinitrotoluene	1.25E-04	8.42E+00	1.75E-02	6.59E+00
Di-n-octylphthalate	7.30E-01	4.09E+04	1.02E+02	3.84E+04
Endosulfan I	2.19E-01	1.23E+04	3.07E+01	1.15E+04
Endosulfan II	2.19E-01	1.23E+04	3.07E+01	1.15E+04
Endosulfan sulfate	2.19E-01	1.23E+04	3.07E+01	1.15E+04
Endosulfan (technical)	2.19E-01	1.23E+04	3.07E+01	1.15E+04
Endrin ketone	2.19E-01	1.23E+04	3.07E+01	1.15E+04
Endrin (technical)	-	-	-	-
Ethylbenzene	1.10E-02	6.13E+02	1.53E+00	5.76E+02
Fluoranthene	3.65E+00	2.04E+05	5.11E+02	1.92E+05
Fluorene	1.46E+00	8.18E+04	2.04E+02	7.68E+04
Heptachlor	1.46E+00	8.18E+04	2.04E+02	7.68E+04
Heptachlor epoxide	1.89E-05	1.27E+00	2.65E-03	9.96E-01
Hexachlorobenzene	9.36E-06	6.29E-01	1.31E-03	4.93E-01
Hexachlorobutadiene	5.32E-05	3.58E+00	7.45E-03	2.80E+00
	1.09E-03	7.34E+01	1.53E-01	5.75E+01

Table 6 - Programmatic Preliminary Risk-Based Remediation Goals For RFETS

Target Analyte List Chemical	Residential Groundwater (mg/L or pCi/L)	Office Worker Soil (mg/kg or pCi/g)	Open Space Surface Water (mg/L or pCi/L)	Open Space Soil (mg/kg or pCi/g)
Hexachlorocyclopentadiene	2.56E-01	1.37E+04	3.58E+01	1.33E+04
Hexachloroethane	6.08E-03	4.09E+02	8.52E-01	3.20E+02
2-Hexanone	(V)	-	-	-
Indeno(1,2,3-cd)pyrene	1.17E-04	7.84E+00	1.63E-02	6.14E+00
Iron	1.10E+01	6.13E+05	1.53E+03	5.76E+05
Isophorone	8.96E-02	6.02E+03	1.26E+01	4.72E+03
Lead	-	1.00E+03 [a]	-	-
Lithium	7.30E-01	4.09E+04	1.02E+02	3.84E+04
Magnesium	-	-	-	-
Manganese	1.72E+00	6.68E+04	2.40E+02	8.36E+04
Mercury	1.10E-02	6.13E+02	1.53E+00	5.76E+02
Methoxychlor	1.83E-01	1.02E+04	2.56E+01	9.61E+03
Methylene chloride	1.14E-02	7.63E+02	1.59E+00	5.98E+02
2-Methylnaphthalene	1.46E+00	8.18E+04	2.04E+02	7.68E+04
4-Methyl-2-pentanone	2.92E+00	1.64E+05	4.09E+02	1.54E+05
2-Methylphenol	1.83E+00	1.02E+05	2.56E+02	9.61E+04
4-Methylphenol	1.83E-01	1.02E+04	2.56E+01	9.61E+03
Molybdenum	1.83E-01	1.02E+04	2.56E+01	9.61E+03
Naphthalene	1.46E+00	8.18E+04	2.04E+02	7.68E+04
Nickel	7.30E-01	4.09E+04	1.02E+02	3.84E+04
2-Nitroaniline	2.19E-03	1.23E+02	3.07E-01	1.15E+02
3-Nitroaniline	-	-	-	-
4-Nitroaniline	-	-	-	-
Nitrobenzene	1.83E-02	1.02E+03	2.56E+00	9.61E+02
2-Nitrophenol	-	-	-	-
4-Nitrophenol	2.92E-01	1.64E+04	4.09E+01	1.54E+04
n-Nitrosodiphenylamine	1.74E-02	1.17E+03	2.43E+00	9.15E+02
n-Nitrosodipropylamine	1.22E-05	8.18E-01	1.70E-03	6.40E-01
Pentachlorophenol	7.10E-04	4.77E+01	9.94E-02	3.74E+01
Phenanthrene	-	-	-	-
Phenol	2.19E+01	>1E+06	3.07E+03	>1E+06
Potassium	-	-	-	-
Pyrene	1.10E+00	6.13E+04	1.53E+02	5.76E+04
Selenium	1.83E-01	1.02E+04	2.56E+01	9.61E+03
Silver	1.83E-01	1.02E+04	2.56E+01	9.61E+03

Table 6 - Programmatic Preliminary Risk-Based Remediation Goals For RFETS

Target Analyte List Chemical	Residential Groundwater (mg/L or pCi/L)	Office Worker Soil (mg/kg or pCi/g)	Open Space Surface Water (mg/L or pCi/L)	Open Space Soil (mg/kg or pCi/g)
Sodium	-	-	-	-
Strontium	2.19E+01	>1E+06	3.07E+03	>1E+06
Stryene	7.30E+00	4.09E+05	1.02E+03	3.84E+05
1,1,2,2-Tetrachloroethane	4.26E-04	2.86E+01	5.96E-02	2.24E+01
Tetrachloroethene	1.64E-03	1.10E+02	2.29E-01	8.62E+01
Thallium	-	-	-	-
Tin	2.19E+01	>1E+06	3.07E+03	>1E+06
Toluene	7.30E+00	4.09E+05	1.02E+03	3.84E+05
Toxaphene	7.74E-05	5.20E+00	1.08E-02	4.07E+00
1,2,4-Trichlorobenzene	3.65E-01	2.04E+04	5.11E+01	1.92E+04
1,1,1-Trichloroethane	7.30E-01	4.09E+04	1.02E+02	3.84E+04
1,1,2-Trichloroethane	1.49E-03	1.00E+02	2.09E-01	7.86E+01
Trichloroethene	7.74E-03	5.20E+02	1.08E+00	4.07E+02
2,4,5-Trichlorophenol	3.65E+00	2.04E+05	5.11E+02	1.92E+05
2,4,6-Trichlorophenol	7.74E-03	5.20E+02	1.08E+00	4.07E+02
Vanadium	2.56E-01	1.43E+04	3.58E+01	1.34E+04
Vinyl acetate	3.65E+01	>1E+06	5.11E+03	>1E+06
Vinyl chloride	4.48E-05	3.01E+00	6.28E-03	2.36E+00
Xylene (total)	7.30E+01	>1E+06	1.02E+04	>1E+06
Zinc	1.10E+01	6.13E+05	1.53E+03	5.76E+05
Nitrate	5.84E+01	>1E+06	8.18E+03	>1E+06
Nitrite	3.65E+00	2.04E+05	5.11E+02	1.92E+05
Sulfide	-	-	-	-
Ammonium (as Ammonia)	3.54E+01	>1E+06	4.96E+03	>1E+06
Bicarbonate	-	-	-	-
Bromide	-	-	-	-
Carbonate	-	-	-	-
Chloride	-	-	-	-
Fluoride (as fluoride)	2.19E+00	1.23E+05	3.07E+02	1.15E+05
Orthophosphate	-	-	-	-
Silica (as Si and SiO2)	-	-	-	-
Sulfate	-	-	-	-

Table 6 - Programmatic Preliminary Risk-Based Remediation Goals For RFETS

Target Analyte List Chemical	Residential Groundwater (mg/L or pCi/L)	Office Worker Soil (mg/kg or pCi/g)	Open Space Surface Water (mg/L or pCi/L)	Open Space Soil (mg/kg or pCi/g)
Am-241	1.45E-01	8.00E+00	2.03E+01	1.58E+01
Cs-137+D	1.51E+00	1.05E-01	2.11E+02	5.57E-01
Pu-239	1.51E-01	1.00E+01	2.11E+01	1.75E+01
Pu-240	1.51E-01	1.00E+01	2.12E+01	1.75E+01
Ra-226+D	1.61E-01	3.24E-02	2.25E+01	1.72E-01
Ra-228+D	1.92E-01	6.64E-02	2.69E+01	3.51E-01
Sr-89	4.62E+00	1.76E+02	6.47E+02	4.32E+02
Sr-90+D	8.52E-01	5.72E+01	1.19E+02	9.94E+01
Tritium	6.66E+02	4.47E+04	9.32E+04	7.77E+04
U-233	1.06E+00	6.78E+01	1.49E+02	1.22E+02
U-234	1.07E+00	6.87E+01	1.50E+02	1.23E+02
U-235+D	1.01E+00	8.16E-01	1.42E+02	4.25E+00
U-238+D	7.68E-01	3.85E+00	1.08E+02	1.78E+01

Notes:

(V) = Chemicals listed are volatile.

- = No toxicity value available.

NA = PPRG value is not applicable for this exposure scenario. Dual oral RfDs available for cadmium. The first value (5E-04) is representative of pathways involving water and the second value (1E-03) is representative of pathways involving food (soil).

[a] U.S. Environmental Protection Agency (EPA). 1994. Revised Interim Soil Lead Guidance for CERCLA Sites and RCRA Corrective Action Facilities. Office of Solid Waste and Emergency Response, Washington, D.C. Directive 9355.4-12.

Appendix Q

DATA MANGEMENT

2. Minnesota

10/15/2004

This page intentionally left blank

"Final Rocky Flats Cleanup Agreement"

APPENDIX Q

1.0 DATA MANAGEMENT

A variety of data will be generated during accelerated actions or decommissioning. These data include, but are not limited to:

- Air monitoring data
- Meteorological data
- Ecological data
- Surface water monitoring data (including physical and chemical information)
- Groundwater monitoring data (including analytical and field parameters)
- Well construction data
- Geological information
- Spatial data
- Soils data (analytical and physical data)
- Other characterization data (including HPGe field data)

The specific types of monitoring and the types of data collected are evaluated during project scoping and identified in the required project planning documents. The data collected during closure activities are essential to the successful closure of the RFETS and, therefore, proper data management is a key responsibility of the project.

1.1 Environmental Data Quality

In most instances, analytical data collected in support of a SAP should be evaluated using the guidance described in the Rocky Flats Administrative Procedure 2-G32-ER-ADM-8.02, *Evaluation of ERM Data for Usability in Final Reports*. This procedure establishes the guidelines for evaluating analytical data with respect to the PARCC parameters. A definition of PARCC parameters and the specific applications to the investigation are as follows:

Precision A quantitative measure of data quality that refers to the reproducibility or degree of agreement among replicate or duplicate measurements of a parameter. The closer the numerical values of the measurements are to each other, the lower the relative percent difference and the greater the precision. The relative percent differences (RPD) for results of duplicate and replicate samples will be tabulated according to matrix and analytical suites to

compare for compliance with established precision DQOs. Deficiencies will be noted and qualified, if required.

Accuracy A quantitative measure of data quality that refers to the degree of difference between measured or calculated values and the true value of a parameter. The closer the measurement to the true value, the more accurate the measurement. The actual analytical method and detection limits will be compared with the required analytical method and detection limits for VOCs and radionuclides to assess the DQO compliance for accuracy.

Representativeness A quantitative characteristic of data quality defined by the degree to which the data absolutely and exactly represented the characteristics of a population. Representativeness is accomplished by obtaining an adequate number of samples from appropriate spatial locations within the medium of interest. The actual sample types and quantities will be compared with those stated in the SAP or other related documents and organized by media type and analytical suite. Deviation from the required and actual parameters will be justified, as required.

Completeness A quantitative measure of data quality expressed as the percentage of valid or acceptable data obtained from a measurement system. A completeness goal of 90% has been set for SAPs. Real samples and QC samples will be reviewed for the data usability and achievement of internal DQO usability goals. If sample data cannot be used, the non-compliance will be justified, as required.

Comparability A qualitative measure defined by the confidence with which one data set can be compared to another. Comparability will be attained through consistent use of industry standards (e.g., SW-846) and standard operating procedures, both in the field and in laboratories. Statistical tests may be used for quantitative comparison between sample sets (populations). Deficiencies will be qualified, as required. Quantitative values for PARCC parameters for the project are provide in Table Q-1.

Laboratory validation should be performed on 25% of the characterization data collected. Laboratory verification shall be performed on the remaining 75% of the data. Data usability shall be performed on laboratory validated data according to procedure 2-G32-ER-ADM-08.02, *Evaluation of ERM Data for Usability in Final Reports*.

Table Q-1 PARCC Parameter Summary

PARCC	Radionuclides	Non-Radionuclides
Precision	Duplicate Error Ratio ≤ 1.42	
Accuracy	Detection Limits per method and ASD Laboratory SOW	Comparison of Laboratory Control Sample Results with Real Sample Results
Representativeness	Based on SOPs and SAP	Based on SOPs and SAP
Comparability	Based on SOPs and SAP	Based on SOPs and SAP
Completeness	90% Useable	90% Useable

Data validation will be performed according to ASD procedures, but will be done after the data is used for its intended purpose. Analytical laboratories supporting this task have all passed regular laboratories audits by ASD.

The ASD provides analytical laboratory validation/verification for all soil, water, and air data according to *General Guidelines for Data Verification and Validation (DA-GRO1-v1)*, December 3, 1997. ASD also provides results for a majority of analysis via an EDD, which includes information on the results of the data validation/verification process. The EDDs are designed for import into site environmental data systems to support further analysis and interpretation of the data.

Projects collecting and reporting non-laboratory data, such as field parameters, geologic logging, ecological sampling, etc, are required to follow and document adherence to site and program specific QA/QC procedures.

1.2 Environmental Data Systems

RFETS environmental data systems are a combination of individual systems developed by programs to support required environmental monitoring and reporting. Current environmental data systems are shown in Table Q-2.

Table Q-2 Current Data Systems at RFETS

Environmental Data System	Typical Data
Air Monitoring System Database	Effluent air, ambient air, meteorology
Soil Water Database	Soil, groundwater, surface water, HPGe, water levels, field parameters, flow
Ecology Database	Ecological species, soil types, sampling locations
Geographic Information System (GIS)	Spatial data
Analytical Services Toolkit/EDDPro	Laboratory analyses tracking, electronic laboratory analyses
WSRIC	Waste characterization
WEMS	Waste container tracking

Most environmental data systems have been upgraded in the last year and several are scheduled for upgrade during FY99. Additional upgrades that are anticipated include conversion to common site standard platforms and improved electronic transfer of data from the laboratory system to the individual environmental databases.

Projects that collect air, soil, ecology, and water data are required to direct electronic data to the applicable database. In this way, such data will be easily available for secondary uses, as well as available in the future, long after the original project is completed and closed out. This relieves the RFCA project manager from long-term data management requirements beyond Site-required record keeping requirements. All data entered into environmental data systems must have a location and sampling event identified.

The current configuration and platform of the SWD allows data other than just soil and groundwater to be stored (for example HPGe data have been recently included). RFCA project managers collecting waste characterization data or other types of D&D data should strongly consider storing their electronic data within SWD to ensure long term retrievability and consistent backup. Because all laboratory data are generated with an EDD and the platform and configuration of the SWD is not media specific, using SWD to store other types of data is highly cost effective and a long-term benefit to the Site closure.

1.3 Public Dissemination of Environmental Data

During FY99, the Site is required to meet RFCA Milestone M9 - "Complete information management system for integrated site-wide monitoring and environmental data by 9/30/99". This Milestone requires that data specified in the IMP be provided to regulators as requested. To support this data transfer effort, some computer system programming and program database interfaces will be developed and/or improved. This development effort (known as ISEDs or Integrated Site-wide Environmental Data Systems) will facilitate data transfer to

requesting external organizations from existing program databases. The effect on existing systems will likely be improved data transfer from the analytical services data system and possibly platform modifications to Site standards. ISEDS will not involve creation of a new data system, but rather, it will rely on improvements in data transfer among existing systems.

Meeting the milestone will also involve development and implementation of a world wide web (WWW) homepage to facilitate electronic transfer of environmental data reports to Stakeholders. The Environmental Data Dynamic Information Exchange (EDDIE) homepage will impact RFCA project managers in several ways:

- Reports submitted to regulators under the IMP will be posted on the WWW, and therefore be far more widely distributed. This could result in increased review, comment and discussion on reports and the costs associated with addressing additional issues
- All reports submitted under the IMP will be required to be produced in electronic format. Electronic copies of files must be sent to the ISEDS administrator for WWW posting. This requirement should not materially impact project budgets or schedules
- All IMP electronic data will be made available to the regulators (and possibly other stakeholders) for independent analysis. Validation and verification codes will be included in electronic files. It is therefore possible to have additional scrutiny by regulators on data analysis and subsequent closure decisions
- Reports will be easily available to Site staff and managers for their use

1.4 Additional Requirements for Soils, IDM and other Solids

1.4.1 Data transfer to SWD

To ensure the long term viability of electronic data for soils and other solids, project managers are obligated to formally transfer soil and solids data generated in conjunction with ER actions, decommissioning, and construction activities to the SWD. This includes all media, including verification soil sampling, investigation-derived materials (IDM) sampling, stockpiles, etc. Electronic data transfer is easy and convenient and can be automated by identifying the data in the analytical services toolkit (AST) system as "owner_id" = SWD. This will automatically place any electronic laboratory generated data into the site's soil database for future use.

1.4.2 Designation of No Longer Representative Samples

Project managers are required to generate the information necessary to flag old soils data that have been superseded during any RFCA action (i.e., the site has been remediated and soils have been treated and removed/replaced). The No Longer Representative flag in the SWD database will be essential to future decision making, especially during risk assessment activities.

1.4.3 Verification Soil Sampling

Any verification soil sampling collected to demonstrate the satisfaction of performance objectives must be formally transferred to SWD. Adequate information must be provided with the data to ensure that the proper location of the sample is recorded.

1.4.4 Stockpile Sampling

Where treated or untreated soil has been stockpiled and sampled prior to returning the soil to an excavated location (putback), any sample results representative of the stockpile and thus representative of the returned soils, must be placed in the SWD database.

Similarly, where treated or untreated soil has been stockpiled and sampled prior to management in a location different from the excavated location, any sample results representative of the stockpile, and thus representative of the soil at the new location, must be included in SWD with the new location information.

**FINAL RFCA
APPENDIX 4
UPDATE PAGES
FEBRUARY 26, 1999**

**ROCKY FLATS CLOSURE PROJECT
COMPLETION METRICS BASELINE**

AND

**ROCKY FLATS CLOSURE PROJECT
CRITICAL CLOSURE PATH CHART**

Rocky Flats Closure Project Completion Metrics Baseline

Key Closure Activities	FY97	FY98 Plan	FY98 Actual	FY98 Mortgage	FY99	FY00	FY01	FY02	FY03	FY04	FY05	FY06	FY07	FY08	FY09	FY10	TOTAL
SMM Shipments																	
Pile (percent of inventory)	0	100%	62%	38%	0%	0	0	0	0	0	0	0	0	0	0	0	100
and (percent of inventory)	0	14%	22%	68%	78%	0	0	0	0	0	0	0	0	0	0	0	92%
Composite Parts (percent of inventory)	0	0	0	0	0	45%	45%	10%	0	0	0	0	0	0	0	0	100%
Ship Pu Metals and Oxides (# of shipments)	0	0	0	0	0	700	1,100	500	0	0	0	0	0	0	0	0	2,300
Piece Pu Metals & Oxides in 30/3 (City Containers)	0	0	0	0	0	750	1,000	150	0	0	0	0	0	0	0	0	1,900
Drum B371 Areas	0	2	2	0	10	0	0	0	0	0	0	0	0	0	0	0	12
Drum & Removes B771 Liquid Systems	0	4	2	2	12	9	12	0	0	0	0	0	0	0	0	0	37
Residues (kg bsk)																	
Salt Category																	
Disposition Salt Residues	0	3,800	868	2,812	7,075	6,525	0	0	0	0	0	0	0	0	0	0	17,400
Asst Category																	
Repackage SS&C	0	2,700	789	1,901	600	0	0	0	0	0	0	0	0	0	0	0	3,300
Ship SS&C to SRS	0	600	0	600	1,300	2,000	0	0	0	0	0	0	0	0	0	0	3,900
Disposition Ash/Gravel/Fine	0	1,000	0	1,000	7,950	9,800	5,400	0	0	0	0	0	0	0	0	0	24,150
Composites Category																	
Disposition Wet Composites	0	3,200	0	3,200	6,500	5,000	5,000	3,700	0	0	0	0	0	0	0	0	23,400
Ship Asbestos to SRS	0	0	0	0	0	317	0	0	0	0	0	0	0	0	0	0	317
Inorganic Category																	
Dry Repackage	0	6,800	3,217	3,583	8,700	11,400	9,200	1,600	0	0	0	0	0	0	0	0	37,700
Ship Low-Level Mixed Waste for disposal (m³)	2,564	4,126	6,527	2,401	2,886	6,575	5,000	8,000	2,706	1,427	1,887	165	8,000	4,555	2,710	0	50,601
Ship Low-Level Waste for disposal (m³)	1,288	2,945	2,627	318	2,300	2,050	10,000	20,000	20,000	20,000	18,751	11,649	14,182	5,742	2,005	0	130,892
Ship TRU Waste for disposal (m³)	0	128	0	128	1,000	2,000	2,000	2,000	2,000	2,000	2,000	1,321	261	14	11	0	14,733
Non-Radiative Waste Disposal/Recycling (m³)	347	87	297	210	88	186	84	77	399	137	271	359	121	71	317	0	2,544
Ship Sanitary Waste for disposal (m³)	9,873	9,461	18,244	8,783	19,800	16,400	26,200	18,800	31,600	30,100	28,900	38,400	37,600	2,500	19,000	0	288,634
Deposition Waste Chemicals (Containers)																	
Facility Groups Completed (Container Order requirement)	2	7	10	-3	9	0	0	0	0	0	0	0	0	0	0	0	18
Waste Chemical Program (Containers)	23,850	25,432	21,842	0 (None)	4,000	0	0	0	0	0	0	0	0	0	0	0	53,342
Life Cycle Program (Containers)	0	5,000	4,891	0 (None)	5,000	5,000	5,000	5,000	5,000	5,000	5,000	5,000	5,000	5,000	1,000	500	56,500
Demolish Buildings & Facilities (# of buildings)	19	6	12	-6	9	33	20	18	14	26	107	55	143	191	75	0	716
Major Buildings																	
53,026	23,338	26,178	-2,840	8,462	91,051	138,461	138,461	108,868	249,114	208,624	397,204	655,107	689,438	588,955	224,348	0	3,495,996
Remediate Environmental Site (#)	1	1	2	1	4	1	2	2	3	4	8	20	11	6	2	0	65
Disposition of Property (#)	30,000	36,000	33,000	3,000	60,000	79,850	85,247	78,130	36,060	72,120	78,130	30,050	25,900	0	0	0	611,487
Disposition Challenged Matter (#)	2,850,400	92,000	148,105	58,105	13,300	12,500	11,700	10,900	9,900	8,300	7,500	6,700	0	0	0	0	3,023,200

Note 1: A negative FY98 mortgage means more work in a specific area was accomplished versus plan. A positive mortgage indicates less work was accomplished versus plan.

Note 2: In some cases actual quantities requiring disposition were less than planned, meaning all required work was completed and there was no carryover mortgage.

Updated: 12/12/88

Best Available Cop

305

RFCA Target Activities

FY99

- T1 Thermally stabilize 90% of the plutonium oxide generated during the year by 9/30/99.
- T2 Complete the off-site shipment of the pits by 9/30/99.
- T3 Drain 6 systems in Building 771 by 9/30/99.
- T5 Remove solid Cat I and II SNM (not holdup and composites) from Building 776/777 by 9/30/99.

FY00

- T1 Complete eU shipments.
- T2 Complete shipments of SS&C.
- T3 Complete SNM holdup removal in Building 771.
- T4 Close the Material Access Area in Building 771.
- T5 Drain mixed residue tanks to RCRA stable and remove Raschig rings in B776/777.

FY01

- T1 Complete holdup removal of areas above Safeguard Termination Limits (attractiveness Level D) in B776/777. (Does not include ducts or ventilation.)
- T2 Close the Material Access Area in B776/777.
- T3 Complete off-site shipment of fluorides.

FY02

- T1 Repackage Pu inorganic oxide and wet combustibles residues.
- T2 Complete salt stabilization.
- T3 Start off-site shipment of metal and oxide.

RFCA REGULATORY MILESTONES

FY99

M1	Either a) ship cumulative amount of 78% of 10/01/96 pond/salt inventory offsite and evacuate all waste from Tent 9 by 9/30/99, or b) the additional onsite storage for pond/salt is operational by 9/30/99.
M2	Ship 670 m ³ of TRU/TRM to WIPP by 9/30/99, assuming a January 1999 opening.
M3	Ship 1,750 cubic meters of low level waste by 9/30/99.
M4	Complete installation and operate remedial action described in decision document for Solar Pond plume (N. Walnut Creek) by 9/30/99.
M5	Complete installation and operate remedial action described in decision document for East Trenches/903 Pad/Ryan 's Pit Mound plume (S. Walnut Creek) by 9/30/99.
M7	Develop a comprehensive characterization/remediation strategy for the Industrial Area soils and ground water by 9/30/99.
M8	Complete off-site shipment by 9/30/99 for treatment and/or disposal of all T-1 waste streams not returned to T-1, and for which treatment or disposal locations are available and controlling documents are in place by 4/30/99.
M9	Complete information management system for integrated site-wide monitoring and environmental database by 9/30/99.
M10	Either a) construct and operate new facility for storage of TRU/TRM by 9/30/99, or b) by 9/30/99 demonstrate adequate storage available for TRU/TRM through 9/30/00.
M11	Complete characterization of the 903 Pad as defined in the approved Sampling Analysis Plan by 9/30/99 (with the exception of the remaining radiologic boreholes, which will be completed by 12/31/99).

FY00

M1	Ship 100% of 10/1/96 pondcrete/saltcrete inventory off-site by 5/30/00 and evacuate all wastes from Tents 10 and 11..
M2	Complete demolition to slab of Building 779 by 9/30/00.
M3	Complete demolition to slab of Building 886 by 9/30/00.
M4	Complete remediation described in decision document for Bowman's Pond.

NOTICE !

**ALL DRAWINGS
ARE LOCATED
AT THE END OF
THE DOCUMENT**

ER Ranking

Rev. 9/98

Status	Rank	HHSS Number and Name	Total Tank Contents	Total Ground Water	Total Subsurface Soil	Total Surface Soil	Total Chemical Score	ALF Score	SW Impact Score	Potential for Further Release	Professional Judgement	Total Priority Score	Exceeds Tier I AL	General Comments
C-96	1	109 Ryan's Pit		33679	2	<1	33681	10	2	3	1	60	Yes	Source removed
C-96	2	110 Trench T-3		26101	1612	<1	27713	10	2	3	1	60	Yes	Source removed
C-96	3	111.1 Trench T-4		26101	78	<1	26179	10	2	3	1	60	Yes	Source removed
SR-98	4	108 Trench T-1		11	11080	<1	11091	9	1	3	2	54	Yes	FY98 - source removed, treatment and trench fill in FY99.
C-97	5	113 Mound		19064	6	<1	19071	9	3	2	1	54	Yes	Source of Mount Plume, removed
	6	112/155 903 Pad and Lip Area		41426	1449	108	42983	10	2	2	1	40	Yes	Characterization in FY98/FY99, remediation planned for FY2001.
IAC-98	7	East Trenches Plume		26105			26105	10	3	1	1	30	Yes	Impact on surface water in the S. Walnut Creek drainage
IAC-98	8	118.1, 132 and 121 Tanks 9 & 10		1194	50000000	2325	50003521	10	1.5	2	1	30	Yes	Tank 10 source removed. Carbon Tel Plume Source
IAC-96	9	Mound Plume		19067			19067	9	3	1	1	27	Yes	Groundwater collection and treatment system in place
IAC-96	11	121/T24 T-1/24 2/125 PW Tank T-16N		3570	n	<1	3570	7	1	3	1	21	Yes	Source removed, tank foamed and stabilized
IAC-96	12	121 Tanks T-2/1-3, 122-Underground Concrete Tanks		751	<1	n	1453	7	1	3	1	21	Yes	Source removed, tank foamed and stabilized
IAC-96	13	121/T24.3 Process Waste Tank T-14		1000	<1	n	1000	6	1	3	1	21	Yes	Tank foamed and stabilized
	14	101 Solar Ponds			<1	14	2417	7	2	1	1	18	Yes	Source removed, tank foamed and stabilized
	15	Solar Ponds Plume		2403	<1		2403	7	2	1	1	14	Yes	HHRA 10.4 to 10.6, groundwater from 118.1 not used in ranking
	16	903 Pad & Ryan's Pit Plume		73365			73365	10	1	1	1	14	Yes	Plume due to NO ₃ impacts surface water in N. Walnut Creek
	17	Carbon Tetrachloride Plume (118.1)		50000000	n	n	50000000	10	1	1	1	10	Yes	No impact to surface water in the Woman Creek drainage
	18	881 Hillside Plume		9167	n	n	9167	8	1	1	1	10	Yes	HHSS 118.1 is suspected source/DNAPL present
	19	Industrial Area Plume		2615	n	n	2615	7	1	1	1	8	Yes	No impact on surface water in the Woman Creek drainage
	20	121 Tank T-29 (Tank 207)		<1	<1	4110	4125	7	1	1	1	7	Yes	No known impact on surface water
	21	PU&D Yard Plume		553	n	n	553	6	1	1	1	7	Yes	New 1995 data-PAHs in surface soil
	22	160 Rad Site Bldg 664 Parking Lot		578	n	1	579	6	1	1	1	6	Yes	Source not present
	23	158 Rad Site - B551/B554		418	n	1	419	5	1	1	1	6	Yes	Paved
	24	Building 881 Area Plume		257			257	5	1	1	1	5	no	Source may be due to UEG at B881
	25	Building 881 UBC		257	7	n	254	5	1	1	1	5	yes	No pathway known
	26	114 Present Landfill		415	<1	31	446	5	2	1	1	5	no	Compliance, presumptive remedy for closure
	27	Present Landfill Area Plume		415	n	18	415	5	2	1	1	5	yes	Process knowledge of probable influent liquids
	28	Bowman's Pond (PAC 700-1108)		n	n	<1	18	4	2	1	1	4	yes	HHRA, less than 10.6, metals
	29	111.4 SE Trenches T-7		<1	128	<1	128	4	2	1	1	4	yes	Tank foamed and stabilized, tank not breached
	30	165 Triangle Area		215	n	14	229	4	2	1	1	4	yes	
IAC-96	31	129 - Tank T-4, outside steam plant		<1	n	2	2	1	1	1	1	4	yes	
	32	121, 126.1, 126.2 Tank T-8		<1	n	<1	<1	1	1	3	1	3	no	
	33	111.8 Trench T-11		n	<1	<1	96	3	1	1	1	3	no	
	34	Building 779 UBC		96	<1	<1	96	3	1	1	1	3	no	
	35	121 Tank T-27		n	n	64	64	2	1	1	1	2	no	
	36	143 771 Outfall		n	n	59	59	2	1	1	1	2	no	
	37	176 S&W Yard		46	<1	3	49	2	1	1	1	2	no	
	38	131 Rad Site #1 - 700 Area		n	n	26	26	2	1	1	1	2	no	
	39	133.4 Ash Pit #4		n	n	4	4	1	1	1	1	2	no	
	40	133.1 Ash Pit #1		44	<1	2	46	2	1	1	1	2	no	
	41	133.2 Ash Pit #2		44	2	<1	46	2	1	1	1	2	no	
	42	133.3 Ash Pit #3		44	<1	<1	46	2	1	1	1	2	no	
	43	Old Landfill Area Plume		44	<1	<1	44	2	1	1	1	2	no	
	44	115 Original Landfill		174			174	4	1	1	1	2	no	
	45	190 Caustic Leak		172	<1	27	199	4	1	1	1	2	no	
	46	Building 123 Site (HHSS 148, 121, 123UBC, RCRA Unit 40)		12	n	<1	12	1	1	1	1	2	no	
	47	120.1 North Fiberglassing area		9	4	1	14	1	1	1	1	2	no	
	48	150.3 Rad Site Between B771 & B774		n	n	20	20	1	1	1	1	1	no	
	49	214 750-Pad pondcrete/sulphate storage		n	n	16	16	1	1	1	1	1	no	
	50	157.1 Rad Site North-Central Ave Ditch		5	n	13	13	1	1	1	1	1	no	
	51	157.2 Rad Site south		2	n	5	10	1	1	1	1	1	no	
	52	120.2 West Fiberglassing Area		n	n	6	6	1	1	1	1	1	no	

September 30, 1998

n = data not available

ER Ranking

Rev. 9/98

ER Ranking															Rev. 9/98
Status	Rank	HHSS Number and Name	Total Tank Contents	Total Ground Water	Total Subsurface Soil	Total Surface Soil	Total Chemical Score	ALF Score	SW Impact Score Multiplier	Potential for Further Release Multiplier	Professional Judgement Multiplier	Total Priority Score	Exceeds Tier 1 AL	General Comments	
	53	144 Sewer line overflow		n	n	4	4	1	1	1	1	1	no		
	54	136.2 Cooling Tower Pond East of B444		n	n	4	4	1	1	1	1	1	no		
	55	163.1 Rad Site 700 North B774		n	n	2	2	1	1	1	1	1	no		
	56	Building 440 Site		n	n	2	2	1	1	1	1	1	no		
	57	177-OU 10		n	n	6	6	1	1	1	1	1	no		
	58	196 in Old Landfill		n	n	2	2	1	1	1	1	1	no		
	59	119.1 - OU 1 - Solvent Spill Site		<1	n	2	2	1	1	1	1	1	no	Investigation done for B440 expansion	
	60	139.1 KOH, NaOH condensate tanks spill		<1	<1	<1	44	2	1	1	1	1	no	PCB hit above AL	
	61	139.2 Hydrofluoric Acid Tank spills		n	29	3	32	2	1	1	1	0.5	no	HHRA, 10E-4 to 10-6	
	62	111.2 Trench T-5		n	n	19	19	1	1	1	1	0.5	no	CAD/ROD amendment pending	
	63	153 Oil Burn Pit		n	n	19	19	1	1	1	1	0.5	no	PAHs in surface soil	
	64	164.3 Rad Site #2 800 Area, 887 Pad		<1	<1	1	1	1	1	1	1	0.5	no	PAHs in surface soil	
	65	127 Low level Rad waste leak		n	n	<1	<1	0	1	1	1	0.5	no		
	66	186 Valve Vault 11, 12 and 13		n	n	<1	<1	0	1	1	1	0.5	no		
	67	150.4 Rad Site NW of B750		n	n	<1	<1	0	1	1	1	0	no	In PA fence, eleven feet of soil removed during fence construction	
	68	159 Rad Site B559		n	n	<1	<1	0	1	1	1	0	no		
	69	111.3 SE Trenches T-6		n	n	<1	<1	0	1	1	1	0	no		
	70	111.5 SE Trenches T-8		<1	<1	n	<1	0	1	1	1	0	no		
	71	111.6 SE Trenches T-9		<1	<1	<1	<1	0	1	1	1	0	no		
	72	138 Bldg 779 Cooling Tower Blowdown		<1	<1	<1	<1	0	1	1	1	0	no		
	73	164.2 Rad Site #2, 800 Area, Bldg 886 Spill		<1	<1	<1	<1	0	1	1	1	0	no		
	74	111.7 SE Trenches T-10		<1	<1	<1	<1	0	1	1	1	0	no		
	75	137 Bldg 712/713 Cooling Tower Blowdown		n	bd	bd	<1	0	1	1	1	0	no		
	76	118.2 Solvent Spills North End of Bldg 707		n	n	n	<1	0	1	1	1	0	no		
	77	121-P08 OPWL Pipeline, 135 ft, Bldg 881		<1	n	n	0	0	1	1	1	0	no		
	78	121-P57 OPWL Pipeline, 112 ft, Bldg 122		n	n	<1	0	0	1	1	1	0	no		
	79	121-T12 Invalid tank location		n	n	n	0	0	1	1	1	0	no		
	80	121-T31 Invalid tank location		n	n	n	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	81	121-T33 Invalid tank location		n	n	n	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	82	121-T34 Invalid tank location		n	n	n	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	83	121-T35 Invalid tank location		n	n	n	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	84	175 S&W B.980 Container Storage Facility		n	n	n	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	85	182 444/453 Drum Storage Area		n	n	n	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	86	205 Sump #8 Acid Site, SE B460*		n	n	<1	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	87	207 Inactive D-386 HW Tank B374		n	n	<1	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	88	208 Inactive B444 Acid Dumpsters		n	n	<1	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	89	187 Sulfuric Acid Spill, B443		n	n	<1	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	90	134(N) Lithium Metal Destruction Site		n	n	<1	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	91	134(S) Lithium Metal Destruction Site		n	n	<1	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	92	150.6 Loading Dock		<1	<1	0	0	0	1	1	1	0	no	Evaluate using approved NAA/FA process	
	93	154 Pallet Burn Site		n	n	<1	0	0	1	1	1	0	no	Evaluate by NAA/FA process/IE B335 D&D	
	94	171 Fire Training Building 444 UBC		n	n	<1	0	0	1	1	1	0	no	Evaluate with NAA/FA process/IE B335 D&D	
	INV	Building 707 UBC		134	n	134	4	1	1	1	0.5	0	no	Removed during PA construction, verify only	
	INV	121 Old Process Waste Lines-includes:		156	n	156	4	1	2	2	16	no	Empirical data indicates free product present		
	INV	66 segments (35,000) & 22 tank units-not investigated		142	n	156	4	1	1	2	8	no	Known contaminant plume		
		123.2 Valve Vault w. of 707		1013	n	0	1	1	1	2	2	no	Many known spills		
		147.1 MAAS Area			n	1013	7	1	1	2	14	yes	HHSS 121 includes the following italicized HHSSs		
		149.1 OPWL to SEPS											Not characterized, probably highly contaminated		
													Not characterized, probably highly contaminated		
													Not characterized, probably highly contaminated		
													Not characterized, probably highly contaminated		

September 30, 1998

September 30, 1998

n = data not available

ER Ranking

Rev. 9/98

Status	Rank	ILHSS Number and Name	Total Tank Contents	Total Ground Water	Total Subsurface Soil	Total Surface Soil	Total Chemical Score	ALF Score	SW Impact Score Multiplier	Potential for Further Release Multiplier	Professional Judgement Multiplier	Total Priority Score	Exceeds Tier I AL	General Comments
	INV	1121 Old Process Waste Lines (continued)		1013	n		1013	7	1	1	2	14	yes	ILHSS 121 includes the following failed ILHSSs
		149.2 OPWL to SEPS												Not characterized, probably highly contaminated
	INV	215 Abandoned sump in 774												Not characterized, probably highly contaminated
	INV	Bldg 774 UBC (146.1, 146.2, 146.3, 146.4, 146.5, 146.6)												Tanks removed, 1971 rad. data exceeded Tier I levels
	INV	150.1 Rad Site N. of 771		n	n	n	0	0	1	1	2	0		Paved, old data exists
	INV	150.2 Rad Site W. of 771/776		n	n	<1	0	0	1	1	1	0		Paved, old data exists
	INV	117.1 (North Site)&197/Scrap Metal Storage		n	n	<1	0	0	1	1	2	0		Suspected source-known buried material PUL&D yard
	INV	161 - W. of 664		n	n	<1	0	0	1	1	2	0		Waste staging area-lack of data
	INV	117.2 Middle Site Chemical Storage		651	n	<1	651	6	1	1	1	6	yes	Source
	INV	128 Oil Burn Pit #1		<1	n	<1	0	0	1	1	1	0		Tied to Building 335 D&D Project
	INV	150.7 Rad Site S. of 778		n	n	<1	0	0	1	1	1	0		Rad Screens only
	INV	163.2 Americium Slab		n	n	<1	0	0	1	1	1	0		HPGe Survey
	INV	213 904 Pad: Pondcrete Storage		n	n	<1	0	0	1	1	1	0		Active Storage Unit, not sampled
	INV	116.1 Bldg 447, W. Loading Dock		n	n	n	0	0	1	1	1	0		
	INV	116.2 Bldg 444, S. Loading Dock		n	n	<1	0	0	1	1	1	0		
	INV	136.1 Cooling Tower Pond W. of 444		n	n	<1	0	0	1	1	1	0		
	INV	148 Waste Leaks		n	n	<1	0	0	1	1	1	0		
	INV	150.8 Rad Site S. of 779		n	n	<1	0	0	1	1	1	0		
	INV	173 Rad Site Bldg 991		n	n	<1	0	0	1	1	1	0		Spills cleaned up at time
	INV	184 Rad Site 991 Steam		n	n	<1	0	0	1	1	1	0		Spills cleaned up at time
	INV	162 - 700 Area		n	n	<1	0	0	1	1	1	0		Unconfirmed-no location found
														Spills cleaned up at time
NFA		140 Hazardous Waste Disposal Site												Spills cleaned up at time
NFA		164.1 Rad Site #2 - 800 Area		n	3	n	3	1	1	1	0.5	0.5		Unconfirmed-no location found
NFA		170, 174.1 (174a), 174.2 (174b) PUL&D Storage Areas		2	n	<1	2	1	1	1	0.5	0.5	no	Evaluated using approved NANAFA process
NFA		117.3 S Chemical Storage Site		n	n	12	12	1	1	1	0.5	0.5	no	Investigation in FY98 determined no source above Tier I present/NFA
NFA		123.1 Valve Vault #7		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		135 Bldg 337 Cooling Tower		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		147.2 Bldg 881 Conversion Activity		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		151 Fuel Oil Leak		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		156.1 Radioactive Site		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		172 Central Avenue Waste Spill		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		181 Building 334 Cargo Container Area		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		188 Acid Leak Southeast of Bldg. 374		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		191 Hydrogen Peroxide Leak		n	n	<1	0	0	1	1	1	0	no	Evaluated using approved NANAFA process
NFA		210 Bldg 980 Cargo Container		n	n	n	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		216.2 East Spray Field - OU 2		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		216.3 East Spray Field - OU 2		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		133.5 Incinerator		n	n	<1	0	0	1	1	1	0		Evaluated using approved NANAFA process
NFA		133.6 Concrete Wash Pad		n	n	<1	0	0	1	1	1	0		PPRG ratio less than 1, *2 downgradient wells
NFA		141 Sludge Dispersal Area		n	n	<1	0	0	1	1	1	0		HHRA, 10E-4 to 10-6
NFA		142.1 Pond A-1		<1	n	<1	0	0	2	1	0.5	0		HHRA, 10E-4 to 10-6
NFA		142.10 Pond C-1		n	n	<1	0	0	1	1	0.5	0		HHRA, less than 10-6
NFA		142.11 Pond C-2		n	n	<1	0	0	1	1	0.5	0		HHRA, 10E-4 to 10-6 w/pond data
NFA		142.12 Walnut and Indiana Pond		n	n	<1	0	0	1	1	0.5	0		HHRA, less than 10-6
NFA		142.2 Pond A-2		<1	<1	<1	0	0	1	1	0.5	0		HHRA, less than 10-6 includes pond & sediments
NFA		142.3 Pond A-3		n	<1	<1	0	0	1	1	0.5	0		HHRA, less than 10-6 includes pond & sediments
NFA		142.4 Pond A-4		n	<1	<1	0	0	1	1	0.5	0		Passed CDPHE screen
NFA		142.5 Pond B-1		<1	<1	<1	0	0	1	1	0.5	0		HHRA, 10E-4 to 10-6 w/pond data
NFA		142.6 Pond B-2		n	<1	<1	0	0	1	1	0.5	0		Passed CDPHE screen w/pond and sediment data
NFA		142.7 Pond B-3		n	<1	<1	0	0	1	1	1	0		HHRA, 10E-4 to 10-6 w/pond & sediment data
NFA		142.8 Pond B-4		n	<1	<1	0	0	1	1	1	0		HHRA, 10E-4 to 10-6 w/pond & sediment data

September 30, 1998

ER Ranking

Rev. 9/98

Status	Rank	IRSS Number and Name	Total Tank Contents	Total Ground Water	Total Surface Soil	Total Surface Soil	Total Chemical Score	ALF Score	SW Impact Score Multiplier	Potential for Further Release Multiplier	Professional Judgement Multiplier	Total Priority Score	Exceeds Tier I AL	General Comments
NFA		142.9 Pond B-5												
NFA		152 Fuel Oil Tank 221 Spill												Passed CDPHE screen w/ pond and sediment data
NFA		156.2 Soil Disposal Area		<1	<1	<1	0	0	1	1	1	0		Evaluated using approved NAFNA process
NFA		166.1 Landfill Trench A		<1	<1	n	0	0	1	1	1	0		HHRA, less than 10.6
NFA		166.2 Landfill Trench B		<1	<1	n	0	0	1	1	1	0		Passed CDPHE screen
NFA		166.3 Landfill Trench C		<1	<1	n	0	0	1	1	1	0		Passed CDPHE screen
NFA		167.1 N Landfill Spray Area		<1	<1	n	0	0	1	1	1	0		HHRA, less than 10.6
NFA		167.2 Landfill Pond Spray Area		<1	<1	n	0	0	1	1	1	0		Passed CDPHE screen
NFA		167.3 Landfill Pond Spray Area		<1	<1	n	0	0	1	1	1	0		Passed CDPHE screen
NFA		169 Hydrogen Peroxide Spill		n	n	<1	0	0	1	1	1	0		HHRA, less than 10.6
NFA		183 Gas Detox Facility		n	n	n	0	0	1	1	1	0		HHRA, 10E-4 to 10-6
NFA		189 Nitric Acid Tank		n	n	n	0	0	1	1	1	0		Focused HHRA, 10E-4 to 10-6
NFA		203 Inactive Hazardous Waste Storage Area		n	n	n	0	0	1	1	1	0		Evaluated using approved NAFNA process
NFA		209 Surface Disturbances		n	n	n	0	0	1	1	1	0		Evaluated using approved NAFNA process
NFA		216.1 East Spray Field - OU 6		<1	<1	<1	0	0	1	1	1	0		Evaluated using approved NAFNA process
NFA		F167.3 Former S. Spray Field		n	<1	<1	0	0	1	1	1	0		Evaluated using approved NAFNA process
C-97		102 Oil Sludge Pit		n	<1	<1	0	0	1	1	1	0		Passed CDPHE screen
C-97		103 Chemical Burial		<1	<1	<1	0	0	1	1	1	0		Passed CDPHE screen
C-97		104 Liquid Dumping		<1	<1	<1	0	0	1	1	1	0		Passed CDPHE screen
C-97		105.1 W Out-of-Service Fuel Tank		<1	<1	<1	<1	0	2	1	1	0		HHRA, less than 10.6
C-97		105.2 E Out-of-Service Fuel Tank		<1	10	<1	<1	0	2	1	1	0		HHRA, less than 10.6
C-97		106 Outfall		<1	<1	<1	0	4	2	1	1	4	yes	HHRA, less than 10.6
C-97		107 Hillside Oil Leak		<1	<1	<1	0	0	2	1	1	0		HHRA, less than 10.6
C-97		119.2 Solvent Spill Site		<1	<1	<1	0	0	2	1	1	0		HHRA, less than 10.6
C-97		130 800 Area Rad Site #1		<1	<1	<1	0	0	2	1	1	0		HHRA, less than 10.6
C-97		145 Sanitary Waste Line Leak		<1	<1	<1	9	1	2	1	1	0		HHRA, less than 10.6
C-97		199 Offsite Land Surface		<1	<1	<1	34	2	2	1	1	0		HHRA, less than 10.6
C-97		200 Great Western Reservoir		<1	<1	<1	0	0	2	1	1	2	yes	HHRA, less than 10.6
C-97		201 Standley Lake		n	<1	<1	0	0	2	1	1	0		HHRA, less than 10.6
C-97		202 Mower Reservoir		<1	<1	<1	0	0	1	1	1	0		HHRA, 10E-4 to 10.6 No groundwater issues
C-95		168 West Spray Field		<1	<1	<1	0	0	1	1	1	0		HHRA, 10E-4 to 10.6, plus sediment samples
C-95		178 B881 Drum Storage, Rm. 165		<1	<1	<1	0	0	1	1	1	0		Passed CDPHE screen
C-95		179 B865 Drum Storage, Rm. 145		190	<1	<1	0	0	1	1	1	0		Passed CDPHE screen
C-95		180 B883 Drum Storage, Rm. 104		n	n	n	0	0	1	1	1	2	no	Passed CDPHE screen
C-95		204 Original Uranium Chip Roaster		n	n	n	0	0	1	1	1	0		BCRA Clean Closure CAD/ROD complete
C-95		211 B881 Drum Storage #26-R211		n	n	n	0	0	1	1	1	0		BCRA Clean Closure CAD/ROD complete
C-95		217 B881 Granite Treatment - #32		n	n	n	0	0	1	1	1	0		BCRA Clean Closure CAD/ROD complete
C-94		185 Solvent Spill		n	n	n	0	0	1	1	1	0		BCRA Clean Closure CAD/ROD complete
C-94		192 Pipeline		n	n	n	0	0	1	1	1	0		No source found CAD/ROD Complete
C-94		193 Steam Condensate		n	n	n	0	0	1	1	1	0		No source found CAD/ROD Complete
C-94		194 Solvent Spill		3	n	n	3	1	1	1	1	0		No source found CAD/ROD Complete
C-94		195 Nickel Carbonyl Disposal		n	n	n	0	0	1	1	1	0		No source found CAD/ROD Complete
C-96		Closure complete		n	n	n	0	0	1	1	1	0		Evaluated using approved NAFNA process
IAC-96		Interim Action Complete												No source found CAD/ROD Complete
NFA		Evaluated and recommended for NAFNA status												No source found CAD/ROD Complete
INV		Needs further investigation												No source found CAD/ROD Complete
LOW		Low priority												

September 30, 1998